

Development Review A	APPLICATION
For Office Use On	lv
STAFF CONTACT TOM SOPPE PROJECT NO(S). DR-1	209 /WA -12-01
NON-REFUNDABLE FEE(S) REFUNDABLE DEPOSIT(S)	D TOTAL 3450-
Type of Review (Please check all that apply):	
Annexation (ANX) Appeal and Review (AP) * Conditional Use (CUP) X Design Review (DR) /050/300 Easement Vacation Extraterritorial Ext. of Utilities Final Plat or Plan (FP) Flood Management Area Historic Review Legislative Plan or Change Lot Line Adjustment (LLA) */** Minor Partition (MIP) (Preliminary Pla Non-Conforming Lots, Uses & Struct Planned Unit Development (PUD) Pre-Application Conference (PA) */* Street Vacation Hillside Protection & Erosion Control Home Occupation, Pre-Application, Sidewalk Use, Sign Review Permit, a different or additional application forms, available on the City website o	tures X Water Resource Area Protection/Single Lot (WAP) Water Resource Area Protection/Wetland (WAP) Willamette & Tualatin River Greenway (WRG) Zone Change
Site Location/Address:	Assessor's Map No.: 2S 2E 30BC
5933 HOLMES STREET	Tax Lot(s): 2300
WEST LINN, OR 97068	Total Land Area: 3.3 acres
Brief Description of Proposal: ENCLOSE TRASH AREA, INSTA	LL TRASH COMPACTOR, STABILIZE STREAM
BANK OF BOLTON CREEK ON THE BOLTON PRIMARY SCHO	
BECE	IVE)
Applicant Name: TIM WOODLEY	Rhone: 503-673-7995
Address: 2755 SW BORLAND RD	Email: woodleyt@wlwv.k12.or.us
City State Zip: TUALATIN, OR 97062 MAR 2 8	2012
Owner Name (required): WEST LINN WILSONVILLE	Phone: 503-673-7995
	BUILDING Email woodleyt@wlwv.k12.or.us
City State Zip: TUALATIN, OR 97062 INT.	A Province and A Prov
Consultant Name: KEITH LIDEN, PARSONS BRINCKERHOFF	Phone: 503-478-2348
Address: 400 SW 6 TH AVE., SUITE 802	Email: liden@pbworld.com
City State Zip: PORTLAND OR 97204	
 All application fees are non-refundable (excluding deposit). Any overruns The owner/applicant or their representative should be present at all public A denial or approval may be reversed on appeal. No permit will be in effect Three (3) complete hard-copy sets (single sided) of application materials on One (1) complete set of digital application materials must also be submitted in the sets of plans are required in application please submit only two sets No CD required / ** Only one hard-copy set needed 	t hearings. It until the appeal period has expired. must be submitted with this application. ted on CD in PDF format.
The undersigned property owner(s) hereby authorizes the filing of this application, and	authorizes on site review by authorized staff. I hereby agree to
comply with all code requirements applicable to my application. Acceptance of this app	plication does not infer a complete submittal. All amendments
to the Community Development Code and to other regulations adopted after the applic Approved applications and/subsequent development is not vested under the provisions	
tim V. Minulan 2.27.12 Km	KMMM 2.27.12
Applicant's signature Date Own	eu's signature (required) Date
	.

BO Development_Review_Application 2012.Docx

PARSONS BRINCKERHOFF

400 SW Sixth Avenue Suite 802 Portland, OR 97204

Transmittal

Tel: (503) 274-8772 Fax: (503) 274-1412

to:	Tom S	oppe			from: Keith Liden					
City of West Linn Planning Department					date: 3.27.12					
	22500	Salamo Road			project: Bolton	Primary School DR I				
	West L	inn, OR 97068			file number:					
via:		for your:		the fol	lowing:					
🗆 mail		□ Information	/use	🗆 shoj	o drawings	□ change order	🗆 spec	cifications		
□ messe	enger	X approval			of letter	□ plans	\Box CD			
□ fed-ex		□ review/comment		🗆 🗆 print	\Box prints \Box set		X appli	X application packages		
			Sig	gned application	form		1	3.26.12		
			CE	of all materials			1	-		
			Ap	plication packet	including:		3	2.26.12		
			1.	Narrative						
			2.	Plan sheets (fu BO-C1, BO-C2 C400, C500, C	, C101, C102, (
			3.	Plan sheets (1 ⁻	1x17 reductions	5)				
				Attachment B - Attachment B -	- Wetland Delin	eation Report,				

.....

Comments:

Fee to be paid by contacting the District – Amy Berger 503.673.7195

Thank you!

Keith Liden, 503.224.4066 / liden@pbworld.com

copy to:

BOLTON PRIMARY SCHOOL Class I Design Review and Water Resources Area Permit March 26, 2012

APPLICATION SUMMARY

Class I Design Review and Water Resources Area Permit for bank and slope stabilization and erosion prevention project at Bolton Primary School.

GENERAL INFORMATION

Location

5933 Holmes St. (2S 2E Section 30 BC, Tax Lot 2300). Its location is shown in Figure 1.

Comprehensive Plan and Zoning Designations

The Comprehensive Plan designation is Low Density.

Consistent with the Comprehensive Plan, the property is zoned Single Family Residential Detached (R10).

Applicant and Owner

Tim Woodley, Director of Operations West Linn-Wilsonville School District 2755 SW Borland Road Tualatin, OR 97062 Phone: 503-673-7976 E-mail: woodleyt@wlwv.K12.or.us

Applicant's Representatives

Keith Liden, AICP Parsons Brinckerhoff 400 S. W. 6th Avenue, Suite 802 Portland, OR 97204 Phone: 503-478-2348 Fax: 503-274-1412 E-mail: <u>liden@pbworld.com</u> Nancy Hubbard Hubbard & Associates PO Box 702 Tualatin, OR 97062 Phone: 503-819-7505 E-mail: hubbard.associates@frontier.com

Plan Sheets and Supplemental Information

C100	Cover Sheet
A2.00	Site Plan
BO-C1	Compactor Site Plan
BO-C2	Compactor Notes and Specifications
C101	General Notes
C102	Erosion Control Notes
C200	Existing Conditions and Demolition Plan
C300	Site, Storm Drainage, Grading and Erosion Control Plan
C400	Cross Sections and Storm Drainage Outfall Profile
C500	Details
C501	Details
L501	Landscape Restoration Plan
Attachment A	Wetland Delineation for the Bolton Primary School Stream Bank Stabilization Project
Attachment B	Compactor Information

Figure 1: Aerial Photo



Source: Metro

BACKGROUND INFORMATION

Site Description

The site is developed with a primary school, driveway, parking, and play fields as shown in Figure 1 and Sheet A2.00. The entire site is approximately 3.3 acres. In addition to the school building, a play area is located on the north side of the school. Parking is located on the north and south sides of the building.

Bolton Creek runs along the northern edge of the site. It is designated as a significant riparian corridor. The creek bank is quite steep, and it is eroding to the point of jeopardizing the adjacent play area to the south. The Creek ranges in width from 4 to 10 feet and averages less than 1 foot in depth. During field work completed by Pacific Habitat Services, Inc. (PHS) on December 29, 2011 the limits of ordinary high water (OHW) were noted as visually apparent based on topographic break, obvious water marks, and changes in vegetation. PHS flagged the OHW for subsequent inclusion on the topographic survey. A wetland delineation was conducted by Pacific Habitat Services, Inc., and no wetlands were identified (Attachment A).

Surrounding Area Description

The zoning designations and current land use of the surrounding area are summarized in Table 1.

Properties in the Vicinity	Zone Designation	Land Use			
Subject Property 2S 2E Section 30 BC, Tax Lot 2300 (3.3 acre school site owned by school district)	R10	Primary school building, ancillary facilities, and parking			
Surrounding Properties					
North	R10	Single family residences			
South	R10	Single family residences			
East	R10	Hammerle Park (City of West			
		Linn)			
West	R10	Single family residences			

Table 1 Land Use Summary

PROPOSED IMPROVEMENTS

Trash and Recycling Area

The district would like to replace the existing trash dumpster with a trash compactor to allow less frequent trash pick-up (Sheet A2.00). The new compactor will be screened from view by a March 26, 2012 Bolton Primary School - DR I new fence and is located in the vicinity of the existing trash and recycle containers on the south side of the school. The compactor, which will only be operated intermittently between the hours of 7 am to 7 pm, will be able to satisfy the city's noise standards as documented in Attachment B. Additionally, the compactor will reduce the trash pick-up frequency from weekly to once a month. The trash compactor is not permanently affixed to the ground, and as such is not subject to the side yard setback requirements. The permanent aspects of the installation, the electrical power hook-up will be within the required property line setbacks. The fence will be on or within the property line.

Stream Bank Stabilization

The bank of Bolton Creek is proposed to be stabilized to end the erosion and creek sedimentation that is occurring. The existing slopes along Bolton Creek are steep, in some areas vertical and unsafe. Sloughing of soil and localized slides are apparent and have created an unstable condition at the west top of slope that interfaces with the school playground. The grades will be altered significantly beginning from approximately 2 feet above ordinary high water line (the delineated wetland). From there the slope will be graded at a two horizontal to one vertical (2:1) slope up to the top of the slope or within 5 feet of playground existing perimeter fence where a Gabion retaining wall will be installed (Sheet C300). This grade is significantly flatter than the existing slope and will require encroachment onto a portion of the playground. At the top of the modified slope a fence will be replaced. A portion of the regraded slope will require a gabion retaining structure to allow for a stable 2:1 slope. The gabion structure will extend approximately 69-feet along the top and with the highest point (6-feet) located in the center of the alignment, then tapering to no height at the north and south ends of the structure (Sheet C300). This project will not modify the Bolton Creek alignment or include any work within the stream channel. A total area of 6,184 square feet will be affected and subject to the city's mitigation requirement in CDC 32.

The slope stabilization work will also include stabilization of an existing drainage ditch, which has been created over time by storm water from two existing storm pipe outfalls (15- and 6- inch storm water pipes). This ditch is not armored, causing erosion. These two existing storm drainage lines are proposed to terminate in a new, concrete manhole, which will then have a new 15-inch storm water pipe extending approximately 20 feet toward the creek, where it will daylight into the newly re-graded and armored ditch. The horizontal alignment of the existing drainage ditch will not be changed, and the re-grading will stabilize the slope and prevent long-term erosion. The new bank will consist of a series of buried gabion, intended to spread the storm water pipe outfall to Bolton Creek (see civil plan sheets). The existing chain link fence along the top of the bank will be replaced by a new 6-foot high chain link fence.

This work will required the removal of 10 deciduous trees ranging in diameter from 7 to 22 inches (Sheet C200). On February 28, 2012 a site visit was conducted with City Arborist Mike Perkins. It was determined there are no heritage trees on site, and the existing trees can be removed within the limits of the project. The re-graded area will be replanted with an appropriate combination of native ground covers, shrubs, and trees (Sheet L501). The new plantings will be hand watered while they are getting established.

DESIGN REVIEW CRITERIA

Section 55.090(A) refers to specific portions of Section 55.100 that apply to Class I Design Review applications. The applicable portions of Section 55.100 are addressed below, including sections identified by the city staff.

Section 55.090(B) states that adequate public facilities must be available. This criterion is satisfied because the school is currently served by a full range of public utilities and streets.

Section 55.100 contains the applicable approval standards for a Class I Design Review. At the conclusion of the preapplication conference, the planning staff determined that the application must meet the following criteria in Chapter 55:

- 55.100(A)(2) Accessory structures
- 55.100(A)(6) Fences
- 55.100(A)(8) Access, egress, and circulation (truck maneuvering)
- 55.100(C) Compatibility, buffering, and screening
- 55.100(D)(4) Noise
- 55.100(I)(5) Solid waste storage areas
- 55.100 (J)(3) Lighting of solid waste area
- 55.100(J)(8) Utility fencing

These criteria are addressed below.

A. The provisions of the following chapters shall be met:

2. Chapter 34 - Accessory Structures

CDC 34.040 states that noise-producing accessory uses and structures must comply with the applicable building setback requirements. The only permanent portion of the trash compactor installation is the new electrical power source and it is proposed to be located in compliance with the side yard set back requirement of 7.5 feet.

6. Chapter 44 - Fences

The proposed fencing satisfies the city's fence provisions because it will be a maximum of 6 feet high in a rear yard. Because the fencing is not near a street intersection or driveway, it does not pose any conflict with the clear vision area requirements in Chapter 42.

8. Chapter 48 - Access, Egress, and Circulation

The trash compactor will be located in the general vicinity currently used for the trash and recycling bins. The district has coordinated the location and accessibility with the waste disposal company. No other vehicular or pedestrian access will be affected by this proposal.

C. Compatibility Between Adjoining Uses, Buffering and Screening

The school has been a fixture in the neighborhood for many years, and it has maintained a compatible relationship with surrounding neighbors. The school operation will not be

changed by either the trash compactor or the stream bank stabilization. The compactor will not generate noise above the city's noise standards, and it will offer the advantage of fewer garbage truck visits and the associated vehicle noise.

D.4. Privacy and Noise

School activities and associated noise is compatible with the surrounding neighborhood. Building entrances, vehicle circulation, and outdoor activity areas will remain in their current location. Proposed screening of the trash and recycling area will improve the situation for neighbors nearby, and the compactor will not generate noise that exceeds city standards.

I.5. Public Facilities

The general location of the solid waste and recycling area will not be changed, and in fact, less area will be required for the trash and recycling because of the new trash compactor. Additionally, the new compactor will be screened with new fencing.

J.3. Lighting of Solid Waste Area

As noted above, new compactor will be in the same general location as the existing solid waste and recycling area and the existing site lighting will remain consistent with previous city approvals.

J.8. Utility Fencing

As noted above, the proposed fence surrounding the trash and recycling area shall be 6-feet high, meeting the maximum height standards of 8 feet.

WATER RESOURCES AREA PERMIT CRITERIA

At the conclusion of the preapplication conference, the city staff determined that the Water Resource Area permit application must meet the following criteria in Chapter 32 – Water Resource Area Protection of the Community Development Code (CDC):

- 32.040 Application
- 32.050 Approval Criteria
- 32.060 Site Plan
- 32.070 Mitigation Plan
- 32.080 Revegetation Plan Requirements

Section 32.040 Application

This section is satisfied because the plan sheet package and the report in Attachment A provide all of the information and narrative responses required by this section.

Section 32.050 Approval Criteria

This section contains a number of requirements relating to the protection of water resources.

- **A.** This section is satisfied because the required information and evaluation is provided as part of this application, including analysis and design by a registered civil engineer.
- B. This section calls for maintaining existing natural drainageways. In this case, the district proposes to minimize encroachment on the southern bank sloping down to Bolton Creek This project does not propose modifying the Bolton Creek alignment or conducting any work within the creek channel. The proposed slope stabilization is intended to eliminate the erosion and siltation created over time by storm water from an existing storm pipe outfall. The bank will be re-graded to stabilize the slope and prevent long term erosion. The new bank will consist of a series of buried gabions intended to spread the storm water flow and riprap to armor the slope. This drainage way will extend from the new storm water pipe outfall to Bolton Creek.
- C. The existing condition is currently causing environmental damage due to the erosion, bank instability, and presence of non-native vegetation. The proposed bank stabilization and replanting will create a stable situation with greatly reduced erosion and the re-introduction of appropriate native vegetation in this area.
- D. The district is committed to protect the water resource areas on the site into the future. It will work with the city staff during final design and permitting to accomplish this. The retention of the chain link fence along the southern boundary of the creek area will further protect the natural resource quality of this area. Buildings and structures on the site (existing including fencing and play equipment) will not be moved closer to the creek, and therefore, existing setbacks shall be maintained.
- E. This section describes how the protected water resource area setback and transition areas are determined. As noted in D. above, a chain link fence and some play equipment are within the setback areas for the creek. These structures shall remain in their current locations.
- *F.* This criterion does not apply because no roads, driveways, or utility crossings are proposed over Bolton Creek.
- **G.** The district will work with the city to maximize the protection of the resource as intended by this criterion, which calls for chain link fencing (or approved equivalent). Due to the steep slopes, installing an anchored chain link construction fence perpendicular to the slope from the top of the bank to the bottom of the bank is not recommended. Orange construction fencing is proposed as an alternative. As noted above, a permanent 6-foot chain link fence shall be installed at the top of bank after work is completed.
- *H.* This criterion does not apply because no new paved surfaces are proposed.
- I. All plans have been developed by experienced civil engineers and environmental scientists

with the goal of maintaining and enhancing the water and natural resources on the site. The design of these elements will meet the city of West Linn and Oregon Stated Department of Environment Quality requirements.

- J. All erosion control measures prescribed by the city shall be followed at all times. Design of these elements will meet the city of West Linn and Oregon Stated Department. of Environment Quality requirements.
- *K.* Due to the nature of this project and the amount of disturbance, a re-vegetation plan is required. The re-vegetation plan proposed by the district will provide the combination of ground cover, shrubs, and trees required by this section and CDC 32.080 (addressed below).
- *L.* As noted above, the existing chain link fence and play equipment are proposed to remain in their current location and no new structures are proposed within the setback area.
- **M**. This criterion does not apply because storm water treatment facilities are not proposed.
- **N.** This criterion is not applicable because opening a covered or piped drainage is not proposed.
- **O.** These criteria do not apply because no new buildings or building remodeling is proposed.
- P. This criterion is not applicable because all relevant storm drainage channels have been identified.

Section 32.060 Site Plan

This section is satisfied because the plan sheet package and the report in Attachment A provide all of the information required by this section.

Section 32.070 Mitigation Plan

This section contains a number of requirements relating to the mitigation of potential adverse impacts on water resource areas.

- A. This section is satisfied because the proposed stream bank restoration is proposed to correct existing erosion and bank instability issues rather than accommodate development. The erosion and bank instability problems extend along virtually the entire south bank of the creek. In addition, non-native vegetation covers much of the area. This restoration work includes the minimum area necessary, and it avoids any work in the stream channel. The problems are clearly identified in the wetland delineation report (Attachment A), and the restoration will improve the current poor condition of the stream area.
- **B**. As noted, this project is not designed to accommodate new development. The current condition of the creek is related to urbanization that has occurred over many years, and this project, as shown in the plan sheets, will provide appropriate mitigation. As noted in the application, the district and its contractors will be responsible for the work and assuring its

proper completion.

- **C.** Because of the small size of the school site and lack of available space for mitigation, off-site mitigation is proposed. Conversations with city staff concur with this approach, and preliminary coordination has begun between the district and parks department.
- **D.** This criterion is not applicable because no wetland areas are involved.
- *E.* With the off-site mitigation proposed to occur on city park property, permanent protection will be provided.

Section 32.080 Revegetation Plan Requirements

This section contains a number of requirements relating to revegetating water resource areas. These standards were followed when the landscaping and planting plans were developed for this application.

- **A**. Temporary irrigation shall be provided as noted in the Landscape Restoration Plan (Sheet L501).
- **B**. As shown in the Landscape Restoration Plan, the non-native plants shall be removed in the area of work and replaced with native vegetation.
- **C.** Replacement trees and shrubs shall meet the minimum size standards of this section, as shown on Sheet L501.
- **D.** The replacement trees and shrubs are proposed to be planted with spacing and density required by this section (Sheet L501).
- *E.* The proposed landscaping plan contains a variety of trees and shrubs, which comply with the requirements in this section.
- *F.* The district shall provide the necessary assurances for plant survival as required by the city.

CONCLUSION

The proposed compactor and stream bank restoration satisfy all of the relevant criteria as demonstrated above. The restoration work will result in an environmentally improved segment of Bolton Creek.

ATTACHMENT A Wetland Delineation Report

Wetland Delineation for the Bolton Primary School Streambank Stabilization Project in West Linn, Oregon

(Township 2 South, Range 2 East, Section 30BC, portion of Tax Lot 2300)

Prepared for

West Linn-Wilsonville School District Attn: Tim Woodley

Prepared by

Pacific Habitat Services, Inc. Wilsonville, Oregon 97070 (503) 570-0800 (503) 570-0855 FAX



Wetland Delineation for the Bolton Primary School Streambank Stabilization Project in West Linn, Oregon

(Township 2 South, Range 2 East, Section 30BC, portion of Tax Lot 2300)

Prepared for

West Linn-Wilsonville School District Attn: Tim Woodley 2755 SW Borland Road Tualatin, Oregon 97062

Prepared by

Caroline Rim Amy Hawkins John van Staveren **Pacific Habitat Services, Inc.** 9450 SW Commerce Circle, Suite 180 Wilsonville, Oregon 97070 (503) 570-0855 FAX PHS Project Number: 4938

February 8, 2012

TABLE OF CONTENTS

I.	INT	RODUCTION	1							
II.	RES	ULTS AND DISCUSSION	1							
	A.	Landscape Setting and Land Use	1							
	B.	Site Alterations								
	C.	Precipitation Data and Analysis	2							
	D.	Methods								
	E.	Description of all Wetlands and Other Non-Wetland Waters	3							
	F.	Deviation from LWI	3							
	G.	Mapping Method	3							
	H.	Additional Information								
	I.	Results and Conclusions	3							
	J.	Required Disclaimer	4							
III.	REF	TERENCES	4							
APP	END	IX A: Figures								
	Figu	re 1: Vicinity Map (USGS)								
	Figure 1: Vicinity Map (USGS) Figure 2: Tax Lot Map									

Figure 3: Local Wetland Inventory Map

Site Photos

Recent Aerial Photograph

Wetland Delineation Map

Wetland Delineation Data Sheets

Wetland Definitions, Methodology (client only)

Figure 4: Soil Survey Map

Figure 5: Figure 6:

APPENDIX B:

APPENDIX C:

APPENDIX D:

Page

I. INTRODUCTION

Pacific Habitat Services, Inc. (PHS) has delineated the limits of potentially jurisdictional waters of the state/US for the Bolton Primary School streambank stabilization project in West Linn, Oregon (Township 2 South, Range 2 East, Section 30BC, Clackamas County, portion of Tax Lot 2300).

This report presents the results of PHS's wetland delineation within the study area. Figures, including a map depicting the location of wetlands within the study area, are located in Appendix A. Data sheets documenting on-site conditions are provided in Appendix B. Ground-level photos of the site are located in Appendix C. A discussion of the wetland delineation methodology (for the client) is provided in Appendix D.

II. RESULTS AND DISCUSSION

A. Landscape Setting and Land Use

The study area is located in the eastern portion of the City of West Linn, Oregon, approximately ½ mile west of the confluence of the Willamette River and the Clackamas River. The study area is located along Bolton Creek, a perennial tributary of the Willamette River. Bolton Primary School is located at 5933 Holmes Street, West Linn, Oregon 97068, and the creek is situated within a steep ravine that is located along the north side of the Bolton Primary School playground.

Bolton Creek enters the northwestern corner of the property and flows in an eastwardly direction, eventually flowing off-site through the northeastern portion of the site. The creek is narrow and shallow. Steep slopes rise above the streambanks along the north and south sides of the creek. The slope along the south bank of the creek, immediately downslope of the north edge of the playground, is quite unstable, which is evident by the presence of a recent landslide in this area. Near the east end of the creek, a seep located along the south slope joins the creek.

The riparian overstory includes red alder (*Alnus rubra*), big-leaf maple (*Acer macrophyllum*), Douglas fir (*Pseudotsuga menziesii*), and Oregon white oak (*Quercus garryana*). The understory primarily consists of English ivy (*Hedera helix*), which extends from the top of slope down to the edge of the creek. Also present within the understory are Himalayan blackberry (*Rubus discolor*), evergreen blackberry (*Rubus laciniatus*), Pacific dewberry (*Rubus ursinus*), and sword fern (*Polystichum munitum*).

Within the study area, there is one stream, Bolton Creek, and a seep flowing into the southeast side of the creek. No wetlands were identified. The delineated features are discussed in more detail in Section E.

B. Site Alterations

PHS did not observe any fill or other alterations that would have affected the location of wetlands/waters within the study area.

C. Precipitation Data and Analysis

Precipitation data recorded in Portland on December 29, 2011, was 0.69 inches. Total precipitation for the two weeks prior to the site visit was 1.36 inches. Total observed precipitation for the water-year (October 1, 2011 through December 29, 2011) was 10.77 inches, which is approximately 22 percent less than normal (National Weather Service, October 2011 through December 2011).

Table 1 compares the average monthly precipitation to the observed monthly precipitation, as well as to the normal precipitation range, as identified in the NRCS WETS Table for the City of Portland. As shown in Table 1, observed precipitation was below normal in September and October, and above normal in November. However, in October and November, the observed precipitation was within the normal range, and only slightly below in September. Although precipitation contributes to site hydrology, it is not a dominant hydrologic influence on the site. Therefore, it is PHS's best professional judgment (BPJ) that precipitation did not significantly affect the hydrologic conditions observed during the wetland delineation field work and that "normal circumstances" were present at that time.

Table 1:Comparison of Average and Observed Precipitation in Portland for Three Full
Months Prior to the Wetland Delineation Field Work

	A	30% Chanc	e Will Have	Observed	Percent of Normal	
Month	Average Precipitation*	Less Than Average*	More Than Average*	Observed Precipitation**		
September	1.65	0.65	2.06	0.63	43	
October	2.88	1.57	3.52	2.14	71	
November	5.61	3.72	6.73	6.57	117	

*Source: NRCS WETS Table

****Source: National Weather Service**

D. Methods

PHS delineated the limits of the wetlands on the site based on the presence of wetland hydrology, hydric soils, and hydrophytic vegetation, in accordance with the Routine On-site Determination, as described in the *Corps of Engineers Wetland Delineation Manual, Wetlands Research Program Technical Report Y-87-1* ("The 1987 Manual") and the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region.*

PHS's delineation and data collection was completed on December 29, 2011. The limits of ordinary high water (OHW) along Bolton Creek and the hillside seep were based on topographic break, obvious water marks, and changes in vegetation.

E. Description of all Wetlands and Other Non-Wetland Waters

PHS identified the limits of Bolton Creek and an adjoining hillside seep within the study area. Approximately 1,183 square feet (0.03 acre) of Bolton Creek and the adjoining seep are located within the study area. No potentially jurisdictional wetlands were identified. A description of the delineated features is provided below.

Bolton Creek

The creek ranges in width from approximately 4 to 10 feet, and averages less than 1 foot deep. The Cowardin class for the creek is Riverine Lower Perennial Unconsolidated Bottom Permanently Flooded (R2UBH), and the HGM class is Riverine Flow Through (RFT). The limits of OHW were delineated using indicators such as topographic break, water marks, and changes in vegetation.

<u>Seep</u>

The seep is relatively narrow, approximately 3 to 4 feet wide, and has a defined bed and bank. It extends upslope along the south side of the creek. A 15-inch concrete stormwater outfall pipe is located at the upper end of the seep. A 6-inch concrete stormwater outfall pipe is located further upslope but not connected to the seep. No water was observed flowing out of either pipe during the site visit. Situated into the slope at the upper end of the seep is a small hollow, approximately 3 feet high, 4 feet long, and 3 to 4 feet deep. Subsurface flow was visibly entering the hollow and flowing into the seep. The Cowardin class for the seep is Riverine Intermittent Unconsolidated Bottom Saturated/Semipermanent/Seasonal (R4UBY), and the HGM class is Headwater Slope (SH).

F. Deviation from LWI

The Local Wetland Inventory (LWI) map for the City of West Linn has mapped Bolton Creek as being present within the study area; no wetlands were mapped. The LWI mapping is consistent with PHS's finding's in the field.

G. Mapping Method

PHS flagged the OHW boundary of the creek and the seep with blue surveyor's tape. Data point locations were flagged with lime green surveyor's tape. These flags were subsequently survey-located by Compass Engineering. The estimated accuracy of the survey is sub-centimeter.

H. Additional Information

Bolton Creek is not designated as Essential Salmonid Habitat (ESH).

I. Results and Conclusions

PHS identified Bolton Creek and an adjoining hillside seep within the study area. The total area of potentially jurisdictional waters of the State/US is 1,183 square feet (0.03 acre) within the project area.

J. Required Disclaimer

This report documents the investigation, best professional judgment and conclusions of the investigators. It is correct and complete to the best of our knowledge. It should be considered a Preliminary Jurisdictional Determination of wetlands and other waters and used at your own risk unless it has been reviewed and approved in writing by the Oregon Department of State Lands in accordance with OAR 141-090-0005 through 141-090-0055.


III. REFERENCES

- Adamus, P.R. and D. Field. 2001 Guidebook for Hydrogeomorphic (HGM)-based Assessment of Oregon Wetland and Riparian Sites. Willamette Valley Ecoregion, Riverine Impounding and Slopes/Flats Subclasses. Oregon Division of State Lands, Salem, OR.
- Hitchcock, CL and A. Cronquist. 1973. *Flora of the Pacific Northwest: An Illustrated manual*. University of Washington Press.
- Munsell Color, 2000. Munsell Soil Color Charts. Gretag-Macbeth, New Windsor, New York.
- MyTopo.Com. 2012. U.S. Geological Survey, Oregon City, Oregon, topographical quadrangle.
- National Resource Conservation Service. Portland WETS table for Multnomah County. <u>http://www.wcc.nrcs.usda.gov/ftpref/support/climate/wetlands/or/41051.txt</u>
- National Weather Service Climate Data. <u>http://www.weather.gov/climate/index.php?wfo=pqr</u>
- Oregon Department of State Lands, 2009. Oregon Revised Statutes (ORS), *Chapter 196 Columbia River Gorge; Ocean Resource Planning; Wetlands; Removal and Fill.* Section 196.800 Definitions for ORS 196.600 196.905.
- ORMAP tax maps. http://www.ormap.org/
- Portland Maps, 2010 photograph.
- Reed, Porter B., Jr., 1988. National List of Plant Species That Occur in Wetlands: Northwest (Region 9). Prepared by the US Fish and Wildlife Service, St. Petersburg, FL. NERC-88/18.37.
- U.S. Army Corps of Engineers, Environmental Laboratory, 1987. Corps of Engineers Wetland Delineation Manual. Technical Report Y-87-1.
- US Army Corps of Engineers, Environmental Laboratory, 2010. *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region (Version 2.0).*
- U.S. Department of Agriculture. *Web Soil Survey*, 2012. Online Mapping for Clackamas County, Oregon.
- Winterbrook Community Resource Planning. Local Wetland Inventory for West Linn, Oregon, January 2005.

Appendix A

Figures








Location and general topography for the Bolton Primary School streambank stabilization project in West Linn, Oregon (USGS Oregon City, OR quadrangle. Courtesy of MyTopo.com, 2012).


figure 1


-Pacific Habitat Services, Inc. -











Appendix B

Wetland Determination Data Sheets



WE.				NRM - West	orn Mountains	. Vallo	ve and Coas	PHS #	4938
	olton Primary S			DATA FORM - Western Mountains, Valley Dity/County: Clackamas				-	9/2011
	Bolton Primary		Only/Obumy.			State:	Sampling Date:	Sampling Point:	
Investigator(s):	C. Rim / A. Ha		Section To	wnship, Range:			30, T 2 South, R		•
Landform (hillslope, terra					ncave, convex, none):		none	Slope (%):	
Subregion (LRR):	LRF		Lat:	45.370			122.618725	Datum:	DD
	LNP			43.370				Datum.	00
Soil Map Unit Name:				N		NI Classifi		· · · · · · · · · · · · · · · · · · ·	
Are climatic/hydrologic c			•	Yes	<u>X</u>	No		in in Remarks)	
are vegetation		· • • –	significantly dist		Are "Normal Circun		,	<u>Y</u>	
re vegetation	Soil or H	lydrology	naturally proble	matic? If needed	d, explain any answers	s in Rema	rks.)		
SUMMARY OF FI	NDINGS – Att	ach site ma	ap showing sa	mpling poin	t locations, tran	nsects,	important feat	ures, etc.	
ydrophytic Vegetation		N					-		
vdric Soil Present?	Yes	N		Is Sampled An a Wetlar		Yes	Ν	lo X	
/etland Hydrology Pres	sent? Yes	N		a wella	nur				
Remarks:									
emarks.									
EGETATION - U	se scientific n	ames of pla	ants.						
		absolute	Dominant	Indicator	Dominance Test	t worksh	neet:		
		% cover	Species?	Status					
ree Stratum (plot siz	ze: 30)			Number of Dominar	nt Species			
Acer macrophyl	lum	30	<u> </u>	FACU	That are OBL, FAC	W, or FAC		1	(A)
Quercus garrya	na	10		UPL					
Alnus rubra		20	<u> </u>	FAC	Total Number of Do	ominant			
1					Species Across All	Strata:		7	(B)
		60	= Total Cover						
apling/Shrub Stratum	(plot size: 5)			Percent of Dominan	nt Species			
Acer macrophyl	lum	20	X	FACU	That are OBL, FAC	W, or FA	D: .	14%	(A/B)
Rubus discolor		10	<u> </u>	FACU					
3					Prevalence Inde		sheet:		
1					Total % Cover of		Multiply by:		
5					OBL Species		x 1 =	0	
		30	= Total Cover		FACW species FAC Species		x 2 = x 3 =	0	
erb Stratum (plot siz	ze: 5)			FACU Species		x 4 =	0	
Polystichum mu		30	х	FACU	UPL Species		x 5 =	0	
2					Column Totals	;	0 (A)	0	(B)
3									
L					Prevalence In	dex =B/A	= #[DIV/0!	
i									
j					Hydrophytic Ve	getation	Indicators:		
						1- R	apid Test for Hydro	phytic Vegetatio	n
3							ominance Test is >		
		30	= Total Cover				evalence Index is ≤		unnerting
oody Vine Stratum	(plot size:)					orphological Adapta i in Remarks or on a		
<i>Hedera helix</i>	(pi0t 5126.	/ 	x	UPL			l in Remarks of on a /etland Non-Vascul	•	1
2 Rubus ursinus		10	<u> </u>	FACU			plematic Hydrophyti		xplain)
		50	= Total Cover		¹ Indicators of hydric			e .	• •
					disturbed or problem		, · ····3) ··		-
	o				Hydrophytic		N		
6 Bare Ground in Herb	Stratum				Vegetation Present?		Yes	No	X
Remarks:					r resent (

SOIL			PHS #	493	38			Samp	ling Point:	1
Profile Descr	iption: (Describe to	the depth	needed to docume	ent the indic	cator or co	nfirm the abser	ce of indicators.)			
Depth	Matrix			Redox	Features	0				
(Inches)	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²	Texture		Remarks	<u> </u>
0-12	10YR 3/2	100					Silt loam	gravelly		
12-16	10YR 4/2	90	7.5YR 4/6	10	С	М	Silt			
¹ Type: C=Con	centration, D=Deplet	ion, RM=R	educed Matrix, CS=	Covered or	Coated Sar	nd Grains.		² Location: PL=P	ore Lining, M=Ma	atrix.
Hydric Soil	Indicators: (App	licable to	all LRRs, unles	s otherwis	se noted.)		Indic	ators for Probl	ematic Hydric	Soils ³ :
	Histosol (A1)			s	andy Redo	x (S5)		20	cm Muck (A10)	
	Histic Epipedon (A2)	1		s	Stripped Mat	trix (S6)		Re	ed Parent Material	(TF2)
	Black Histic (A3)			L	oamy Muck	ky Mineral (F1) (e	except MLRA 1)	Ve	ery Shallow Dark S	Surface (TF12)
	Hydrogen Sulfide (A	4)		L	oamy Gleye	ed Matrix (F2)		Ot	her (explain in Re	marks)
	Depleted Below Darl	k Surface (A11)	C	Depleted Ma	atrix (F3)				
	Thick Dark Surface (A12)		F	Redox Dark	Surface (F6)				
	Sandy Mucky Minera	al (S1)		C	Depleted Da	rk Surface (F7)			drophytic vegetati t be present, unles	
	Sandy Gleyed Matrix	(S4)		٩	Redox Depre	essions (F8)		nyarology mao	problematic.	
Restrictive	Layer (if present)):								
Type:		N	one							
Depth (inche	s):						Hydric Soil Pres	sent? Yes	N	o X
HYDROLC	DGY									
Wetland Hy	drology Indicato	rs:								
Primary Indi	icators (minimum o	of one req	uired; check all th					Secondary In	idicators (2 or n	nore required)
	Surface Water (A1)				Vater staine , 2, 4A, and	ed Leaves (B9) (Except MLRA		ater stained Leave Except MLRA1, 2	
	High Water Table (A	2)							-	-
	Saturation (A3)				Salt Crust (B	,			ainage Patterns (I	
	Water Marks (B1)					rtebrates (B13)			y-Season Water 1	
	Sediment Deposits (Drift Deposits (B3)	B2)				ulfide Odor (C1)				n Aerial Imagery (CS
	Algal Mat or Crust (E	84)				Reduced Iron (0	g Living Roots (C3)		eomorphic Position nallow Aquitard (D	
	Iron Deposits (B5)	, , ,				Reduction in Plo			ac-Neutral Test (D	
	Surface Soil Cracks	(B6)				tressed Plants (. ,		aised Ant Mounds	
	Inundation Visible or		agery (B7)			in in Remarks)		Fr	ost-Heave Humm	ocks (D7)
	Sparsely Vegetated									
Field Obser	rvations:									
Surface Wate	r Present? Yes		No X	Depth (i	inches):					
Water Table F			No X	Depth (i			Wetland Hyd	rology Presen	t?	
Saturation Pre	esent? Yes		No X	Depth (i			-	Yes	N	o X
(includes capilla	ry fringe)									
Describe Reco None	orded Data (stream g	auge, mon	itoring well, aerial pl	hotos, previc	ous inspection	ons), if available	c			
Remarks:										

	WETLAND	DETE	RMINATIO	ON DATA FO	RM - West	ern Mountains, Va	allevs, and Coa	PHS# st Region	4938
Project/Site: Bolton Primary School				D DETERMINATION DATA FORM - Western Mountains, Valleys imary School City/County: Clackamas Sa					/2011
pplicant/Owner:	Bolton Pr	imary So	chool			State:	OR	Sampling Point:	2
vestigator(s):	C. Rim	n / A. Hav	vkins	Section, To	wnship, Range:	s	Sec 30, T 2 South,	R 2 East	
andform (hillslope	e, terrace, etc.:)		terrac	e	Local relief (cor	ncave, convex, none):	none	Slope (%):	
bregion (LRR):		LRR		Lat:	45.3707	753 Long:	122.618725	Datum:	DD
oil Map Unit Nam	ne:		Alol	— ha silt loam		NWI Cla	assification:		
re climatic/hydrol		on the site	typical for this	s time of year?	Yes	X No	(if no, exp	lain in Remarks)	
re vegetation	0			significantly dist	urbed?	Are "Normal Circumstan		,	
e vegetation						, explain any answers in R	,		
<u> </u>		_ ,					,		
UMMARY O	F FINDINGS	6 – Atta	ch site ma	p showing sa	mpling poin	t locations, transec	ts, important fea	tures, etc.	
ydrophytic Veget	tation Present?	Yes	No	o <u>X</u>	Is Sampled Ar	ea within			
ydric Soil Presen	nt?	Yes	X No	0	a Wetlar			No X	
etland Hydrology	y Present?	Yes	No	o <u>X</u>					
emarks:									
EGETATION	N - Use scier	ntific na							
			absolute	Dominant	Indicator	Dominance Test wor	rksheet:		
ee Stratum (p	olot size:	5)	% cover	Species?	Status	Number of Dominant Spe			
Acer macro		/	30	X	FACU	That are OBL, FACW, or		0 (A)
								(, ,
						Total Number of Dominar	nt		
						Species Across All Strata	a:	3 (B)
			30	= Total Cover					
apling/Shrub Stra	atum (plot size	e:)			Percent of Dominant Spe	ecies		
	, i		_^			That are OBL, FACW, or		0% (A/B)
						Prevalence Index We	orksheet:		
						Total % Cover of	Multiply b	/:	
. <u> </u>						OBL Species	x 1 =	0	
			0	= Total Cover		FACW species	x 2 =	0	
erb Stratum (p	olot size:	5)				FAC Species FACU Species	x 3 = x 4 =	0	
Polystichur		/	20	X	FACU	UPL Species	x 5 =	0	
						Column Totals	0 (A)	0 (B)
3							()	`	,
•						Prevalence Index =	B/A =	DIV/0!	
						Hydrophytic Vegetat	tion Indicators:		
							1- Rapid Test for Hyd	rophytic Vegetation	,
							2- Dominance Test is		
			20	= Total Cover			3-Prevalence Index is 4-Morphological Adap		unnorting
oody Vine Stratu	um (plot size:	5)				data in Remarks or or		
Hedera heli			-′ 80	x	UPL		5- Wetland Non-Vasc		
							Problematic Hydrophy		plain)
			80	= Total Cover		¹ Indicators of hydric soil a			
						disturbed or problematic.			
						Hydrophytic			
Bare Ground in	Herb Stratum					Vegetation	Yes	No	Х

SOIL			PHS #	49	38			Sampling Point:	2	
Profile Descr	iption: (Describe to	the depth	needed to docume	ent the ind	icator or co	nfirm the abse	nce of indicators.)			
Depth	Matrix				x Features	12				
(Inches)	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²	Texture	Remarks		
0-6	10YR 2/2	100					Sandy Clay Loam			
6-9	10YR 2/2 4N	<u>80</u> 10	7.5YR 3/4	10	C	M	Silty Clay Loam	medium		
9-16	4N	85	10YR 4/6	15	С	М	Silt Loam	medium		
¹ Type: C=Con	ncentration, D=Deple	tion, RM=R	educed Matrix, CS=	Covered o	r Coated Sar	nd Grains.		² Location: PL=Pore Lining, M=Ma	trix.	
-	Indicators: (App							tors for Problematic Hydric		
-	Histosol (A1)				Sandy Redo			2 cm Muck (A10)		
	Histic Epipedon (A2)			Stripped Mat			Red Parent Material	(TF2)	
	Black Histic (A3)	, ,				(v Mineral (F1)	except MLRA 1)	Very Shallow Dark S		
	Hydrogen Sulfide (A	4)				ed Matrix (F2)	,	Other (explain in Re		
	Depleted Below Dar		A11)						narks)	
			ATT)		Depleted Ma					
	Thick Dark Surface	. ,				Surface (F6)		³ Indicators of hydrophytic vegetation	on and wetland	
	Sandy Mucky Miner					rk Surface (F7)		hydrology must be present, unles		
	Sandy Gleyed Matri	x (S4)			Redox Depre	essions (F8)	-	problematic.		
Restrictive	Layer (if present):								
Type:		N	one							
Depth (inche	s):				_		Hydric Soil Pres	ent? Yes X No)	
HYDROLC	DGY									
Wetland Hy	drology Indicato	rs:								
Primary Indi	icators (minimum	of one req	uired; check all th	nat apply)	1			Secondary Indicators (2 or m	ore required)	
-	Surface Water (A1)					ed Leaves (B9) (Except MLRA	Water stained Leave	es (B9)	
	High Water Table (A	2)			1, 2, 4A, and	d 4B)		(Except MLRA1, 2,	4A, and 4B)	
	Saturation (A3)				Salt Crust (E	311)		Drainage Patterns (E	310)	
	Water Marks (B1)				Aquatic Inve	rtebrates (B13)		Dry-Season Water T	able (C2)	
	Sediment Deposits (B2)			Hydrogen Su	ulfide Odor (C1)	1	Saturation Visible or	Aerial Imagery (C9)	
	Drift Deposits (B3)				Oxidized Rh	izospheres alon	g Living Roots (C3)	Geomorphic Position	ı (D2)	
	Algal Mat or Crust (I	34)			Presence of	Reduced Iron (C4)	Shallow Aquitard (D3	3)	
	Iron Deposits (B5)				Recent Iron	Reduction in Ple	owed Soils (C6)	Fac-Neutral Test (D	5)	
	Surface Soil Cracks	(B6)			Stunted or S	stressed Plants	nts (D1) (LRR A) Raised Ant Mounds (D6) (LRR A			
	Inundation Visible of	n Aerial Ima	agery (B7)		Other (Expla	ain in Remarks)		Frost-Heave Hummo	ocks (D7)	
	Sparsely Vegetated	Concave S	urface (B8)							
Field Obser	rvations:									
Surface Wate	r Present? Yes		No X	Depth	(inches):					
Water Table F			No X	-	(inches):		Wetland Hvdr	ology Present?		
Saturation Pre			No X	-	(inches):			Yes No	o X	
(includes capilla	ry fringe)				· · · -					
Describe Reco None	orded Data (stream g	jauge, mon	itoring well, aerial pl	notos, prev	ious inspecti	ons), if available	2:			
Remarks:										
I										

Appendix C

Site Photos





Photos for the Bolton Primary School streambank stabilization project in West Linn, Oregon. Photos taken on 12/29/2011.

—Pacific Habitat Services, Inc. –

HS.



Photo C:

Upper end of hillside seep. Left: 15-inch concrete cylinder pipe (CCP). Right: "hollow" within hillside, behind blue flagging tape on right.

4938


Photo D: 6-inch CCP upslope of the hillside seep.



1/27/2012

Photos for the Bolton Primary School streambank stabilization project in West Linn, Oregon. Photos taken on 12/29/2011.

–Pacific Habitat Services, Inc. -



Landslide along south slope. View to southwest.

1/27/2012

Photos for the Bolton Primary School streambank stabilization project in West Linn, Oregon. Photos taken on 12/29/2011.

–Pacific Habitat Services, Inc. -

4938

Photo F



Photo G:

Landslide along south slope. View to east.

Photo H: Bolton Creek. View to

NW / upstream.



1/27/2012

4938

Photos for the Bolton Primary School streambank stabilization project in West Linn, Oregon. Photos taken on 12/29/2011.

—Pacific Habitat Services, Inc. –

Appendix D

Wetland Definitions, Methodology



WATERS OF THE STATE AND WETLAND DEFINITION AND CRITERIA

Regulatory Jurisdiction

Wetlands and water resources in Oregon are regulated by the Oregon Department of State Lands (DSL) under the Removal-Fill Law (ORS 196.800-196.990) and by the U.S. Army Corps of Engineers (COE) through Section 404 of the Clean Water Act.

The primary source documents for wetland delineations within Oregon is the *Corps of Engineers Wetlands Delineation Manual, Technical Report Y-87-1* (Environmental Laboratory 1987) and the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region (Version 2.0)* (U.S. Army Corps of Engineers, 2010), which are required by both DSL and COE.

Waters of This State and Wetland Definition

Waters of This State are defined as "all natural waterways, all tidal and non-tidal bays, intermittent streams, constantly flowing streams, lakes, wetlands, that portion of the Pacific Ocean that is in the boundaries of this state, all other navigable and nonnavigable bodies of water in this state and those portions of the ocean shore ..." (DSL, 2009).

Wetlands are defined as "those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions" (DSL 2009).

Wetland Criteria

Based on the above definition, three major factors characterize a wetland: hydrology, substrate, and biota.

Wetland Hydrology

Wetland hydrology is related to duration of saturation, frequency of saturation, and critical depth of saturation. The 1987 manual defines wetland hydrology as inundation or saturation within a major portion of the root zone (usually above 12 inches), typically for at least 12.5% of the growing season. The wetland hydrology criterion can be met, however, if saturation within the major portion of the root zone is present for only 5% of the growing season, depending on other evidence.

The growing season is defined as the portion of the year when soil temperatures at 12.0 inches below the soil surface are higher than biological zero (41 degrees Fahrenheit, 5 degrees Celsius), but also allows approximation from frost-free days, based on air temperature. The growing season for any given site or location is determined from US Natural Resources Conservation Service, (formerly Soil Conservation Service) data and information.

Wetland hydrologic indicators include the following: visual observation of inundation or saturation, watermarks, drift lines, sediment deposits, and/or oxidized rhizospheres with living roots. Oxidized rhizospheres are defined as yellowish-red zones around the roots and rhizomes of some plants that grow in frequently saturated soils. Other indicators of hydrology, including algal mats or crust, iron deposits, surface soil cracks, sparsely vegetated concave surface, salt crust, aquatic invertebrates, hydrogen sulfide odor, reduced iron, iron reduction in tilled soils, and stunted or stressed plants can also be used to determine the presence of wetland hydrology.

Wetland Substrate (Soils)

Most wetlands are characterized by hydric soils. Hydric soils are those that are ponded, flooded, or saturated for long enough during the growing season to develop anaerobic conditions. Periodic saturation of soils causes alternation of reduced and oxidized conditions, which leads to the formation of redoximorphic features (gleying and mottling). Mineral hydric soils will be either gleyed or will have bright mottles and/or low matrix chroma. The redoximorphic feature known as gley is a result of greatly reduced soil conditions, which result in a characteristic grayish, bluish or greenish soil color. The term mottling is used to describe areas of contrasting color within a soil matrix. The soil matrix is the portion of the soil layer that has the predominant color. Soils that have brightly colored mottles and a low matrix chroma are indicative of a fluctuating water table.

Hydric soil indicators include organic content of greater than 50% by volume, and/or presence of redoximorphic features and dark soil matrix, as determined by the use of a Munsell Soil Color Chart. This chart establishes the chroma, value and hue of soils based on comparison with color chips. Mineral hydric soil must meet one of the 16 definitions for hydric soil indicators, or be classified as a "problem soil" in the Interim Regional Supplement.

Wetland Biota (Vegetation)

Wetland biota is defined as hydrophytic vegetation. A hydrophyte is a plant species that is capable of growing in substrates that are periodically deficient in oxygen as a result of saturated soil conditions. The U.S. Fish and Wildlife Service, in the *National List of Plant Species that Occur in Wetlands*, has established five basic groups of vegetation based on their frequency of occurrence in wetlands. These categories, referred to as the "wetland indicator status", are as follows: obligate wetland plants (OBL), facultative wetland (FACW), facultative (FAC), facultative upland (FACU), and obligate upland (UPL). Table 1 gives a definition of the plant indicator codes.

Table 1. Description of Wetland Plant Indicator Status Codes

Indicator	
Code	Status
OBL	Obligate wetland. Estimated to occur almost exclusively in wetlands (>99%)
FACW	Facultative wetland. Estimated to occur 67-99% of the time in wetlands.
FAC	Facultative. Occur equally in wetlands and non-wetlands (34-66%).
FACU	Facultative upland. Usually occur in non-wetlands (67-99%).
UPL	Obligate upland. Estimated to occur almost exclusively in non-wetlands (>99%). If a species is not assigned to one of the four groups described above it is assumed to be obligate upland.
NI	Has not yet received a wetland indicator status, but is probably not obligate upland.

Observations of hydrology, soils, and vegetation, were made using the "Routine On-site" delineation method as defined in the 1987 manual and the Interim Regional Supplement for areas that were not currently in agricultural production. One-foot diameter soil pits were excavated to 20 inches and soil profiles were examined for hydric soil and wetland hydrology field indicators. In addition, a visual absolute-cover estimate of the dominant species of the plant community was performed using soil pit locations as a center of reference. Dominant plant species are based on estimates of absolute cover for herbaceous, and shrub species within a 5-foot radius of the sample point, and basal area cover for tree and woody vine species within a 30 foot radius of the sample point. Plant species in each vegetative layer, which are estimated at less than 20% of the total cover, are not considered dominant. The wetland indicator status is then used to determine if there is an overall dominance (greater than 50%) of wetland or upland plant species. If less than 50% of the dominant species are hydrophytic, then the prevalence index may be used to determine if the subdominant species are hydrophytic. If the prevalence index is less than or equal to three, hydrophytic vegetation criterion is met.

During data collection, the soil profiles were examined for hydric soil and wetland hydrology field indicators. Plant species and cover were recorded. Data was recorded on standard data sheets, which contain the information specified in the 1987 Corps Manual and the Interim Regional Supplement.

ATTACHMENT B Compactor Information

RJ-88SC Self Contained Compactor



[Specifications | Literature | Operational & Steel Options]

Marathon's **RJ-88SC Self-Contained Compactor/ Containers** are ideal for waste with high liquid content and for applications where space is limited. Each RJ-88 series compactors store liquid and controls insect and odor problems.

RJ-250SC Features:

The RJ-88SC is ideal for...

Shopping Centers

Supermarkets

Restaurants

Hotels

Inflight Kitchens

Hospitals and institutions

Components are selected for longevity and minimum maintenance, with special attention given to the selection of highly sensitive components. Stress engineering provides the optimum degree of structural integrity. Only the best materials are used. The highest standards of quality are observe in the manufacturing process. That's why you'll find Marathon Compactors "packing trash" long after other makes have failed!

The **RJ-88 SC**'s smaller size makes it excellent for restaurant and fast food applications. They normally fit easily in waste corrals for an attractive and convenient installation at minimum installation cost.

With standard double end pick-up, the unit can be loaded for hauling from either end. This is especially useful if installed perpendicular to a dock (Packer End pick-up option does not include front ground rollers).

The RJ-88 SC uses a **Remote Power Pack** that remains on-site while the selfcontained compactor container is taken to the landfill.

Factory testing to assure leakproof construction.



The RJ-250SC uses a Remote Power Pack that remains on-site while the selfcontained compactor container is taken to the landfill.



Also See the RJ-88 HT. The RJ-88 HT features a Hydraulic Tailgate and is well suited for security chute-fed and dock-fed applications where maneuvering space for the collection vehicle is limited.

The RJ-88 Series Self-Contains can be used with a hopper to double or triple your loading capacity!

They are equally easy to load from ground or dock level and can be continuously fed while the unit is cycling!

Total odor and pest control via Marathon's Ozone Odor Control option

Easy and fast installation! Installation costs are cut by half over conventional compaction systems.

Fire hose connection provided on each unit.

RJ-88C Compactors can be customized with a variety of loading arrangements to suit your specific needs.



Marathon's RJ-88SC Self Contained Compactor is UL Listed!

Features & Benefits of Marathon's Self-Contained Wet Waste Compaction Equipment:

Marathon's **CYCON Life-Xtender**[®] **Cyclic Control System:** eliminates troublesome limit and pressure cycle control switches. It also reduces trash removal cost by producing superior payloads and dramatically improving cold weather performance.

Marathon's compactors meet all of ANSI and OSHA standards.

Each unit is *UL Listed* to assure quality and maintains the highest industry standards (does not apply to GreenBuilt).

Standard **double end pick-up** (except HT models) which allows the unit to be loaded for hauling from either end. This is especially useful if the self-contained unit is perpendicular to a dock.

Through-the-wall feed chutes offer convenience to employees that reduces labor cost and improves security.

Specifications:

RJ-88 SC Self-Contained



The **Qwik Clean Tank**® funnels any liquid seepage during compaction into an enclosed area underneath the charge box floor. The liquid is automatically discharged at the disposal site, in effect

flushing the container and the area behind the ram.



Rear door retains wet waste effectively with its patented "**Double-Hinge**" and custom designed "**P**" **Seal**.



The innovative **"Bubble Gate"** adds a cubic yard to the container capacity. Its curved shape also produces superior compaction ratios.

Dimension	A *	В	С	D	E	Weight		
15 cu yds	43"	30 1/2"	70"	187"	89"	7200 lbs.		
	1092mm	777mm	1778mm	4750mm	2261mm	3265 kg.		
20 cu yds	43"	30 1/2"	70"	222"	89"	7600 lbs.		
	1092mm	777mm	1778mm	5639mm	2261mm	3447 kg.		
24 cu yds	43"	30 1/2"	70"	256"	89"	8000 lbs.		
	1092mm	777mm	1778mm	6502mm	2261mm	3628 kg.		
		Cha	rge Box Cap	acity				
[Mfr's. Rating]			1.0 cy		.76 m ³			
[WASTEC Rating]			0.70 cy		.54 m ³			
Clear Top Opening	Clear Top Opening			W	775mm x 1219	mm		
		Per	formance D	ata:				
Cycle Time			44 sec		44 sec			
Total Normal Force			36,600 lb		162 kN	162 kN		
Total Maximum Force			43,100 lb		192 kN	192 kN		
Normal Ram Face Press	ure		34.7 psi		239 kPa	239 kPa		
Maximum Ram Face Pre	essure		40.8 psi		281 kPa	281 kPa		
Ram Penetration			6Ó		152 mm	152 mm		
		Elec	trical Equipr	nent				
Electric Motor 3/60/230-	-460		5 hp		3.7 kW			
Electric Control Voltage			120 VAC		120 VAC			
Panel Box Assembly UL	Listed							
All Circuits Fused Key O	perated							
3 Push Button Station S	tart/Stop/Reverse	2						
		Hyd	raulic Equipi	ment				
Hydraulic Pump			6 gpm		23 L/min			
Normal Pressure			1700 psi		117 bar			
Maximum Pressure			2000 psi		138 bar			
Cylinder Bore			2 @ 4" each		102 mm	102 mm		
Cylinder Rod			2 @ 2.5"		64 mm			

RJ-88SC Specifications

Optional Features:

TrashMinder[®]



The optional **TrashMinder**[®] is the most advanced method for reporting and measuring container fullness as well as for managing user access and billing. **Get More Details.**

The StreamLine[®] Option



allows excess liquid to be drained from the container reducing net payload weight and significantly reducing hauling costs! Liquid is routed to four interconnected 4" drain

Qwik Clean Door®



The innovative Qwik Clean Door provides access to the area behind the ram of self-contained compactors. It allows for quick, easy cleaning and other routine

maintenance without having to unbolt panels or break welds. The Qwik Clean Door features our Auto-Relatch to hold the door closed while the door is being ratcheted and our patented "P" Seal for a tight, leak proof seal.

Pictures on this page are illustrative only. Specifications are subject to change without notice to accommodate improvements to the equipment. Certified in compliance with ANSI Regulation

outlets located at each corner of the StreamLine unit. Connection can be made to a hose, piping, or pump.

See how the StreamLine System works.

Cart Dumpers




Your Self-Contained can be fitted with various configurations of cart dumper systems. Other options include: multi-cycle timer, dual controls, ozone odor control system, security chutes, hoppers,

and many much more.

Z245.2, all OSHA standards, and certified under WASTEC's Stationary Compactor Certification Program. Products must be used with safe practice and in accordance with said regulations and standards.

Top of Page



NOT TO SCALE **PROJECT LOCATION:**

BOLTON PRIMARY SCHOOL 5933 SW HOLMES STREET

WEST LINN, OR 97068-2773

DEVELOPER:

WEST LINN-WILSONVILLE SCHOOL DISTRICT #3JT CONTACT: 22210 SW STAFFORD RD TUALATIN, OREGON 97062 PHONE: (503) 673-7000 FAX: (503) 673-7001

ENGINEERING FIRMS:

GHD CONTACT: DON WHITEHEAD, P.E. 15575 SW SEQUOIA PARKWAY, SUITE 140 PORTLAND, OR 97224 PHONE: (503) 226-3921 FAX: (503) 226-3926

PERMITTEE'S SITE INSPECTOR:

NAME: PATRICK TORTORA, P.E. WINZLER & KELLY 15575 SW SEQUOIA PARKWAY, SUITE 140 PORTLAND, OR 97224 PHONE: (503) 226-3921 FAX: (503) 226-3926

EXPERIENCE: PAT TORTORA HAS OVER 18 YEARS EXPERIENCE WITH EARTHWORK PROJECTS INSTALLING, INSPECTING, AND MAINTAINING EROSION CONTROL MEASURES DURING CONSTRUCTION.

		((
						Reuse of Documents
						This document and the ideas and designs incorporated
						herein, as an instrument of professional service, is the
						property of GHD Inc. and shall not be reused in whole or
						in part for any other project without GHD Inc.'s written
						authorization. © GHD Inc. 2012
-	-	-			-	
			Job	Project		
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Manager	Director	Date	

Plot Date: 22 March 2012 - 4:28 PM

NARRATIVE DESCRIPTIONS:

EXISTING SITE CONDITIONS

• EXISTING DEGRADED SLOPE.

DEVELOPED CONDITIONS

• NEW STABILIZED SLOPE.

NATURE OF CONSTRUCTION ACTIVITY AND ESTIMATED TIME TABLE

• TOPSOIL REMOVAL / EXCAVATION: (JUNE – JULY 2012) • TOPSOIL PLACEMENT: (JULY – AUGUST 2012) • FINAL STABILIZATION: (AUGUST 2012)


TOTAL SITE AREA = APPROX 3.3 ACRES

TOTAL DISTURBED AREA = 6,184 SF

SITE SOIL CLASSIFICATION

RECEIVING WATER BODIES

LOCAL DRAINAGE PUBLIC STORM SYSTEM IN PUBLIC RIGHT-OF-WAY WHICH DRAINS TO BOLTON CREEK.



WEST LINN - WILSONVILLE **SCHOOL DISTRICT BOLTON PRIMARY SCHOOL STREAM BANK SLIDE REPAIR**



0	
	→
Ϋ	
——×—	
-xxx	-x—

 ∇

VICINITY MAP

NOT TO SCALE

TOTAL SEEP/SWALE AREA FILLED = 114 SF

• ALOHA SILT LOAM 3 TO 6 PERCENT SLOPES.

PROPERTY DESCRIPTION:

TAX LOT 2300 TAX MAP 22E30BC IN THE SOUTHWEST ONE QUARTER OF THE NORTH WEST ONE QUARTER OF SECTION 30, TOWNSHIP 2 SOUTH, RANGE 2 EAST, W. M., CITY OF WEST LINN, CLACKAMAS COUNTY, OREGON

DRAWING LIST:

SHEET INDEX:						
C100	TITLE SHEET					
C101	GENERAL NOTES					
C102	EROSION CONTROL NOTES					
C200	EXISTING CONDITIONS AND DEMOLITION PLAN					
C300	SITE, STORM DRAINAGE, GRADING AND EROSION CONTROL					
C400	CROSS SECTIONS & STORM DRAINAGE OUTFALL PROFILE					
C500	DETAILS					
C501	DETAILS					
L501	LANDSCAPE RESTORATION PLAN					

	Drawn	КРТ	Designer PRT			WILSONVILLE SCHOOL D	ISTRICT
	Drafting Check		Design DMW Check			NK REMEDIATION	
	Approved (Project	Director)			TITLESHEE 11456-11012	-	
*	Date Scale	03/06/12 AS SHOWN	This Drawing shall not be used for Construction unless Signed	Original Size		C100	Sht of
			and Sealed For Construction		2 annig 1101		Rev:



15575 SW Sequoia Parkway Suite 140 Portland Oregon 97224 USA T 1 503 226 3921 F 1 503 226 3926 W www.ghd.com

Cad File No: O:\11456 - WLWSD (West Linn-Wilsonville School District)\11456-11012 WLWSD Bolton Primary School\06-CAD\Sheets\11456-11012_C100 COVER.dwg

CIVIL ABBREVIATIONS

OLS	AB AC ACP	ANCHOR BOLT ASPHALTIC CONCRETE ASBESTOS CONCRETE PIPE	NIC NO NOM NTS
CATCH BASIN	BLDG BOT	BUILDING BOTTOM OF TRENCH	OC
CURB INLET	BOC BOS	BOTTOM OF CONCRETE BOTTOM OF SUMP	OH OW
MANHOLE	CA	COMPRESSED AIR	PD
DIRECTION OF FLOW	CB CJ	CATCH BASIN CONSTRUCTION JOINT	erf Piv
HANDICAPPED RAMP	CI CIP	CURB INLET CAST IRON PIPE	POC PVC
HYDRANT	CMP CND	CORRUGATED METAL PIPE CONDUIT	PVMT PW
WATER VALVE	CO CONC CR	CLEANOUT CONCRETE CONDENSATE RETURN	R
FENCING	DIA Ø	DIAMETER	RCP RIM
EROSION CONTROL FENCING	DIA Ø DIP DS DW	DUCTILE IRON PIPE DOWNSPOUTS DRYWELL	RR S SAN
THRUST BLOCK	DWG	DRAWING	SB SD
	E ELEV ELEC	ELECTRICAL	SS STM
	EXIST FA FD FF FH FW G	EXISTING FIRE ALARM FOUNDATION DRAIN FINISH FLOOR FIRE HYDRANT FIRE WATER GUTTER	TB TBM TC TEL TOB TOC TOG TOP TYP
	GR GV	GRADE GATE VALVE	UGND UNO
	HB HDPE HH HPG HC HYD	HOSE BIBB HIGH DENSITY POLYETHYLENE HAND HOLE HIGH PRESSURE GAS HANDICAPPED HYDRANT	VCP VT VV
	IE IRR	INVERT ELEVATION IRRIGATION	WTR WV WWF
	L LP	LENGTH LIGHT POLE	XFMR
	MAX MH MIN	MAXIMUM MANHOLE MINIMUM	

ON CENTER OVERHEAD OIL/WATER SEPARATC POLYDRAIN PERFORATED STORM DRAI OST INDICTOR VALVE OINT OF CONNECTION OLYVINYL CHLORIDE PAVEMENT POTABLE WATER radius REINFORCED CONCRETE PIPE RIM ELEVATION RAILROAD SLOPE SANITARY SPLASH BLOCK STORM DRAIN SANITARY SEWER STEAM THRUST BLOCK TEMPORARY BENCH MARK TOP OF CURB TELEPHONE TOP OF BERM TOP OF CONCRETE TOP OF GRATE TOP OF PIPE TYPICAL UNDERGROUND UNLESS NOTED OTHERWISE VITRIFIED CLAY PIPE VENT VALVE VAULT WATER METER WATER

NOT IN CONTRACT


NUMBER NOMINAL NOT TO SCALE


WATER VALVE WELDED WIRE FABRIC TRANSFORMER

PRELIMINARY


Plotted by: Keith Tolle












CONTRUCTION NOTES

- 1 SAVE AND PROTECT EXISTING SIDEWALK. 2 SAVE AND PROTECT EXISTING FENCE. 3 SAVE AND PROTECT EXISTING STORM DRAINAGE PIPE. 4 SAVE AND PROTECT EXISTING TREE. 5 SAVE AND PROTECT EXISTING BUILDING AND OVERHANG. 6 SAVE AND PROTECT EXISTING ASPHALT PAVEMENT. 7 SAWCUT STRAIGHT EDGE IN ASPHALT TO CONSTRUCT PAD.
- 8 INSTALL 8.5'Lx14'Wx6" THICK CONCRETE PAD ON COMPACTED GRAVEL SUBGRADE. SLOPE CONCRETE PAD TOWARD ACCESS AS SHOWN, MAX. SLOPE 2%. – FOR COMPACTOR UNIT.
- 9 INSTALL 5'Lx3'Wx6" THICK CONCRETE PAD ON COMPACTED GRAVEL SUBGRADE. SLOPE CONCRETE PAD TOWARD ACCESS AS SHOWN, MAX. SLOPE 2%. - FOR ELECTRICAL CONTROL UNIT.
- 10 INSTALL 6' BLACK VINYL COATED CHAIN LINK FENCE AROUND COMPACTOR PAD AS SHOWN. PROVIDE "SIGHT OBSCURING" BLACK VINYL SLATS.
- 11 PROVIDE 16' WIDE GATE OPENING, WITH TWO 8' WIDE GATES. BLACK VINYL COATED CHAIN LINK FENCE AROUND COMPACTOR PAD AS SHOWN. PROVIDE "SIGHT OBSCURING" BLACK VINYL SLATS.
- 12 PROVIDE 4' WIDE MAN GATE. BLACK VINYL COATED CHAIN LINK FENCE AROUND COMPACTOR PAD AS SHOWN. PROVIDE "SIGHT OBSCURING" BLACK VINYL SLATS.
- 13 INSTALL COMPACTOR AND ELECTRICAL CONTROL UNIT (PROVIDED BY OTHERS).
- 14 CONCRETE SLAB TO BE FLUSH WITH EXISTING ASPHALT.
- 15 PATCH ASPHALT PAVING AS NEEDED AROUND CONCRETE SLAB FROM CONCRETE SLAB TO SAWCUT. MATCH EXISTING ASPHALT PAVEMENT SECTION.





PARK

	NDICATED. PREVENT UNDERMINING OF PAVEMENTS AND
UNFINISHED FILLS, OR OTHER LOW AREAS. PUMPING, OR OTHER METHODS TO PREVEN	IIIS. R WHICH MAY ACCUMULATE IN OPEN EXCAVATIONS, REMOVE WATER BY TRENCHING WHERE APPROVED, T SOFTENING OF EXPOSED SURFACES. SURFACE EROUTING OF ANY STORM WATER RUN-OFF OR NATURAL
3. MOVEMENT OF CONSTRUCTION MACHINERY CONSTRUCTION SHALL BE AT THE CONTRAC PRIVATELY OWNED UTILITIES AS INDICATED COMPANY. FOR WORK IMMEDIATELY ADJACE	AND EQUIPMENT OVER PIPE AND UTILITIES DURING DTOR'S RISK. PERFORM ALL WORK ADJACENT TO IN ACCORDANCE WITH PROCEDURES OUTLINED BY UTILITY NT TO OR FOR EXCAVATIONS EXPOSING A UTILITY OR OR LIGHT EQUIPMENT EXCAVATION. SUPPORT UNCOVERED DTED BY THE CONTRACT EXCAVATION.
RE-ESTABLISH DAMAGED OR ERODED SLOP CONSTRUCTION PRIOR TO ACCEPTANCE. PR	FFIC, EROSION, AND SETTLEMENTS. REPAIR AND ES, ELEVATIONS, OR GRADES AND RESTORE SURFACE OTECT EXISTING STREAMS, DITCHES, AND STORM DRAIN ANS OF STRAW BALE DIKES AND/OR FILTER FABRIC
5. STRUCTURAL FILL MATERIAL	
FILL MATERIAL UNDER STRUCTURES OF B. IMPORTED MATERIAL: 1½" MINUS WELL PASSING THROUGH A #200 SIEVE. C. IMPORTED LEVELING COURSE: PLACE (E NATIVE MATERIAL SHALL NOT BE USED AS STRUCTURAL R PAVEMENTS. GRADED CRUSHED ROCK WITH LESS THAN 5% OF FINES COMPACTED 6" LAYER OF ¾" MINUS WELL GRADED FINES PASS #200 SIEVE, UNDER CONCRETE SLABS.
7. AGGREGATE BASE COURSE MATERIAL	
FINES PASSING THROUGH A #200 SIE B. LEVELING COURSE MATERIAL: ¾" MINU OF FINES PASSING THROUGH A #200	IS WELL GRADED CRUSHED ROCK WITH LESS THAN 5% SIEVE.
 THE CONSTRUCTION DOCUMENTS MAKE NO CONTRACTOR IS RESPONSIBLE FOR DETERM COMPLETE THE PROJECT. 	REPRESENTATION OR WARRANTEES OF SOIL QUANTITIES. MINING ALL QUANTITIES OF MATERIALS NECESSARY TO
SUPPLIED BY THE CONTRACTOR. EXCESS (S AS SHOWN IN THE DESIGN DOCUMENTS SHALL BE DNSITE EXCAVATED MATERIAL STOCKPILED AND NOT USED REMOVED FROM THE SITE AT THE END OF THE PROJECT
OFF SITE. IF ORGANIC SOILS ARE FOUND	RIAL, INCLUDING FILL, SHALL BE STRIPPED AND WASTED AFTER THE STRIPPING OPERATION, LOCALIZED AREAS OVER-EXCAVATED AND BACKFILLED WITH ENGINEERED
AND DISPOSAL OF SURFACE AND SUBSURI CONSTRUCTION. DISPOSE OF SURFACE WAT	, EQUIPMENT, AND CONSTRUCTION FOR THE COLLECTION FACE WATER ENCOUNTERED IN THE COURSE OF FER WHICH MAY ACCUMULATE IN OPEN EXCAVATIONS, REMOVE WATER BY TRENCHING WHERE APPROVED, NT SOFTENING OF EXPOSED SURFACES.
SLOUGHING OR EXCAVATION SLOPES AND AND TO ELIMINATE INTERFERENCE WITH OF	EXCAVATIONS SHALL BE CONTROLLED TO PREVENT WALLS, BOILS, UPLIFT AND HEAVE IN THE EXCAVATION RDERLY PROGRESS OF CONSTRUCTION. FRENCH DRAINS, BE PERMITTED WITHIN 3' OF THE FOUNDATION OF ANY
ALLOW FOR FORM CLEARANCE AND FOR F	/EMENTS TO SIZES AND LEVELS SHOWN OR REQUIRED. PROPER COMPACTION OF REQUIRED BACKFILLING MATERIAL. NATURAL, UNDISTURBED SOIL FREE OF ORGANIC MATERIAL
UNDISTURBED SOIL, AND BACKFILLED WITH	AL CONDITION SHALL BE EXCAVATED TO FIRM, NATURAL, SPECIFIED FILL MATERIALS. BACKFILL AND COMPACT ALL IR FILL BELOW AT NO ADDITIONAL COST TO THE OWNER.
15. NATIVE, IN-SITU SOILS UNDERLYING RETAI	NING WALL FOUNDATIONS, BUILDING FOUNDATIONS, FLOOR AL FILL SHALL BE PROOF-ROLLED TO A UNIFORM DRY
SPREAD IN UNIFORM LIFTS NOT TO EXCEE OF ITS MAXIMUM MODIFIED PROCTOR (AST TIME OF COMPACTION SHALL BE WITHIN ±	
EXCEEDING 8 INCHES IN COMPACTED THIC COMPACTED TO A UNIFORM DRY DENSITY DRY DENSITY (ASTM D698). IT SHALL BE	PAVEMENT STRUCTURES SHALL BE PLACED IN LAYERS NOT KNESS. EACH LAYER OF STRUCTURAL FILL SHALL BE OF 95 PERCENT OF THE MODIFIED PROCTOR MAXIMUM TESTED FOR COMPACTION AS CONSTRUCTION ME OF COMPACTION SHALL BE WITHIN ±3 PERCENT OF
THICKNESS AND COMPACTED TO 92 PERC	SHALL BE PLACED IN LAYERS NOT TO EXCEED 8" IN ENT OF ITS MAXIMUM MODIFIED PROCTOR (ASTM D698) ME OF CONNECTION SHALL BE WITHIN ±3 PERCENT OF
19. BASE COURSE AND LEVELING COURSE MA PERCENT OF THE MODIFIED PROCTOR DRY	terials for paving areas shall be compacted to 95 ′ density (astm d698).

- A. PIPE: 1.8 OZ. COMPLYING WITH ASTM A120. C. FABRIC: 2.0 OZ. COMPLYING WITH CLASS II OF ASTM A121.
- 5.79 LBS PER LINEAR FOOT MINIMUM WEIGHT.
- LINEAR FOOT MINIMUM WEIGHT.
- CORNER, PULL, SLOPE AND END POST.
- HORIZONTAL BRACE.
- 9. TRUSS RODS: PROVIDE 者" DIA. STEEL.

FABRIC.

- WOVEN INTEGRALLY INTO THE POST.
- CORNER, PULL, SLOPE, AND GATE POSTS.

- A. CHAIN LINK FENCING. B. ACCESSORIES & COMPONANTS. C. SHOP DRAWINGS OF GATES. D. POSTS.

SECTION 32 31 13 - CHAIN LINK FENCES AND GATES

1. ON STEEL FRAMEWORK AND APPURTENANCES, PROVIDE GALVANIZED FINISH WITH NOT LESS THAN THE FOLLOWING WEIGHT OF ZINC PER SQUARE FOOT:

B. HARDWARE AND ACCESSORIES: COMPLY WITH TABLE 1 OF ASTM A153.

2. PROVIDE FENCE FABRIC IN ONW PIECE WIDTHS, NUMBER 9 GAGE OR 0.148" WIRES IN 2" MESH, WITH TOP AND BOTTOM SELVAGES TWISTED AND BARBED.

3. END, CORNER, SLOPE AND PULL POSTS: PROVIDE 2.875" MINIMUM OUTSIDE DIAMETER AND

4. LINE POSTS: PROVIDE 2.375" MINIMUM OUTSIDE DIAMETER AND 3.65 LBS PER LINEAR FOOT MINIMUM WEIGHT. PROVIDE MINIMUM SIZES AND WEIGHTS AS FOLLOWS:

5. GATE POSTS: PROVIDE GATE POSTS FOR SUPPORTING SINGLE GATE LEAF, OR ONE LEAF OF A DOUBLE GATE INSTALLATION. PROVIDE 4" MINIMUM OUTSIDE DIAMETER AND 9.10 LBS PER

6. TOP RAILS: USE 1.660" OUTSIDE DIAMETER PIPE WEIGHING 1.80 LBS. PER LIN. FT. PROVIDE IN MANUFACTURER'S LONGEST LENGTHS, WITH EXPANSION TYPE COUPLINGS APPROXIMATELY 6" LONG FOR EACH JOINT. PROVIDE MEANS FOR ATTACHING TOP RAIL SECURELY TO EACH GATE,

7. POST BRACE ASSEMBLIES: PROVIDE AT END AND GATE POSTS, AND AT BOTH SIDES OF CORNER, SLOPE, AND PULL POSTS, WITH THE HORIZONTAL BRACE LOCATED AT MID-HEIGHT OF THE FABRIC. USE 1.660" OUTSIDE DIAMETER PIPE WEIGHING 1.80 LBS. PER LIN. FT. FOR

8. TENSION WIRE: PROVIDE NUMBER 7 GAGE GALVANIZED COILED SPRING WIRE AT BOTTOM OF

10. POST TOPS (CAPS): PROVIDE STEEL DESIGNED AS WEATHER-TIGHT CLOSURE CAP.

11. STRETCHER BARS: PROVIDE ONE-PIECE LENGTHS EQUAL TO FULL HEIGHT OF FABRIC, WITH A MINIMUM CROSS-SECTION OF $\frac{3}{16}$ " X $\frac{3}{4}$ ". PROVIDE ONE STRETCHER BAR FOR EACH GATE AND END POST, AND TWO FOR EACH CORNER, SLOPE, AND PULL POST, EXCEPT WHERE FABRIC IS

12. STRETCHER BAR BANDS: PROVIDE STEEL, WROUGHT IRON, OR MALLEABLE IRON, SPACED NOT OVER 15" ON CENTERS, TO SECURE STRETCHER BARS TO END, CORNER, PULL, SLOPE, AND GATE POSTS. BANDS MAY BE USED ALSO WITH SPECIAL FITTINGS FOR SECURING RAILS TO END,

13. GATES: ASSEMBLE GATE FRAMES BY WELDING WITH SPECIAL MALLEABLE OR PRESSED STEEL FITTINGS AND RIVETS FOR RIGID CONNECTIONS. USE SAME FABRIC AS USED IN THE FENCE. INSTALL FABRIC WITH STRETCHER BARS AT VERTICAL EDGES AS A MINIMUM. ATTACH STRETCHERS TO GATE FRAME AT NOT MORE THAN 15" ON CENTERS. ATTACH HARDWARE WITH RIVETS OR BY OTHER MEANS WHICH WILL PROVIDE SECURITY AGAINST REMOVAL AND BREAKAGE. PROVIDE DIAGONAL CROSS-BRACING CONSISTING OF $\frac{3}{6}$ " DIAMETER ADJUSTABLE LENGTH TRUSS RODS ON GATES WHERE REQUIRED TO PROVIDE FRAME RIGIDITY WITHOUT SAG OR TWIST.

14. SUBMITTALS: SUBMIT MANUFACTURERS STANDARD CATALOG DATA FOR THE FOLLOWING:

SECTION 32 12 16 - ASPHALT PAVING

- 1. HOT MIXED ASPHALT CONCRETE (HMAC): PROVIDE A HOT PLANT MIXED, UNIFORMLY COATED MIXTURE OF ASPHALT CEMENT, GRADED AGGREGATE, AND ADDITIVES CONFORMING TO OSSC SECTION 00745 FOR ALL PAVED AREAS IN THICKNESS INDICATED.
- A. LEVEL 3 HMAC HMAC FOR USE IN APPLICATIONS EXPOSED TOP MODERATE TRUCK TRAFFIC.
- 2. ASPHALT CEMENT SHALL CONFORM TO SECTION 00745 OF THE OSSC SECTION 00745. THE ASPHALT CEMENT SHALL BE HEATED AND DELIVERED TO THE MIXER AT A TEMPERATURE RECOMMENDED BY THE ASPHALT MANUFACTURER FOR THE TEMPERATURE-VISCOSITY RELATIONSHIP OF THE CEMENT.
- 3. PROVIDE AGGREGATE MATERIAL FOR HMAC AS SPECIFIED IN OSSC SECTION 00745.
- 4. RECLAIMED ASPHALT PAVEMENT (RAP) MATERIAL: RECLAIMED HMAC PAVEMENT (RAP) MATERIAL USED IN THE PRODUCTION OF NEW HMAC IS OPTIONAL. NO MORE THAN 20% RAP MATERIAL WILL BE ALLOWED IN THE NEW HMAC PAVEMENT. RAP MATERIAL WILL NOT BE ALLOWED IN OPEN GRADED HMAC OR LEVEL 4 DENSE GRADED HMAC WEARING COURSES.
- 5. MIX TYPE AND BROADBAND LIMITS: FURNISH THE TYPE(S) OF HMAC AS INDICATED. THE BROADBAND LIMITS FOR EACH OF THE MIX TYPES ARE SPECIFIED IN OSSC SECTION 00745.
- A. $\frac{3}{4}$ " dense graded mix.
- 6. PRIOR TO THE APPLICATION OF THE ASPHALTIC CONCRETE, APPLY A PRIME COAT OF LIQUID ASPHALT AT THE RATE OF .25 GALLONS PER SQUARE YARD ON THE PREPARED COMPACTED BASE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. APPLY LIQUID ASPHALT BY PRESSURE DISTRIBUTORS. ALLOW SUFFICIENT TIME BEFORE PLACING THE ASPHALT CONCRETE TO PERMIT THE PRIME COAT ASPHALT TO PENETRATE THE PREPARED COMPACTED BASE.
- 7. PLACE AND COMPACT ASPHALT CONCRETE PAVEMENT IN ACCORDANCE WITH THE OSSC SECTION 00745 FOR HMAC. THE MIXING PLANT AND CONSTRUCTION EQUIPMENT SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS.
- 8. CAREFULLY MAKE JOINTS BETWEEN OLD AND NEW PAVEMENTS OR BETWEEN SUCCESSIVE DAYS' work made in such manner as to insure a continuous bond between old and NEW SECTIONS OF THE COURSE. TRANSVERSE AND LONGITUDINAL JOINTS SHALL BE MADE AS SPECIFIED IN OSSC SECTION 00745. PAINT ALL JOINTS WITH A UNIFORM COAT OF TACK COAT BEFORE THE FRESH MIXTURE IS PLACED.
- 9. PERFORM DENSITY COMPACTION TESTS ON BASE COURSE PER SECTION 02315, EARTHWORK. 10. PERFORM DENSITY TESTING OF HMAC USING RANDOM TESTING METHOD SPECIFIED IN OSSC
- 11. SUBMITTALS ASPHALT JOB MIX FORMULA FOR EACH TYPE OF HOT MIX ASPHALT CONCRETE (HMAC) INDICATED. THE TMF SHALL MEET THE REQUIREMENT OF OSSC SECTION 00745.

SECTION 32 13 00 - SITE CONCRETE

- 1. REINFORCING MATERIALS: ASTM A 615, GRADE 60, DEFORMED.
- 2. JOINT DOWELL BARS: PLAIN STEEL BARS, ASTM A 615, GRADE 60. CUT BARS TRUE TO LENGTH WITH ENDS SQUARE AND FREE OF BURRS.
- 3. CONCRETE MATERIALS

SECTION 00745.

- A. PORTLAND CEMENT: ASTM C 150, TYPE I. USE ONE BRAND OF CEMENT THROUGHOUT PROJECT UNLESS OTHERWISE APPROVED IN WRITING BY OWNER'S REPRESENTATIVE.
- B. FLY ASH: ASTM C 618, TYPE F. . NORMAL-WEIGHT AGGREGATES: ASTM C 33, CLASS 4, AND AS FOLLOWS. PROVIDE
- AGGREGATES FROM A SINGLE SOURCE. MAXIMUM AGGREGATE SIZE: 3/4 INCH. DO NOT USE FINE OR COARSE AGGREGATES THAT CONTAIN SUBSTANCES THAT CAUSE SPALLING. D. WATER: POTABLE.
- . AIR-ENTRAINING ADMIXTURE: ASTM C 260, CERTIFIED BY MANUFACTURER TO BE COMPATIBLE WITH OTHER REQUIRED ADMIXTURES.
- F. WATER-REDUCING ADMIXTURE: ASTM C 494, TYPE A.
- 4. CONCRETE MIX
- A. PREPARE DESIGN MIXES FOR EACH TYPE AND STRENGTH OF NORMAL-WEIGHT CONCRETE BY EITHER LABORATORY TRIAL BATCH OR FIELD EXPERIENCE METHODS AS SPECIFIED IN ACI 301. PROPORTION MIXES ACCORDING TO ACI 211.1 AND ACI 301 TO PROVIDE NORMAL-WEIGHT CONCRETE WITH THE FOLLOWING PROPERTIES: B. COMPRESSIVE STRENGTH (28-DAY): 3,500 PSI UNLESS OTHERWISE NOTED.
- C. MAXIMUM COURSE AGGREGATE SIZE: 3/4 INCH. D. MAXIMUM SLUMP: 4 INCHES PLUS 1/5 TO 1 INCH.
- E. ENTRAINED AIR: 5 PERCENT \pm ½ TO 1 PERCENT.
- 5. SUBMITTALS: DESIGN MIX FOR EACH CLASS OF CONCRETE. SUBMIT LABORATORY TEST RESULTS FOR EVULATION OF CONCRETE MATERALS AND MIX DESIGN TESTS.

GENERAL SITE NOTES

- 1. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING SITE CONDITIONS PRIOR TO THE COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO THE OWNER'S REPRESENTATIVE. CONTRACTOR IS RESPONSIBLE FOR VISITING THE SITE AND BECOMING FAMILIAR WITH THE SITE CONDITIONS PRIOR TO BIDDING.
- 2. CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THAT NEW FEATURES TIE INTO EXISTING SITE DEVELOPMENT, PAVEMENT JOINTS MATCH CORRECTLY, AND THAT GENERAL DESIGN ELEVATIONS FOR NEW CONSTRUCTION PROVIDE PROPER PAVEMENT AND DRAINAGE SLOPES FROM EXISTING TIE IN POINTS. REPORT DISCREPANCIES TO OWNER'S REPRESENTATIVE PRIOR TO CONSTRUCTION.
- 3. IN AREAS WHERE ASPHALT PAVING IS BEING REWORKED, PROVIDE NEW PAINT STRIPING FOR ALL REVISED PAVING WORK AND PARKING STALLS. EXISTING STRIPING TO BE BLACKENED OUT IN RECONFIGURED AREAS AS REQUIRED.
- 4. ALL CONSTRUCTION ACTIVITIES SHALL BE COORDINATED WITH CITY INSPECTOR(S). CONTRACTOR SHALL NOTIFY CITY INSPECTOR(S) 48 HOURS PRIOR TO START OF CONSTRUCTION.
- 5. DURING CONSTRUCTION, THE CONTRACTOR AND/OR SUBCONTRACTORS SHALL HAVE A MINIMUM OF ONE (1) SET OF PERMIT APPROVED PLANS AND SPECIFICATIONS ON THE JOB SITE AT ALL TIMES.
- 6. UPON COMPLETION OF THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL LEAVE THE PROJECT AREA FREE OF DEBRIS AND UNUSED MATERIAL. ALL DAMAGE CAUSED BY THE CONTRACTOR SHALL BE RESTORED TO AN "AS GOOD OR BETTER" CONDITION.
- 7. THE CHAIN LINK FENCE THAT IS BEING REMOVED FOR ACCESS TO INSTALL THE UTILITIES, IS TO BE REPLACED IN LIKE.

DEMOLITION NOTES

- 1. DEMOLITION REQUIREMENTS ARE NOT SHOWN ON THESE DRAWINGS. CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING SCOPE OF DEMOLITION WORK FROM OWNER AND FOR EXAMINATION OF EXISTING SITE CONDITIONS. CONTRACTOR SHALL SUBMIT A DEMOLITION PLAN PRIOR TO CONSTRUCTION OUTLINING ITEMS TO BE REMOVED. ALL UTILITY LINES AND STRUCTURES SHOWN WITHIN THE LIMITS OF.
- 2. DEMOLITION SHALL BE REMOVED EXCEPT THOSE INDICATED AS "TO REMAIN". ALL LINES THAT ARE CUT AT LIMITS OF DEMOLITION OR POINTS OF DISCONNECTION WITHIN THE WORK AREA, ARE TO BE CAPPED OR PLUGGED. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TEMPORARY ACCESS.
- 3. DURING CONSTRUCTION. UTILITY OUTAGES AND ACCESS CLOSURES REQUIRE A MINIMUM OF 24 HOURS NOTICE TO OWNER OR SITE TENANTS.

SUBMITTALS


- 1. THE SUBMITTALS SHALL BE PROPERLY BOUND WITH SECTIONS CLEARLY IDENTIFIED. SUBMITTALS FOR EACH SECTION NEED TO BE COMPLETE. PARTIAL SUBMITTALS FOR A SECTION SHALL BE RETURNED UNREVIEWED.
- 2. THE SUBMITTALS SHALL CONTAIN PREFORMANCE DATA AND TECHNICAL SPECIFICATIONS ON ALL MATERIALS AND EQUIPMENT TO BE USED ON THE PROJECT.
- 3. SHOP DRAWINGS SHALL BE INCLUDED WITH THE SUBMITTALS WHERE SPECIFICALLY REQUESTED IN THE SPECIFICATIONS. WHERE NECESSARY TO DETERMINE CLEARANCE, WHERE THE CONTRACTOR PROPOSES ALTERNATE EQUIPMENT OR MATERIAL ARRANGEMENTS, AND WHEN REQUESTED BY THE OWNER.
- 4. ALL SHOP DRAWINGS MUST BE REVIEWED AND APPROVED BY THE GENERAL CONTRACTOR PRIOR TO BEING SUBMITTED TO THE ENGINEER. ANY SHOP DRAWINGS SUBMITTED WITHOUT CONTRACTOR'S APPROVAL STAMP SHALL BE REJECTED.
- 5. REVIEW OF SUBMITTALS OR SHOP DRAWINGS BY THE OWNER AND ENGINEER DOES NOT RELIEVE THE CONTRACTOR FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS UNLESS SPECIFIC APPROVAL HAS BEEN REQUESTED FOR A GIVEN DEVIATION.
- 6. BY SUBMITTING. THE CONTRACTOR/SUPPLIER CERTIFIES THAT THE MATERIALS OR FQUIPMENT PROPOSED IS SATISFACTORY FOR THE APPLICATION INTENDED.
- 7. FABRICATION OF MATERIALS AND INSTALLATION OF EQUIPMENT IS NOT AUTHORIZED PRIOR TO APPROVAL OF SHOP DRAWINGS AND VENDOR DATA.
- 8. ALTERNATE ITEMS INSTALLED WITHOUT THE OWNERS APPROVAL SHALL BE REPLACED WITH THE SPECIFIED MATERIALS AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR ASSUMES FULL RESPONSIBILITY THAT ALTERNATE ITEMS OR PROCEDURES WILL MEET THE JOB REQUIREMENTS AND IS RESPONSIBLE FOR COST OF REDESIGN AND OF MODIFICATION TO THIS AND OTHER PARTIES' WORK CAUSED BY ALTERNATE ITEMS FURNISHED UNDER WORK OF THIS SECTION.

EROSION CONTROL

- 1. ALL EROSION, SEDIMENT, AND POLLUTION CONTROL PLAN (ESPCP) MEASURES SHALL BE INSTALLED AS PER THE DETAIL DRAWINGS IN THE <u>CITY OF PORTLAND</u> EROSION CONTROL MANUAL.
- 2. TEMPORARY ESPCP MEASURES SHALL BE INSTALLED, INSPECTED, AND APPROVED BY A CITY INSPECTOR BEFORE STARTING GROUND DISTURBING ACTIVITIES.
- 3. ESPCP MEASURES SHALL NOT BE REMOVED UNTIL PERMANENT LANDSCAPING HAS BEEN INSTALLED AND FINAL INSPECTION HAS BEEN REQUESTED AND APPROVED BY A CITY INSPECTOR.
- 4. INSPECTIONS MAY BE REQUESTED BY TELEPHONING THE INSPECTION REQUEST NUMBER 823-7000 ONE DAY PRIOR TO THE TIME OF INSPECTION.
- 5. APPROVAL OF THIS ESPCP PLAN DOES NOT CONSTITUTE APPROVAL OF PERMANENT OR DRAINAGE DESIGN (I.E. SIZE AND LOCATION OF ROADS, PIPES, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITES, ETC.)
- 6. THE IMPLEMENTATION OF THIS ESPCP AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESPCP FACILITIES IS THE RESPONSIBILITY OF THE APPLICANT/CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- 7. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES may be required to insure that all paved areas are kept clean for the duration OF THE PROJECT.
- 8. THE BOUNDARIES OF THE CLEARING LIMITS (IF REQUIRED BY THE CITY) SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE APPLICANT/CONTRACTOR FOR THE DURATION OF THE CONSTRUCTION.
- 9. THE ESPCP FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR THE ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESPCP FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- 10. THE ESPCP FACILITIES SHALL BE INSPECTED DAILY BETWEEN OCTOBER 1 AND APRIL 30 BY THE APPLICANT/CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING. ALL INSPECTIONS SHALL BE NOTED IN AN INSPECTION LOG WHICH SHALL BE MADE AVAILABLE TO THE CITY INSPECTOR UPON REQUEST.
- 11. ESPCP FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN 24 HOURS FOLLOWING A STORM EVENT.
- 12. A SIGN WITH THE CITY'S EROSION CONTROL HOTLINE NUMBER, PROJECT ADDRESS, AND PERMIT NUMBER SHALL BE POSTED AT A LOCATION CLEARLY VISIBLE FROM THE RIGHT OF WAY AND MAINTAINED UNTIL PROJECT COMPLETION.
- 13. EXPOSED SOILS THAT REMAIN UNWORKED FOR 14 DAYS OR MORE SHALL BE IMMEDIATELY PROTECTED BY APPROPRIATE GROUND COVER. DISTURBED LAND THAT WILL REMAIN UNWORKED FOR 2 MONTHS OR LONGER SHALL ALSO BE SEEDED WITH AN APPROVED SEED MIXTURE.
- 14. PUBLIC STREETS WILL BE SWEPT DAILY, IF NECESSARY, TO ALLEVIATE SEDIMENT DISCHARGE TO THE STORM WATER MANAGEMENT SYSTEM. UNFILTERED WASH WATER CANNOT BE DISCHARGED TO STORM DRAINS.
- 15. ALL EROSION CONTROL SEEDING FOR SITE STABILIZATION WILL BE PERFORMED NO LATER THAN SEPTEMBER 1ST TO ALLOW TIME FOR VEGETATIVE ESTABLISHMENT PRIOR TO THE ONSET OF THE WET WEATHER SEASON. 16. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30
- DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THEY ARE NO LONGER NEEDED. 17. TRAPPED SEDIMENT SHALL BE REMOVED OR STABILIZED ON SITE. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE REPAIRED AND PROTECTED WITH ADEQUATE GROUND
- 18. SEEDING SHALL BE SUPPLIED WITH ADEQUATE MOISTURE. SUPPLY WATER AS NEEDED. WATER SHOULD BE CONTROLLED TO PREVENT RUNDEE AREAS WHICH FAIL TO ESTABLISH VEGETATIVE COVER ADEQUATE TO PREVENT EROSION SHALL BE RESEEDED AS SOON AS AREAS ARE IDENTIFIED.

COVER (2" STRAW, COMPOST, MULCH, ETC.)

- 19. DISTURBED AREAS OF SLOPE GREATER THAN 2:1 WILL BE STABLIZED THROUGH SEEDING AND THE INSTALLATION OF NORTH AMERICAN GREEN SCI50BN MATTING OR EQUIVALENT PRODUCT.
- 20. THE PROPOSED EROSION CONTROL MEASURES ARE A MINIMUM BEST MANAGEMENT PRACTICE. THE CONTRACTOR MAY BE REQUIRED TO MAKE ADDITIONAL EROSION CONTROL MEASURES TO ENSURE THAT NO SEDIMENT LADEN WATER EXITS THE SITE OR ENTERS THE EXISTING STORMWATER SYSTEM.
- 21. IN THE CASE OF STABLIZATION SEEDING AND PLANTINGS FOR SWALES & SLOPES, IT IS THE CONTRACTORS RESPONSIBILITY TO SEQUENCE THE WORK SUCH THAT THE PLANTINGS ARE ESTABLISHED AS FAR AS POSSIBILE PRIOR TO OCTOBER 1.
- 22. CONTRACTOR SHALL DESIGNATE AN ONSITE EROSION & SEDIMENT CONTROL INSPECTOR AND SHALL SUBMIT THE NAME TO THE OWNER'S REPRESENTATIVE FOR SUBMITTAL TO DEQ AS PART OF THE DEQ 1200C PERMIT REQUIREMENTS.
- 23. AN EROSION AND SEDIMENT CONTROL PERMIT HAS BEEN ISSUED BY OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ 1200C PERMIT). CONTRACTOR IS RESPONSIBLE FOR ADMINISTRATION AND CONFORMANCE OF ALLEROSION AND SEDIMENT CONTROL REQUIREMENTS STIPULATED IN THIS PERMIT INCLUDING MANTENANCE & MONITORING.



						Reuse of Documents This document and the ideas and designs incorporated
						herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012
-	-	-			-	
Nc	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date	

Plot Date: 21 March 2012 - 8:44 AM Plotted by: Keith Tolle

GENERAL SITE NOTES

- 1. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING SITE CONDITIONS PRIOR TO THE COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO THE OWNER'S REPRESENTATIVE. CONTRACTOR IS RESPONSIBLE FOR VISITING THE SITE AND BECOMING FAMILIAR WITH THE SITE CONDITIONS PRIOR TO BIDDING.
- 2. CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THAT NEW FEATURES TIE INTO EXISTING SITE DEVELOPMENT, PAVEMENT JOINTS MATCH CORRECTLY, AND THAT GENERAL DESIGN ELEVATIONS FOR NEW CONSTRUCTION PROVIDE PROPER PAVEMENT AND DRAINAGE SLOPES FROM EXISTING TIE IN POINTS. REPORT DISCREPANCIES TO OWNER'S REPRESENTATIVE PRIOR TO CONSTRUCTION.
- 3. ALL CONSTRUCTION ACTIVITIES SHALL BE COORDINATED WITH CITY INSPECTOR(S) CONTRACTOR SHALL NOTIFY CITY INSPECTOR(S) 48 HOURS PRIOR TO START OF CONSTRUCTION.
- 4. DURING CONSTRUCTION, THE CONTRACTOR AND/OR SUBCONTRACTORS SHALL HAVE A MINIMUM OF ONE (1) SET OF PERMIT APPROVED PLANS AND SPECIFICATIONS ON THE JOB SITE AT ALL TIMES.
- 5. UPON COMPLETION OF THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL LEAVE THE PROJECT AREA FREE OF DEBRIS AND UNUSED MATERIAL. ALL DAMAGE CAUSED BY THE CONTRACTOR SHALL BE RESTORED TO AN "AS GOOD OR BETTER" CONDITION.

DEMOLITION NOTES

- 1. DEMOLITION REQUIREMENTS ARE NOT SHOWN ON THESE DRAWINGS. CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING SCOPE OF DEMOLITION WORK AND FOR EXAMINATION OF EXISTING SITE CONDITIONS. CONTRACTOR SHALL SUBMIT A DEMOLITION PLAN PRIOR TO CONSTRUCTION OUTLINING PROPOSED SCHEDULE, SEQUENCE AND ITEMS TO BE REMOVED. ALL UTILITY LINES AND STRUCTURES SHOWN WITHIN THE LIMITS OF PROJECT SHALL BE PROTECTED OR MODIFIED TO MAINTAIN FUNCTION.
- 2. DEMOLITION SHALL BE REMOVED EXCEPT THOSE INDICATED AS "TO REMAIN". ALL LINES THAT ARE CUT AT LIMITS OF DEMOLITION OR POINTS OF DISCONNECTION WITHIN THE WORK AREA. ARE TO BE CAPPED OR PLUGGED. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING TEMPORARY ACCESS.
- 3. DURING CONSTRUCTION. UTILITY OUTAGES AND ACCESS CLOSURES REQUIRE A MINIMUM OF 24 HOURS NOTICE TO OWNER OR SITE TENANTS.
- 4. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- 5. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE, BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, OR OTHER SUITABLE MATERIAL, STRAW WATTLES, OR OTHER APPROVED MATERIALS.
- 6. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
- 7. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING, MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 8. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.

IREE PROTECTION NOTES

- 1. CITY ARBORIST SHALL BE ON SITE TO DISCUSS METHODS OF TREE REMOVAL AND TREE PROTECTION PRIOR TO START OF ANY CONSTRUCTION.
- 2. CONTRACTOR SHALL DESIGNATE WITH THE CITY ARBORIST THE TREE PROTECTION ZONE. WHERE FEASIBLE, THE TREE PROTECTION ZONE SHALL BE ESTABLISHED AT THE DRIPLINE OF THE TREE OR GROVE AS MINIMUM. IF PROPOSED SLOPE MUST BE INSTALLED CLOSER TO THE TREE(S). THE TREE PROTECTION ZONE MAY BE ESTABLISHED WITHIN THE DRIPLINE AREA IS THE CITY ARBORIST DETERMINES THAT THE TREE(S) WILL NOT BE UNDULY DAMAGED.
- 3. CONTRACTOR SHALL PROVIDE TREE PROTECTION FENCING AT LEAST AT THE EDGE OF THE ROOT ZONE OF EACH TREE OR GROUP OF TREES. THE FENCE SHALL BE PLACED BEFORE CONSTRUCTION STARTS AND REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETE. THE FENCE SHALL BE FOUR (4) FOOT TALL ORANGE PLASTIC OR SNOW FENCE.
- 4. CONTRACTOR SHALL CLEARLY MARK ALL TREES TO BE REMOVED WITH CONSTRUCTION FLAGGING. TREE-MARKING PAINT, OR OTHER METHODS APPROVED IN ADVANCE BY THE CITY ARBORIST.
- 5. CONTRACTOR SHALL NOT STORE MATERIALS OR EQUIPMENT WITHIN THE TREE PROTECTION ZONE.
- 6. CONTRACTOR SHALL AVOID EXCAVATION WITHIN THE TREE PROTECTION ZONE IF ALTERNATIVES ARE AVAILABLE. IF EXCAVATION IS UNAVOIDABLE WITHIN THE TREE PROTECTION ZONE, THE CITY ARBORIST SHALL EVALUATE THE PROPOSED EXCAVATION TO DETERMINE METHODS TO MINIMIZE THE IMPACTS TO TRESS. THIS CAN INCLUDE TUNNELING, HAND DIGGING, OR OTHER APPROACHES. ALL CONSTRUCTION WITHIN THE TREE PROTECTION ZONE SHALL BE UNDER THE ON-SITE TECHNICAL SUPERVISION OF THE CITY ARBORIST.
- 7. CITY ARBORIST TO MONITOR CONSTRUCTION ACTIVITIES AND PROGRESS, AND PROVIDE WRITTEN REPORTS TO THE DEVELOPER AND THE CITY'S PROJECT PLANNER AT REGULAR INTERVALS.

GRADING NOTES

- 1. SURVEY OF EXISTING CONDITIONS PREPARED BY COMPASS ENGINEERING DATED 1/9/2012. THE CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFICATION OF ALL SURVEY DATA. CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING RIGHT-OF-WAY LINES, SLOPE EASEMENTS, AND ALL HORIZONTAL AND VERTICAL CONTROL PRIOR TO CONSTRUCTION.
- 2. CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION STAKING AND SHALL ARRANGE FOR STAKING WITH A LICENSED SURVEYOR. STAKING WILL BE REVIEWED BY OWNER FOR CONFORMATION TO DESIGN PRIOR TO CONSTRUCTION.
- 3. ALL GRADES BETWEEN SPOT ELEVATIONS SHALL HAVE UNIFORM SLOPE UNLESS OTHERWISE INDICATED, MAINTAIN POSITIVE DRAINAGE AWAY FROM ALL BUILDING WALLS AND DOORS.
- 4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY OF ALL CONSTRUCTION. ADEQUATE SHORING BRACING, TIES, AND SUPPORTS SHALL BE USED TO PROVIDE PROPER TEMPORARY INTEGRITY DURING ALL PHASES OF CONSTRUCTION.
- 5. UNLESS OTHERWISE NOTED ON THE PROJECT LANDSCAPE PLAN. ALL EXISTING LANDSCAPED AND UNPAVED AREAS WHICH ARE DISTURBED BY CONSTRUCTION OR EARTHWORK OPERATIONS SHALL BE HAND RAKED SMOOTH AND RETURNED TO ORIGINAL EXISTING CONDITIONS. DISTURBED LANDSCAPED AREAS SHALL RECEIVE BARK DUST AND REPLACEMENT PLANTINGS. DISTURBED NATURAL AREAS SHALL BE HYDROSEEDED TO REPLACE NATIVE COVER. DISTURBED GRAVEL AREAS SHALL RECEIVE REPLACEMENT GRAVEL OR CRUSHED ROCK SURFACING.
- 6. ALL DITCHES, SWALES, GUTTERS, ETC. SHALL BE CONSIDERED ACTIVE STORM CONVEYANCES UNLESS OTHERWISE INDICATED. CONTRACTOR IS RESPONSIBLE FOR ADDRESSING STORM WATER DRAINAGE AND DEWATERING OF WORK AREAS DURING CONSTRUCTION.
- 7. DURING WET WEATHER PERIODS, CONTRACTOR IS RESPONSIBLE FOR SEQUENCING CONSTRUCTION IN A MANNER TO MINIMIZE IMPACT ON OPEN EARTHWORK AND COMPACTION OPERATIONS.
- 8. ALL EXISTING MONUMENTS SHALL BE PROTECTED DURING CONSTRUCTION. IF ANY MONUMENTS ARE DISTURBED OR DESTROYED DURING CONSTRUCTION. CONTRACTOR SHALL RETAIN THE SERVICES OF A REGISTERED LAND SURVEYOR TO RESTORE THE MONUMENT TO ITS ORIGINAL CONDITION AND FILE THE NECESSARY SURVEYS AS REQUIRED BY STATE LAW.
- 9. COMPLETELY COVER ANY SOIL STOCKPILES WITH 6 MIL BLACK PLASTIC AND PROVIDE RESTRAINTS TO HOLD PLASTIC IN PLACE. MONITOR PLASTIC COVER AS PART OF CONTINUOUS EROSION CONTROL PLAN. PLACE SILT FENCE COMPLETELY AROUND STOCKPILE.

UTILITY NOTES

- 1. LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE PLOTTED FROM RECORD DRAWINGS AND INTERPOLATION OF PHYSICAL EVIDENCE ON THE SITE AND ARE SUBJECT TO FIELD VERIFICATION BY THE CONTRACTOR.
- 2. ALL LOCATIONS FOR WORK SHALL BE CHECKED AND COORDINATED WITH EXISTING CONDITIONS IN THE FIELD BEFORE BEGINNING CONSTRUCTION UNDER THIS SECTION OR ANY OTHER SECTION.
- 3. THE WORKING DRAWINGS ARE GENERALLY DIAGRAMMATIC. THEY DO NOT SHOW EVERY OFFSET, BEND OR ELBOW REQUIRED FOR INSTALLATION IN THE SPACE PROVIDED. THEY DO NOT SHOW EVERY DIMENSION, COMPONENT PIECE, OR FITTING REQUIRED TO COMPLETE THE PROJECT. CONTRACTOR IS RESPONSIBLE FOR PROVIDING A COMPLETE AND WORKING SYSTEM.
- 4. CONTRACTOR SHALL COORDINATE A UTILITY LOCATE 48 HOURS PRIOR TO BEGINNING ANY UTILITY CONSTRUCTION FOR LOCATION MARK-UP OF ALL EXISTING UTILITIES BOTH IN THE RIGHT-OF-WAY AND ON PRIVATE PROPERTY. CONTRACTOR SHALL COORDINATE THE UTILITY LOCAL WITH MUNICIPALITY HAVING JURISDICTION FOR ALL UTILITY WORK WITHIN A PUBLIC RIGHT-OF-WAY. INFORM ENGINEER IMMEDIATELY IF LOCATE INDICATES THAT EXISTING UTILITIES ARE DIFFERENT THAN SHOWN ON DRAWINGS
- 5. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO UTILITIES, FEATURES, AND STRUCTURES LOCATED ON THE SITE. LOCATE, PROTECT, AND AVOID DISRUPTION OF ALL ABOVE AND BELOW GRADE UTILITIES DURING CONSTRUCTION.
- 6. ALL UTILITY CONSTRUCTION ON PRIVATE PROPERTY SHALL CONFORM TO THE LATEST EDITION OF THE STATE OF OREGON PLUMBING SPECIALTY CODE. ALL UTILITY CONSTRUCTION WITHIN THE RIGHT-OF-WAY SHALL CONFORM TO THE STANDARD REQUIREMENTS OF THE MUNICIPALITY HAVING JURISDICTION.
- 7. ALL BURIED LINES TO HAVE 2 FEET MINIMUM COVER, UNLESS NOTED OTHERWISE
- 8. SEE LANDSCAPE DRAWINGS FOR PLANTING AND IRRIGATION LINES.
- 9. ALL EXISTING UTILITIES AND TIE-IN POINTS SHOULD BE CONSIDERED ACTIVE UTILITIES UNLESS OTHERWISE INDICATED.




W www.ghd.com

T 1 503 226 3921 **F** 1 503 226 3926

15575 SW Sequoia Parkway Suite 140 Portland Oregon 97224 USA

Drawn KPT	Designer PRT			WILSONVILLE SCHOOL	DISTRIC	CT	
Drafting Check	Design Check DMW			NK REMEDIATION			
Approved (Project Director) Date 03/06/12		-	GENERAL N 11456-11012				
Scale AS SHOWN	This Drawing shall not be used for Construction unless Signed and Sealed For Construction	Original Size	Drawing No:	_		Sht	of Rev:



SUBMITTALS

1. THE SUBMITTALS SHALL BE PROPERLY BOUND WITH SECTIONS CLEARLY IDENTIFIED. SUBMITTALS FOR EACH SECTION NEED TO BE COMPLETE. PARTIAL SUBMITTALS FOR A SECTION SHALL BE RETURNED UNREVIEWED.

2. THE SUBMITTALS SHALL CONTAIN PERFORMANCE DATA AND TECHNICAL SPECIFICATIONS ON ALL MATERIALS AND EQUIPMENT TO BE USED ON THE PROJECT.

3. SHOP DRAWINGS SHALL BE INCLUDED WITH THE SUBMITTALS WHERE SPECIFICALLY REQUESTED IN THE SPECIFICATIONS, WHERE NECESSARY TO DETERMINE CLEARANCE, WHERE THE CONTRACTOR PROPOSES ALTERNATE EQUIPMENT OR MATERIAL ARRANGEMENTS, AND WHEN REQUESTED BY THE OWNER.

- 4. ALL SHOP DRAWINGS MUST BE REVIEWED AND APPROVED BY THE GENERAL CONTRACTOR PRIOR TO BEING SUBMITTED TO THE ENGINEER. ANY SHOP DRAWINGS SUBMITTED WITHOUT CONTRACTOR'S APPROVAL STAMP SHALL BE REJECTED.
- 5. REVIEW OF SUBMITTALS OR SHOP DRAWINGS BY THE OWNER AND ENGINEER DOES NOT RELIEVE THE CONTRACTOR FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS UNLESS SPECIFICALLY WRITTEN APPROVAL HAS BEEN REQUESTED FOR A GIVEN DEVIATION.
- BY SUBMITTING, THE CONTRACTOR/SUPPLIER CERTIFIES THAT THE MATERIALS OR EQUIPMENT PROPOSED IS SATISFACTORY FOR THE APPLICATION INTENDED.
- 7. FABRICATION OF MATERIALS AND INSTALLATION OF EQUIPMENT IS NOT AUTHORIZED PRIOR TO APPROVAL OF SHOP DRAWINGS AND VENDOR DATA.
- 8. ALTERNATE ITEMS INSTALLED WITHOUT THE OWNERS APPROVAL SHALL BE REPLACED WITH THE SPECIFIED MATERIALS AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR ASSUMES FULL RESPONSIBILITY THAT ALTERNATE ITEMS OR PROCEDURES WILL MEET THE JOB REQUIREMENTS AND IS RESPONSIBLE FOR COST OF REDESIGN AND OF MODIFICATION TO THIS AND OTHER PARTIES' WORK CAUSED BY ALTERNATE ITEMS FURNISHED UNDER WORK OF THIS SECTION.

PRELIMINARY

LOCAL AGENCY EROSION CONTROL NOTES:

- 1. ALL EROSION, SEDIMENT, AND POLLUTION CONTROL PLAN (ESPCP) MEASURES SHALL BE INSTALLED AS PER THE EROSION PREVENTION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL (CLACKAMAS COUNTY WATER ENVIRONMENT SERVICES REVISED DECEMBER 2000).
- 2. PRIOR TO GROUND BREAKING TEMPORARY ESCP MEASURES SHALL BE INSTALLED, INSPECTED, AND APPROVED BY A CITY OF WEST LINN INSPECTOR BEFORE STARTING GROUND DISTURBING ACTIVITIES. CONTACT THE CITY AT 503-722-5509 24 HOURS IN ADVANCE FOR AN INSPECTION.
- 3. ESCP MEASURES SHALL NOT BE REMOVED UNTIL PERMANENT LANDSCAPING HAS BEEN INSTALLED AND FINAL INSPECTION HAS BEEN REQUESTED AND APPROVED BY A CITY OF WEST LINN INSPECTOR.
- 4. INSPECTIONS MAY BE REQUESTED BY TELEPHONING CITY OF WEST LINN ONE DAY PRIOR TO THE TIME OF INSPECTION. NO HOLIDAYS OR WEEKENDS.
- 5. APPROVAL OF THIS ESCP PLAN DOES NOT CONSTITUTE APPROVAL OF PERMANENT OR DRAINAGE DESIGN (I.E. SIZE AND LOCATION OF ROADS, PIPES, RESTRICTORS, CHANNELS, RETENTION FACILITIES, UTILITIES, ETC.)
- 6. THE IMPLEMENTATION OF THIS ESCP AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESCP FACILITIES IS THE RESPONSIBILITY OF THE APPLICANT/CONTRACTOR AND OWNER UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- 7. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 8. THE BOUNDARIES OF THE CLEARING LIMITS (IF REQUIRED BY THE CITY OF WEST LINN) SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE APPLICANT/CONTRACTOR FOR THE DURATION OF THE CONSTRUCTION.
- 9. THE ESCP FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR THE ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESCP FACILITIES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- 10. ESCP FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF EVERY TWO WEEKS OR WITHIN 24 HOURS FOLLOWING A STORM EVENT.
- 11. EXPOSED SOILS THAT REMAIN UNWORKED FOR 14 DAYS OR MORE SHALL BE IMMEDIATELY PROTECTED BY APPROPRIATE GROUND COVER. DISTURBED LAND THAT WILL REMAIN UNWORKED FOR 2 MONTHS OR LONGER SHALL ALSO BE SEEDED WITH AN APPROVED SEED MIXTURE.
- 12. PUBLIC STREETS WILL BE SWEPT DAILY, IF NECESSARY, TO ALLEVIATE SEDIMENT DISCHARGE TO THE STORM WATER MANAGEMENT SYSTEM. UNFILTERED WASH WATER CANNOT BE DISCHARGED TO STORM DRAINS.
- 13. ALL EROSION CONTROL SEEDING FOR SITE STABILIZATION WILL BE PERFORMED NO LATER THAN SEPTEMBER 1ST TO ALLOW TIME FOR VEGETATIVE ESTABLISHMENT PRIOR TO THE ONSET OF THE WET WEATHER SEASON.
- 14. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THEY ARE NO LONGER NEEDED.
- 15. TRAPPED SEDIMENT SHALL BE REMOVED OR STABILIZED ON SITE. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE REPAIRED AND PROTECTED WITH ADEQUATE GROUND COVER (2" STRAW, COMPOST, MULCH, ETC.)
- 16. SEEDING SHALL BE SUPPLIED WITH ADEQUATE MOISTURE. SUPPLY WATER AS NEEDED. WATER SHOULD BE CONTROLLED TO PREVENT RUNOFF. AREAS WHICH FAIL TO ESTABLISH VEGETATIVE COVER ADEQUATE TO PREVENT EROSION SHALL BE RESEEDED AS SOON AS AREAS ARE IDENTIFIED.
- 17. DISTURBED AREAS OF SLOPE GREATER THAN 2:1 WILL BE STABILIZED THROUGH SEEDING AND THE INSTALLATION OF NORTH AMERICAN GREEN SCI50BN MATTING OR EQUIVALENT PRODUCT.
- 18. THE PROPOSED EROSION CONTROL MEASURES ARE A MINIMUM BEST MANAGEMENT PRACTICE. THE CONTRACTOR MAY BE REQUIRED TO MAKE ADDITIONAL EROSION CONTROL MEASURES TO ENSURE THAT NO SEDIMENT LADEN WATER EXITS THE SITE OR ENTERS THE EXISTING STORMWATER SYSTEM.
- 19. IN THE CASE OF STABILIZATION SEEDING AND PLANTINGS FOR SWALES & SLOPES, IT IS THE CONTRACTORS RESPONSIBILITY TO SEQUENCE THE WORK SUCH THAT THE PLANTINGS ARE ESTABLISHED AS FAR AS POSSIBLE PRIOR TO OCTOBER 1.
- 20. CONTRACTOR SHALL DESIGNATE AN ONSITE EROSION & SEDIMENT CONTROL INSPECTOR AND SHALL SUBMIT THE NAME TO THE OWNER'S REPRESENTATIVE FOR SUBMITTAL TO DEQ AS PART OF THE DEQ 1200C PERMIT REQUIREMENTS.
- 21. AN EROSION AND SEDIMENT CONTROL PERMIT HAS BEEN ISSUED BY OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ 1200C PERMIT). CONTRACTOR IS RESPONSIBLE FOR ADMINISTRATION AND CONFORMANCE OF ALL EROSION AND SEDIMENT CONTROL REQUIREMENTS STIPULATED IN THIS PERMIT INCLUDING MAINTENANCE & MONITORING.
- 22. A MINIMUM OF ONE WATER TRUCK IS REQUIRED ON SITE AT ALL TIMES.

STANDARD EROSION AND SEDIMENT CONTROL PLAN DRAWING NOTES:

- 1. HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDII MEASURES AND CONSTRUCTION LIMITS. (SCHEDULE A.8.C.I.(3))
- 2. ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS.
- 3. INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS.
- 4. RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, RETAIN THE ESCP AT THE CONSTRUCTION SITE OR AT ANOTHER LOCATION. (SCHEDULE B.2.A)
- 5. ALL PERMIT REGISTRANTS MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SCHEDULE A 8.A)
- 6. THE ESCP MEASURES SHOWN ON THIS PLAN ARE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, UPGRADE THESE MEASURES AS NEEDED TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL EROSION AND SEDIMENT CONTROL REGULATIONS. (SCHEDULE A.8.C.II.(1)(C))
- 7. SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT. (SCHEDULE A.12.C.III)
- 8. PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (SCHEDULE A 8.C.II.(1)(D))
- 9. IDENTIFY, MARK, AND PROTECT (BY FENCING OFF OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED. IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS. (SCHEDULE A.8.C.I.(1) & (2))
- 10. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED. (SCHEDULE A.7.B.III(1) AND A.7.B.III(3))
- 11. EROSION AND SEDIMENT CONTROL MEASURES INCLUDING PERIMETER SEDIMENT CONTROL MUST BE IN PLACE BEFORE VEGETATION IS DISTURBED AND MUST REMAIN IN PLACE AND BE MAINTAINED, REPAIRED, AND PROMPTLY IMPLEMENTED FOLLOWING PROCEDURES ESTABLISHED FOR THE DURATION OF CONSTRUCTION, INCLUDING PROTECTION FOR ACTIVE STORM DRAIN INLETS AND CATCH BASINS AND APPROPRIATE NON-STORMWATER POLLUTION CONTROLS. (SCHEDULE A.7.D.I AND A.8.C)
- 12. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (SCHEDULE A.8.C.I.(6))
- 13. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES AND FOR ALL ROADWAYS INCLUDING GRAVEL ROADWAYS. (SCHEDULE A.8.C.II.(2))
- 14. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. (SCHEDULE A.8.C.I.(7))
- 15. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMPS SUCH AS: GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMPS MUST BE IN PLACE PRIOR TO LAND-DISTURBING ACTIVITIES. (SCHEDULE A 7.D.II.(1) AND A.8.C.I(4))
- 16. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (SCHEDULE A.7.D.II.(3))
- 17. USE BMPS TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANTS FROM SPILLS: VEHICLE AND EQUIPMENT FUELING. MAINTENANCE. AND STORAGE: OTHER CLEANING AND MAINTENANCE ACTIVITIES; AND WASTE HANDLING ACTIVITIES THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, LEFTOVER PAINTS, SOLVENTS, AND GLUES FROM CONSTRUCTION OPERATIONS. (SCHEDULE A.7.E.I.(2))
- 18. IMPLEMENT THE FOLLOWING BMPS WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY. MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (SCH A 7.E.III.)
- 19. USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL. (SCHEDULE A 7.B.II)
- 20. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE. (SCHEDULE A.9.B.III)

						Reuse of Documents This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012
-	-	-			-	
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date	

Plot Date: 21 March 2012 - 8:43 AM

Plotted by: Keith Tolle

INSPECTION FREQUENCY:

JN	ΡĿ	RSONNEL	
ME	NT	CONTRO	

- 21. IF A STORMWATER TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN PLAN APPROVAL BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SCHEDULE A.9.D)
- 22. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR. (SCHEDULE A 7.B)
- 23. AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMPS MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEADING TO SURFACE WATERS. $(SCHEDULE \land 7.E.II.(2))$
- 24. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND CREATION OF BARE GROUND DURING WET WEATHER. (SCHEDULE A.7.A.I)
- 25. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (SCHEDULE A.9.C.I)
- 26. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT. AND BEFORE BMP REMOVAL. (SCHEDULE A.9.C.II)
- 27. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT. SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT. (SCHEDULE A.9.C.III & IV)
- 28. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DIVISION OF STATE LANDS REQUIRED TIMEFRAME. (SCHEDULE A.9.B.I)
- 29. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NOT OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (SCHEDULE A.9.B.II)
- 30. THE ENTIRE SITE MUST BE TEMPORARILY STABILIZED USING VEGETATION OR A HEAVY MULCH LAYER, TEMPORARY SEEDING, OR OTHER METHOD SHOULD ALL CONSTRUCTION ACTIVITIES CEASE FOR 30 DAYS OR MORE. (SCHEDULE A.7.F.I)
- 31. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR AN ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (SCHEDULE A.7.F.II)
- 32. PROVIDE PERMANENT EROSION CONTROL MEASURES ON ALL EXPOSED AREAS. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. HOWEVER, DO REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AS EXPOSED AREAS BECOME STABILIZED, UNLESS DOING SO CONFLICTS WITH LOCAL REQUIREMENTS. PROPERLY DISPOSE OF CONSTRUCTION MATERIALS AND WASTE, INCLUDING SEDIMENT RETAINED BY TEMPORARY BMPS. (SCHEDULE A.7.B.III(2) AND A.8.C.III)

ATTENTION EXCAVATORS:

OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CENTER. YOU MUST NOTIFY THE CENTER AT LEAST TWO BUSINESS DAYS BEFORE COMMENCING ANY EXCAVATION. CALL 503-246-6699.

TEMPORARY SEED MIX:

TEMPORARY GRASS COVER SHALL BE A DWARF GRAS MIX "PRO-TIME COMPANION" OR APPROVED EQUAL. GENERAL MIX SHALL BE AS FOLLOWS:

vS.		
	DWARF PERENNIAL RYEGRASS	
	CREEPING RED FESCUE	

80% BY SEED COUNT 20% BY SEED COUNT

100 MINIMUM PER ACRE

APPLICATION RATE

PERMANENT SEED MIX:


"SUNMARK SEEDS - CELEBRATION" AS FOLLOWS: 33.33% HALO PERENNIAL RYEGRASS 33.33% BUENA VISTA PERENNIAL RYEGRASS 33.33% FUSION PERENNIAL RYEGRASS


APPLICATION RATE

8 LBS/1000 FT²

SITE CONDITION	MINIMUM FREQUENCY
1. ACTIVE PERIOD	DAILY WHEN STORMWATER RUNOFF, INCLUDING RUNOFF FROM SNOWMELT, IS OCCURRING. AT LEAST ONCE EVERY TWO WEEKS, REGARDLESS OF WHETHER OR NOT RUNOFF IS OCCURRING.
2. PRIOR TO THE SITE BECOMING INACTIVE OR IN ANTICIPATION OF SITE INACCESSIBILITY.	ONCE TO ENSURE THAT EROSION AND SEDIMENT CONTROL MEASURES ARE IN WORKING ORDER. ANY NECESSARY MAINTENANCE AND REPAIR MUST BE MADE PRIOR TO LEAVING THE SITE.
3. INACTIVE PERIODS GREATER THAN FOURTEEN (14) CONSECUTIVE CALENDAR DAYS.	ONCE EVERY TWO (2) WEEKS.
4. PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER.	IF PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT ANI ACCESSIBLE DISCHARGE POINT OR DOWNSTREAM LOCATION.
	N PERSONNEL THAT INCLUDES THE EROSION CONTROL INSPECTOR. O C PERMIT REQUIREMENTS. O C PERMIT REQUIREMENTS.

	CLEARING	MASS GRADING	UTILITY INSTALLATION	STREET CONSTRUCTION	FINAL STABILIZATION	WET WEATHER (OCT. 1 - MAY 31
ROSION PROTECTION						
PRESERVE NATURAL VEGETATION	**X	X	Х		Х	Х
GROUND COVER						
HYDRAULIC APPLICATIONS						
PLASTIC SHEETING						
MATTING		Х			Х	
DUST CONTROL	Х	Х	Х		Х	
TEMPORARY / PERMANENT SEEDING		Х			Х	
BUFFER ZONE						
OTHER:						
EDIMENT CONTROL						
SEDIMENT FENCE (PERIMETER)	Х	Х	Х			Х
SEDIMENT FENCE (INTERIOR)						
STRAW WATTLES						
FILTER BERM						
INLET PROTECTION						
CURB SEDIMENT TRAPS						
DEWATERING						
SEDIMENT TRAP						
COMPOST BLANKET						
OTHER:						
RUN OFF CONTROL						
CONSTRUCTION ENTRANCE	**X	Х	Х			Х
PIPE SLOPE DRAIN						
OUTLET PROTECTION						
SURFACE ROUGHENING						
CHECK DAMS						
WHEEL WASH						
OTHER:						
OLLUTION PREVENTION						
PROPER SIGNAGE	**X	Х	Х		Х	
HAZ WASTE MGMT						
SPILL KIT ON-SITE	**X	Х	Х		Х	
CONCRETE WASHOUT AREA						
OTHER:						








GHD Inc. 15575 SW Sequoia Parkway Suite 140 Portland Oregon 97224 USA **T** 1 503 226 3921 **F** 1 503 226 3926 W www.ghd.com

REFER TO DEQ GUIDANCE MANUAL FOR A COMPREHENSIVE LIST OF AVAILABLE BMP'S.

PRELIMINARY

RT	WEST LINN BOLTON PF			CHOOL DISTRI	СТ		
MW	STREAMBA			N			
	EROSION C No. 11456-11012		NOTES				
ng shall not be used ction unless Signed For Construction	Drawing No:	C102			Sht	of Rev:	



			:			
						Reuse of Documents
						This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of GHD Inc. and shall not be reused in whole or
						in part for any other project without GHD Inc.'s written authorization. © GHD Inc. 2012
-	-	-			-	
No	Revision Note: * indicates signatures on original issue of drawing or last revision of drawing	Drawn	Job Manager	Project Director	Date	

Plot Date: 22 March 2012 - 5:09 PM Plotted by: Keith Tolle

Cad File No: O:\11456 - WLWSD (West Linn-Wilsonville School District)\11456-11012 WLWSD Bolton Primary School\06-CAD\Sheets\11456-11012_C200 EXIST-DEMO.dwg

HOUSE

15' ALLEY PER THE PLAT OF "MOODY INVESTMENT COMPANY'S PLAT OF HOLLY

	Drawn	KPT	Designer	PRT
GHD	Drafting Check		Design Check	DMW
GHD Inc.	Approve (Project	d Director)		
15575 SW Sequoia Parkway Suite 140 Portland Oregon 97224 USA	Date	03/06/12		
T 1 503 226 3921 F 1 503 226 3926 W www.ghd.com	Scale	AS SHOWN	for Cor	awing shall no struction unle aled For Cons


DEMOLITION NOTES


- (1) SAVE AND PROTECT EXISTING TREE
- (2) SAVE AND PROTECT EXISTING CREEK
- (3) SAVE AND PROTECT EXISTING FENCE
- (4) SAVE AND PROTECT EXISTING STRUCTURE
- 5 SAVE AND PROTECT EXISTING PLAYGROUND SURFACING, PLAY STRUCTURES, SAND BOXES AND BANDING CURB
- 6 REMOVE EXISTING CHAIN LINK FENCE
- (7) REMOVE EXISTING TREES
- 8 EXISTING DRAINAGE WAY TO BE FILLED (APPROXIMATELY 114 SF)

- (9) SAVE AND PROTECT EXISTING STORM DRAINAGE PIPE
- (10) REMOVE EXISTING VEGETATION, BRUSH, BLACKBERRIES, SMALL TREES, ETC.
- (1) CONTRACTOR TO PROTECT AND PRESERVE THE EXISTING PLAYGROUND AND UNDERDRAIN SYSTEM. DESIGN DRAWINGS AVAILABLE UPON REQUEST. CONTRACTOR TO PROVIDE CONSTRUCTION. STAGING AND ACCESS PLAN TO SHOW HOW THE PLAYGROUND AND UNDERDRAIN SYSTEM WILL BE PROTECTED FROM DAMAGE. PLAN SHALL BE SUBMITTED FOR REVIEW AND APPROVAL.

EROSION CONTROL NOTES


- WATER (OHW) BOUNDARY INSTALL 6" FROM OHW BOUNDARY LINE.
- 2 LIMITS OF CONSTRUCTION INSTALL ORANGE CONSTRUCTION FENCES.






Plot Date: 22 March 2012 - 5:13 PM

Plotted by: Keith Tolle




	Original Olze		\frown
Signed uction	Ansi D	Drawing No:	C400
		-	




Plot I	Date:	21 March 2012 - 8:40 AM	Plotted by:	Keith Tolle

Cad File No: O:\11456 - WLWSD (West Linn-Wilsonville School District)\11456-11012 WLWSD Bolton Prima

		1
ary School\06-CAD\Sheets\11456-11012	C500 DET.dv	٨





PLANTING AND IRRIGATION LEGEND



NATIVE RE-VEGETATION -EROSION CONTROL GRASS SEED MIX AND SHRUBS. 3-YR TEMPORARY IRRIGATION TO BE COMPLETED BY THE WILSONVILLE WEST LINN SCHOOL DISTRICT, NO AUTOMATIC IRRIGATION SYSTEM WILL BE INSTALLED.

EXISTING TREES TO REMAIN

LAND USE REQUIREMENTS

CODE REQUIREMENT	RESTORATION AREA	TOTAL REQUIRED	TOTAL PROVIDED
40 SHRUBS/1000 SF (5 FT O.C.)	6250 SF	250 EA	250 EA
7 TREES/1000 SF (12 FT O.C.)	6250 SF	44 EA	44 EA

PRELIMINARY LAND USE PERMIT PLANT SCHEDULE

SYMB	KEY	BOTANICAL NAME	COMMON NAME	SIZE/CONDITION	SPACING
and the second s	THPL	<u>Evergreen trees</u> Thuja plicata <u>Native/Adaptive trees</u>	WESTERN RED CEDAR	5'-6' HT	AS SHOWN
O ⊗ ⊖	ALRU AMAL FRLA QUGA	ALNUS RUBRA AMELANCHIER ALNIFOLIA FRAXINUS LATIFOLIA QUERCUS GARRYANA	RED ALDER WESTERN SERVICEBERRY OREGON ASH OREGON WHITE OAK	2 GAL. CONT. 5–6'HT/MULTI 1"CAL./B&B 1"CAL./B&B	AS SHOWN AS SHOWN AS SHOWN AS SHOWN
	SYAL RUPA SARA SPBE MAAQ FRVE MARE POMU	SHRUBS SYMPHORICARPOS ALBUS RUBUS PARVIFOLIA SAMBUCUS RACEMOSA SPIRAEA BETULIFOLIA MAHONIA AQUIFOLIUM GROUNDCOVER FRAGARIA VESCA MAHONIA REPENS POLYSTICHUM MUNITUM PROTIME 702 LOW PROFILE PLUS	SNOWBERRY THIMBLEBERRY RED ELDERBERRY BIRCH LEAF SPIREA TALL OREGON GRAPE WOODLAND STRAWBERRY CASCADE OREGON GRAPE WESTERN SWORD FERN EROSION CONTROL MIX	1 GAL. CONT.	48" O.C. 48" O.C. 48" O.C. 48" O.C. 18" O.C. – 50% OF MIX 24" O.C. – 35% OF MIX 24" O.C. – 15% OF MIX

				SCALE: 1"=10'-0" NORTH PRELIMINARY
	Drawn GD	Designer GD		WEST LINN WILSONVILLE SCHOOL DISTRICT BOLTON PRIMARY SCHOOL
	Drafting DO Check DO	Design DO Check DO		STREAMBANK REMEDIATION
	Approved (Project Director)			LANDSCAPE RESTORATION PLAN
JSA	Date03/06/12ScaleAS SHOWN	nine Branning entait net be abea	Contract Original Size Ansi D	Sht of

15575 SW Sequoia Parkway Suite 140 Portland Oregon 97224 USA T 1 503 226 3921 F 1 503 226 3926

PLANTING NOTES:

1. CONTRACTOR TO VERIFY LOCATION OF EXISTING TREES INDICATED TO REMAIN PRIOR TO SOIL PREPARATION. PROTECT ALL TREES AND SHRUBS INDICATED TO REMAIN. COORDINATE WITH THE OWNER'S REPRESENTATIVE.

2. PLANTING AREAS TO BE SUFFICIENTLY CLEANED OF ALL CONSTRUCTION MATERIALS, INCLUDING IMPORTED ROCK, TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE BEFORE BEGINNING ANY LANDSCAPE WORK.

3. IDENTIFY ALL PLANTING AREAS IN FIELD WITH WHITE FIELD-MARKING CHALK OR APPROVED EQUAL. PLANTING BEDS TO BE ADJUSTED AND APPROVED BY OWNER'S REPRESENTATIVE PRIOR TO PLANT LOCATION.

4. FOR PLANTING OCCURRING IN MASSES OF SAME SPECIES PLANT, LABELING REFERS TO ALL ADJACENT IDENTICAL SYMBOLS. REFER TO DETAILS AND LEGEND FOR SPACING INFORMATION.

5. THE OWNER'S REPRESENTATIVE WILL APPROVE INDIVIDUAL PLANT MATERIAL AND LOCATION OF PLANT MATERIAL PRIOR TO INSTALLATION. REFER TO SPECIFICATIONS FOR PROCEDURE.

6. PLANT QUANTITIES INDICATED ARE FOR THE CONVENIENCE OF THE CONTRACTOR ONLY. CONTRACTOR IS RESPONSIBLE FOR PROVIDING PLANTS IN QUANTITIES AND LOCATIONS SHOWN ON DRAWINGS.

7. PROVIDE GEOTEXTILE FABRIC AS DIRECTED BY THE CIVIL ENGINEER OR JUTE NETTING ON ALL SLOPES WITH GRADIENT OF 3:1 OR GREATER. STAPLE FABRIC TO GROUND PER MANUFACTURERS RECOMMENDATIONS OR WITH METAL STAKES AT 4' O.C.

8. VERIFY ALL EROSION CONTROL MEASURES ARE INSTALLED IN PLACE PRIOR TO START OF PLANTING.