

Main Bid - Sanitary Sewer Rehabilitation - Phase 3

Zone 4 Summary

	From MH #	To MH#	Length	# Laterals	Issues
VIEW DR	3D-4	3D-3	144.3	4	crack @135.4, outside drop 3D-3
	3D-4-1	3D-4	498.9	5	
Subtotal			643.2	9	
HILLCREST CT	3D-8-3	3D-8-2	312.3	3	roots at tap @ 3', cracked pipe & roots at 132.5
	3D-8-4	3D-8-3	28.3	1	
	3D-8-5	3D-8-4	241.1	4	126 to 131.6 is pvc & tap please line entire pipe, outside drop 3D-8-5
	3D-8-6	3D-8-5	212.3	3	
	3D-8-7	3D-8-6	97.4	2	
	3D-8-8	3D-8-7	123.2	1	
Subtotal			1014.6	14	
WILDWOOD DR	3D-18-3	3D-18-2	116.3	0	
	3D-18-4	3D-18-3	261.3	2	
	3D-18-5	3D-18-4	173.3	2	
	3D-18-6	3D-18-5	173.7	1	
Subtotal			724.6	5	
SUN CIR	3D-20-1	3D-20	391.7	8	plus one capped tap, outside drop 3D--20
	3D-20-2	3D-20-1	386.4	9	
Subtotal			778.1	17	
SUN CIR	3D-21	3D-20	120.2	2	
	3D-22	3D-21	101.1	3	
	3D-23	3D-22	217.5	4	
	3D-24	3D-23	131.7	4	
	3D-25	3D-24	404.3	10	
	3D-26	3D-25	185.8	3	
Subtotal			1160.6	26	
SUNBURST TERR	3D-26-3	3D-26-2	139.8	2	infiltration 70.8 to 79.5
	3D-26-4	3D-26-3	163.4	4	
	3D-26-5	3D-26-4	352.4	7	
Subtotal			655.6	13	
SUNCREST DR	3D-30	3D-29	143.9	2	
	3D-31	3D-30	89.9	1	
	3D-32	3D-31	211.6	5	
	3D-33	3D-32	211.2	4	
Subtotal			656.6	12	
SUNBURST TERR	3D-31-1	3D-31	329.5	2	possible main line decay @ 259.5, joint offset 320 pipe changes to PVC @ 320.6 please line entire pipe
Subtotal			329.5	2	
TOTAL ZONE 4			5962.8	98	