



**DIG OUT AND REPAIR  
APPROXIMATE AREA - 500SF  
TO BE MARKED BY THE CITY**

**NEW PAVEMENT  
EXACT DELINEATION TO BE  
MARKED BY THE CITY  
APPROXIMATE LENGTH - 500'  
APPROXIMATE WIDTH - 18'**

**MUNGER DRIVE**

**NOTES:**

PRE-LEVEL AC COURSE TO BE APPLIED AS DIRECTED BY THE CITY  
DIG OUT AND REPAIR: 3" OF AC OVER 12" OF ROCK PRIOR TO OVERLAY  
APPLY FABRIC AND 2" AC OVERLAY SIMILAR TO THE REST OF THE PROJECT

PROJECT NO. PW-1205  
DATE: 02/27/2012  
BY: BP  
SHEET NO. 3 OF 3

**PAVEMENT PROJECT 2012  
MUNGER DRIVE**

CITY OF WEST LINN - PUBLIC WORKS  
22500 SALAMO ROAD, NO. 800, WEST LINN, OREGON

**CITY OF WEST LINN  
PUBLIC WORKS**  
22500 SALAMO ROAD, NO. 800  
WEST LINN, OR 97068  
SCALE: NTS