




DIG OUT AND REPAIR TYPICAL SECTION

AREA TO BE MARKED OUT BY THE CITY.

REMOVE DAMAGED PAVEMENT AND SUBGRADE MATERIAL TO THE REQUIRED 18" DEPTH BY GRINDING OR SAW CUT AND EXCAVATION.

PLACE 4" HOT MIX AC MIN. WITH 2 x 2" LIFTS OVER 14' OF 1 1/2"-3" COMPACTED ROCK

EXISTING PAVEMENT




PAVEMENT REPAIR TYPICAL SECTION

AREA TO BE MARKED OUT BY THE CITY.

REMOVE DAMAGED PAVEMENT AND SUBGRADE MATERIAL TO THE REQUIRED 4" DEPTH BY GRINDING OR SAW CUT AND EXCAVATION.

PLACE 4" HOT MIX AC MIN. IN 2 x 2" LIFTS



PROJECT NO. PW-1205
 DATE: 02/27/2012
 BY: B.P.
 SHEET NO. 1 OF 3

PAVEMENT PROJECT 2012
 ROSEMONT ROAD

CITY OF WEST LINN - PUBLIC WORKS
 22500 SALAMO ROAD, NO. 800, WEST LINN, OREGON

CITY OF WEST LINN
PUBLIC WORKS

22500 SALAMO ROAD, NO. 800
 WEST LINN, OR 97068
 SCALE: NTS