


CITY OF
**West
Linn**

CITY OF WEST LINN BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06

SEPTEMBER 2015 VOLUME 2 OF 2




TAX LOT 21E25AD07100
TOWNSHIP 2 SOUTH, RANGE 1 EAST, SECTION 25AD
WILLAMETTE MERIDIAN, CITY OF WEST LINN,
CLACKAMAS COUNTY, OREGON

RESERVOIR SITE ADDRESS:
6111 SKYLINE DRIVE
WEST LINN, OREGON 97068

LOCATION MAP
SCALE: 1"=2,000'

ATTENTION: OREGON LAW REQUIRES THE CONTRACTOR TO FOLLOW THE RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. THE CONTRACTOR MAY OBTAIN COPIES OF THE RULES BY CALLING THE UTILITY NOTIFICATION CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 503-232-1987.) THE ONE-CALL NUMBER IS 1-800-332-2344.

MSA Murray, Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900 PHONE 503-225-9010
Portland, Oregon 97204 FAX 503-225-9022



VICINITY MAP
SCALE: 1"=1,000'

INDEX OF DRAWINGS

GENERAL

- 1 G-1 COVER SHEET, LOCATION AND VICINITY MAPS
- 2 G-2 INDEX OF DRAWINGS AND ODOT STANDARD DRAWING INDEX
- 3 G-3 SYMBOLS AND LEGEND
- 4 G-4 ABBREVIATIONS
- 5 G-5 GENERAL NOTES
- 6 G-6 PROJECT OVERVIEW

EROSION AND SEDIMENT CONTROL

- 7 ESC-1 EROSION AND SEDIMENT CONTROL COVER SHEET
- 8 ESC-2 EROSION AND SEDIMENT CONTROL SCHEDULES A & B - INITIAL CLEARING AND GRADING
- 9 ESC-3 EROSION AND SEDIMENT CONTROL SCHEDULES A & B - CONSTRUCTION AND FINAL GRADING
- 10 ESC-4 EROSION AND SEDIMENT CONTROL SCHEDULES A & B - TYPICAL PIPELINE INSTALLATION MEASURES
- 11 ESC-5 EROSION AND SEDIMENT CONTROL SCHEDULE D PLAN - 1
- 12 ESC-6 EROSION AND SEDIMENT CONTROL SCHEDULE D PLAN - 2
- 13 ESC-7 EROSION AND SEDIMENT CONTROL SCHEDULE D PLAN - 3
- 14 ESC-8 EROSION AND SEDIMENT CONTROL SCHEDULE D PLAN - 4
- 15 ESC-9 EROSION AND SEDIMENT CONTROL ALL SCHEDULES - STANDARD DETAILS - 1
- 16 ESC-10 EROSION AND SEDIMENT CONTROL ALL SCHEDULES - STANDARD DETAILS - 2

SCHEDULE A - RESERVOIR

CIVIL

- 17 C-A1 RESERVOIR SITE LAYOUT PLAN
- 18 C-A2 RESERVOIR SITE TREE PROTECTION AND REMOVAL PLAN
- 19 C-A3 RESERVOIR SITE DEMOLITION PLAN
- 20 C-A4 RESERVOIR SITE GRADING AND ACCESS ROAD PAVING PLAN
- 21 C-A5 ACCESS ROAD DETAILS
- 22 C-A6 RESERVOIR SECTION AND UNDERDRAIN DETAILS
- 23 C-A7 RESERVOIR PIPING AND FLOOR PLAN
- 24 C-A8 RESERVOIR SITE WATER PIPING PLAN AND DETAILS
- 25 C-A9 RESERVOIR SITE WATER PIPING PROFILES AND CALL-OUTS
- 26 C-A10 RESERVOIR SITE DRAIN PIPING PLAN AND CALL-OUTS
- 27 C-A11 RESERVOIR SITE DRAIN PIPING PROFILES AND MANHOLE DETAILS
- 28 C-A12 VALVE VAULT PLAN AND SECTION
- 29 C-A13 STORMWATER DETENTION FACILITY DETAILS
- 30 C-A14 STORMWATER SWALE DETAILS
- 31 C-A15 STORMWATER DETAILS
- 32 C-A16 MISCELLANEOUS SITEWORK DETAILS
- 33 C-A17 MISCELLANEOUS DETAILS
- 34 C-A18 FENCING DETAILS - 1
- 35 C-A19 FENCING DETAILS - 2
- 36 C-A20 RESERVOIR SITE ACCESS ROAD VERTICAL PROFILES

ARCHITECTURAL

- 37 A-A1 RESERVOIR EXTERIOR FINISH WORK

STRUCTURAL

- 38 S-A1 RESERVOIR GENERAL STRUCTURAL NOTES
- 39 S-A2 RESERVOIR QUALITY CONTROL PLAN
- 40 S-A3 RESERVOIR ROOF AND FLOOR PLANS
- 41 S-A4 RESERVOIR SECTION AND COLUMN DETAILS
- 42 S-A5 RESERVOIR ROOF SLAB REINFORCING DETAILS
- 43 S-A6 RESERVOIR ROOF HATCH AND SLAB JOINT REINFORCING DETAILS
- 44 S-A7 PRESTRESSED RESERVOIR WALL SECTIONS & DETAILS
- 45 S-A8 PRESTRESSED RESERVOIR WALL ELEVATION & DETAILS
- 46 S-A9 MISCELLANEOUS RESERVOIR DETAILS & PRESTRESSING NOTES
- 47 S-A10 RESERVOIR FOUNDATION AND PIPE BLOCK DETAILS
- 48 S-A11 RESERVOIR INTERIOR LADDER AND HATCH DETAILS
- 49 S-A12 RESERVOIR EXTERIOR ROOF ACCESS STAIRWAY
- 50 S-A13 RESERVOIR EXTERIOR ROOF ACCESS STAIRWAY
- 51 S-A14 RESERVOIR INLET/OUTLET PIPING DETAILS
- 52 S-A15 RESERVOIR OVERFLOW/DRAIN PIPING DETAILS
- 53 S-A16 RESERVOIR ROOF VENT DETAILS

MECHANICAL

- 54 M-A1 RESERVOIR INLET MIXING SYSTEM DETAILS

LANDSCAPING

- 55 L-A1 RESERVOIR LANDSCAPE PLAN
- 56 L-A2 PLANTING DETAILS

SCHEDULE B - PUMP STATION IMPROVEMENTS

ARCHITECTURAL

- 57 A-B1 EXISTING ROOF DEMO PLAN AND PROPOSED ROOF PLAN
- 58 A-B2 ARCHITECTURAL ELEVATIONS
- 59 A-B3 ARCHITECTURAL DETAILS - 1

STRUCTURAL

- 60 S-B1 PUMP STATION GENERAL STRUCTURAL NOTES
- 61 S-B2 PUMP STATION BUILDING PLAN, SECTION AND DETAILS

MECHANICAL

- 62 M-B1 EXISTING PUMP STATION DEMOLITION PLAN
- 63 M-B2 PROPOSED PUMP STATION PLAN
- 64 M-B3 EXISTING AND PROPOSED PUMP STATION SECTION VIEWS - 1
- 65 M-B4 EXISTING AND PROPOSED PUMP STATION SECTION VIEWS - 2

ELECTRICAL

- 66 E-B1 ELECTRICAL LEGEND AND ABBREVIATION
- 67 E-B2 ELECTRICAL SITE PLAN
- 68 E-B3 ELECTRICAL DETAILS
- 69 E-B4 ELECTRICAL CIRCUIT AND PANEL SCHEDULES
- 70 E-B5 ELECTRICAL PLAN PUMP STATION
- 71 E-B6 PUMP NO. 1 SCHEMATIC
- 72 E-B7 ONE-LINE DIAGRAM

INSTRUMENTATION AND CONTROL

- 73 IC-B1 BLOCK DIAGRAM PUMPING SYSTEMS
- 74 IC-B2 BLOCK DIAGRAM ANCILLARY SYSTEMS
- 75 IC-B3 NETWORK DIAGRAM LOCAL AND WIDE AREA CONNECTIONS
- 76 IC-B4 P&ID PROCESS CONTROLS
- 77 IC-B5 PRESENTATION TREMOTE TELEMETRY UNIT
- 78 IC-B6 MCC FIELD WIRING 3UF7 ADDITION
- 79 IC-B7 MCC FIELD WIRING 3UF7 ADDITION

SCHEDULE C - WATER MAIN REPLACEMENTS

CIVIL

- 80 C-C1 WATER MAIN REPLACEMENT KEY MAP
- 81 C-C2 WATER MAIN REPLACEMENT ALIGNMENT 'A' & 'B' PLAN AND PROFILE, STA A1+00 TO STA A4+60
- 82 C-C3 WATER MAIN REPLACEMENT ALIGNMENT 'A', 'B' & 'C' PLAN AND PROFILE, STA A4+60 TO STA A8+40
- 83 C-C4 WATER MAIN REPLACEMENT ALIGNMENT 'A' & 'C' PLAN AND PROFILE, STA A8+40 TO STA A12+40
- 84 C-C5 WATER MAIN REPLACEMENT ALIGNMENT 'A' & 'C' PLAN AND PROFILE, STA A12+40 TO STA A16+80
- 85 C-C6 WATER MAIN REPLACEMENT ALIGNMENT 'A' PLAN AND PROFILE, STA A16+80 TO STA A21+80
- 86 C-C7 WATER MAIN REPLACEMENT ALIGNMENT 'A' PLAN AND PROFILE, STA A21+80 TO STA A26+60
- 87 C-C8 WATER MAIN REPLACEMENT ALIGNMENT 'A' PLAN AND PROFILE, STA A26+60 TO STA A30+60
- 88 C-C9 WATER MAIN REPLACEMENT ALIGNMENT 'A' & 'H' PLAN AND PROFILE STA A30+60 TO STA A33+26 AND STA H1+00 TO STA H2+31
- 89 C-C10 WATER MAIN REPLACEMENT ALIGNMENT 'C' AND 'G' PLAN AND PROFILE, STA C1+00 TO STA C4+40 AND STA G1+00 TO STA G2+20
- 90 C-C11 WATER MAIN REPLACEMENT ALIGNMENT 'C' PLAN AND PROFILE, STA C4+40 TO STA C7+40
- 91 C-C12 PIPING CONNECTION DETAILS

SCHEDULE D - SKYLINE DRIVE STREET IMPROVEMENTS

CIVIL

- 92 C-D1 ALIGNMENT AND GRADING PLAN - 1
- 93 C-D2 ALIGNMENT AND GRADING PLAN - 2
- 94 C-D3 ALIGNMENT AND GRADING PLAN - 3
- 95 C-D4 ALIGNMENT AND GRADING PLAN - 4
- 96 C-D5 ALIGNMENT AND GRADING PLAN - 5
- 97 C-D6 ALIGNMENT AND GRADING PLAN - 6
- 98 C-D7 ALIGNMENT AND GRADING PLAN - 7
- 99 C-D8 ALIGNMENT AND GRADING PLAN - 8
- 100 C-D9 ALIGNMENT AND GRADING PLAN - 9
- 101 C-D10 STREET IMPROVEMENTS PLAN - 1
- 102 C-D11 STREET IMPROVEMENTS PLAN - 2
- 103 C-D12 STREET IMPROVEMENTS PLAN - 3
- 104 C-D13 STREET IMPROVEMENTS PLAN - 4
- 105 C-D14 STREET IMPROVEMENTS PLAN - 5
- 106 C-D15 STREET IMPROVEMENTS PLAN - 6
- 107 C-D16 STREET IMPROVEMENTS PLAN - 7
- 108 C-D17 STREET IMPROVEMENTS PLAN - 8
- 109 C-D18 STREET IMPROVEMENTS PLAN - 9
- 110 C-D19 STREET IMPROVEMENTS PROFILES - 1
- 111 C-D20 STREET IMPROVEMENTS PROFILES - 2
- 112 C-D21 STREET IMPROVEMENTS PROFILES - 3
- 113 C-D22 STREET IMPROVEMENTS PROFILES - 4
- 114 C-D23 STREET IMPROVEMENTS PROFILES - 5
- 115 C-D24 STORMWATER AND UTILITIES PLAN - 1
- 116 C-D25 STORMWATER AND UTILITIES PLAN - 2
- 117 C-D26 STORMWATER AND UTILITIES PLAN - 3
- 118 C-D27 STORMWATER AND UTILITIES PLAN - 4
- 119 C-D28 STORMWATER AND UTILITIES PLAN - 5
- 120 C-D29 STORMWATER AND UTILITIES PLAN - 6
- 121 C-D30 STORMWATER AND UTILITIES PLAN - 7
- 122 C-D31 STORMWATER AND UTILITIES PLAN - 8
- 123 C-D32 STORMWATER AND UTILITIES PLAN - 9
- 124 C-D33 TYPICAL ROAD SECTIONS - 1
- 125 C-D34 TYPICAL ROAD SECTIONS - 2
- 126 C-D35 TYPICAL ROAD SECTIONS - 3
- 127 C-D36 TYPICAL ROAD SECTIONS - 4
- 128 C-D37 TYPICAL ROAD SECTIONS - 5

- 129 C-D38 CIVIL DETAILS - 1 RETAINING WALL
- 130 C-D39 CIVIL DETAILS - 2 MISCELLANEOUS DETAILS
- 131 C-D40 CIVIL DETAILS - 3 MISCELLANEOUS DETAILS
- 132 C-D41 CIVIL DETAILS - 4 MISCELLANEOUS DETAILS
- 133 C-D42 CIVIL DETAILS - 5 CROSS SECTIONS
- 134 C-D43 CIVIL DETAILS - 6 CROSS SECTIONS
- 135 C-D44 CIVIL DETAILS - 7 CROSS SECTIONS
- 136 C-D45 CIVIL DETAILS - 8 CROSS SECTIONS
- 137 C-D46 CIVIL DETAILS - 9 CROSS SECTIONS
- 138 C-D47 CIVIL DETAILS - 10 CROSS SECTIONS
- 139 C-D48 CIVIL DETAILS - 11 CROSS SECTIONS

TRAFFIC CONTROL

- 140 TC-D1 TRAFFIC CONTROL STAGING PLAN
- 141 TC-D2 TRAFFIC CONTROL DETOUR AND ROAD CLOSURE PLAN

SIGNING AND STRIPING

- 142 S-D1 SIGNING AND STRIPING PLAN - 1
- 143 S-D2 SIGNING AND STRIPING PLAN - 2
- 144 S-D3 SIGNING AND STRIPING PLAN - 3
- 145 S-D4 SIGNING AND STRIPING PLAN - 4
- 146 S-D5 SIGNING AND STRIPING PLAN - 5
- 147 S-D6 SIGNING AND STRIPING PLAN - 6

LANDSCAPING

- 148 L-D1 SKYLINE DR LANDSCAPE PLAN-1
- 149 L-D2 SKYLINE DR LANDSCAPE PLAN-2
- 150 L-D3 SKYLINE DR LANDSCAPE PLAN-3
- 151 L-D4 SKYLINE DR LANDSCAPE PLAN-4
- 152 L-D5 SKYLINE DR LANDSCAPE PLAN-5
- 153 L-D6 SKYLINE DR LANDSCAPE PLAN-6
- 154 L-D7 SKYLINE DR LANDSCAPE PLAN-7
- 155 L-D8 SKYLINE DR LANDSCAPE PLAN-8


DETAILS (SCHEDULES A, B & C)

- 156 DET-1 CITY STANDARD DETAILS - 1
- 157 DET-2 CITY STANDARD DETAILS - 2
- 158 DET-3 CITY STANDARD DETAILS - 3
- 159 DET-4 CITY STANDARD DETAILS - 4
- 160 DET-5 CITY STANDARD DETAILS - 5
- 161 DET-6 CITY STANDARD DETAILS - 6
- 162 DET-7 CITY STANDARD DETAILS - 7
- 163 DET-8 CITY STANDARD DETAILS - 8
- 164 DET-9 CITY STANDARD DETAILS - 9
- 165 DET-10 CORROSION CONTROL DETAILS - 1
- 166 DET-11 CORROSION CONTROL DETAILS - 2
- 167 DET-12 CORROSION CONTROL DETAILS - 3

ODOT STANDARD DRAWINGS (SCHEDULE D)

- RD100, RD101, RD140, RD150, RD160
- RD300, RD302, RD306, RD312, RD317, RD318, RD325, RD326, RD335, RD336, RD339, RD344, RD345, RD356, RD364, RD365, RD370, RD371, RD373, RD380, RD386
- RD610
- RD700, RD715, RD720, RD755, RD756, RD759
- RD815
- TM500, TM501, TM503, TM520, TM521, TM530, TM531, TM560, TM561
- TM800, TM810, TM820, TM821, TM840, TM841, TM850

DRAWING NAMING SYSTEM:



g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\GENERAL\14-1586-OR-GEN.dwg G-2 9/4/2015 8:34 AM HCM 20.0s (LMS Tech)

| | | | | | |
|-----|------|----------|----|---------------|-----|
| NO. | DATE | REVISION | BY | SHEET | G-2 |
| | | | | | |
| | | | | DESIGNED: MLM | |
| | | | | DRAWN: DKH | |
| | | | | CHECKED: TPB | |
| | | | | APPROVED: TPB | |

VERT: AS SHOWN
 HORIZ: AS SHOWN

SCALE: 0 1
 NOTICE: IF THIS BAR DOES NOT SCALE, THEN DRAWING IS NOT TO SCALE.

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE: INDEX OF DRAWINGS AND ODOT STANDARD DRAWING INDEX

Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE: 503-225-9010
 FAX: 503-225-9022

DATE: SEPTEMBER 2015

MSA PROJECT: 14-1586

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\GENERAL\14-1586-OR-GEN.dwg G-3 9/3/2015 9:58 AM HCM HCV 20.0s (LMS Tech)

PIPE SYMBOLS

| PLANT | SCHEMATIC | DESCRIPTION |
|-------|-----------|---|
| | | WELDED JOINT |
| | | FLANGED JOINT |
| | | GROOVED END JOINT |
| | | MECHANICAL JOINT |
| | | PUSH-ON JOINT (RUBBER GASKET) |
| | | FLANGED COUPLING ADAPTER |
| | | DOUBLE BALL FLEXIBLE EXTENSION COUPLING |
| | | FLEXIBLE COUPLING W/ THRUST RING |
| | | ELBOW UP |
| | | ELBOW DOWN |
| | | TEE UP |
| | | TEE DOWN |
| | | LATERAL UP |
| | | LATERAL DOWN |
| | | CONCENTRIC REDUCER |
| | | ECCENTRIC REDUCER |
| | | UNION |
| | | BLIND FLANGE |
| | | CAP |
| | | LONG SLEEVE |
| | | FLEXIBLE COUPLING |
| | | CAPPED END OR PLUGGED END |
| | | FITTING |

VALVE SYMBOLS


| PLANT | SCHEMATIC | DESCRIPTION |
|-------|-----------|--|
| | | BUTTERFLY VALVE |
| | | GATE VALVE |
| | | GLOBE VALVE |
| | | BALL VALVE |
| | | BALANCING VALVE |
| | | DIAPHRAGM VALVE |
| | | PLUG VALVE (TOP) |
| | | PLUG VALVE (SIDE) |
| | | 3-WAY PLUG VALVE |
| | | SWING CHECK VALVE |
| | | DOUBLE CHECK ASSEMBLY |
| | | BALL SWING CHECK |
| | | SILENT CHECK VALVE |
| | | PRESSURE REDUCING VALVE |
| | | ALTITUDE CONTROL VALVE |
| | | SOLENOID VALVE |
| | | RELIEF VALVE |
| | | NEEDLE VALVE |
| | | HOSE VALVE |
| | | REDUCED PRESSURE BACKFLOW PREVENTER W/ GATE VALVES |
| | | HOSE BIBB |

TOPOGRAPHIC LEGEND


| | EXISTING | PROPOSED | EXISTING | PROPOSED |
|---------------------------|--------------|----------------|------------------------------------|----------|
| WATERLINE | ---10"W--- | ---12" DI W--- | TREE DECIDUOUS | |
| UNDERGROUND POWER | ---UGP--- | | TREE CONIFEROUS | |
| OVERHEAD POWER | ---OHP--- | | TREE TO BE REMOVED | |
| GAS | ---4"G--- | | BENCHMARK | |
| TELEPHONE/TELEMETRY | ---T--- | | IRON ROD | |
| CABLE TELEVISION | ---CATV--- | | CONTOUR MINOR | |
| SANITARY SEWER LINE | ---8"SS--- | | CONTOUR MAJOR | |
| SANITARY SEWER FORCE MAIN | ---6"FM--- | | SURFACE ELEVATION | |
| STORM DRAIN | ---8"SD--- | ---8"SD--- | TOE OF SLOPE | |
| CULVERT | ---CUL--- | ---CUL--- | TOP OF CUT | |
| ABANDON PIPE | ---ABAND--- | +++++ | EDGE OF PAVEMENT/AC | |
| REMOVE PIPE/STRUCTURE | ---REMOVE--- | ***** | EDGE OF GRAVEL | |
| DRAINAGE DITCH | ---DITCH--- | ---DITCH--- | CURB | |
| BARBWARE FENCE | ---X X X--- | ---BARB--- | SIDEWALK | |
| CHAIN LINK FENCE | ---O O O--- | ---CHAIN--- | SAWCUT | |
| DECORATIVE METAL FENCING | ---DECOR--- | ---METAL--- | AC BERM | |
| TEMPORARY SILT FENCE | ---SILT--- | ---TEMP--- | AC PAVING | |
| GUARDRAIL | ---GUARD--- | ---GUARD--- | 0"-2" TAPER GRIND SHOWN THUS: | |
| ROCK WALL | ---ROCK--- | ---ROCK--- | 2" GRIND SHOWN THUS: | |
| RETAINING WALL | ---RETAIN--- | ---RETAIN--- | 6" GRIND SHOWN THUS: | |
| TREE/BUSH LINE | ---TREE--- | ---TREE--- | REMOVE EXIST SURFACING SHOWN THUS: | |
| CENTERLINE | ---CENT--- | ---CENT--- | | |
| EASEMENT/PROPERTY LINE | ---EASE--- | ---EASE--- | | |
| RIGHT-OF-WAY | ---ROW--- | ---ROW--- | | |
| STRUCTURE OR FACILITY | ---STRUCT--- | ---STRUCT--- | | |
| MANHOLE | | | | |
| CLEAN-OUT | | | | |
| CATCH BASIN | | | | |
| CATCH BASIN (AT CURB) | | | | |
| FIELD INLET | | | | |
| CURB DOOR | | | | |
| THRUST BLOCK | | | | |
| VALVE | | | | |
| AIR INJECTION ASSEMBLY | | | | |
| BLOW-OFF ASSEMBLY | | | | |
| AIR RELEASE ASSEMBLY | | | | |
| FIRE HYDRANT ASSEMBLY | | | | |
| TEST STATION | | | | |
| WATER METER | | | | |
| GUY WIRE | | | | |
| LIGHT POST | | | | |
| MAILBOX | | | | |
| PULL BOX/JUNCTION BOX | | | | |
| SIGN | | | | |
| TELEPHONE JUNCTION BOX | | | | |
| TELEPHONE VAULT/MANHOLE | | | | |
| TRAFFIC SIGNAL CABINET | | | | |
| UTILITY POLE | | | | |

SECTION AND DETAIL DESIGNATIONS

SECTION DESIGNATIONS



DETAIL DESIGNATIONS



* NOTE: IF PLAN AND SECTION FOR DETAIL CALL-OUT AND DETAIL ARE SHOWN ON THE SAME DRAWING, DRAWING NUMBER IS REPLACED WITH A DASH.

MISCELLANEOUS PIPING SYMBOLS

| | |
|--|-------------------------|
| | STRAINER |
| | SIGHT GLASS |
| | PRESSURE GAUGE W/ COCK |
| | PRESSURE SWITCH W/ COCK |
| | METER |
| | SLIP-ON JOINT PIPE |
| | RESTRAINED JOINT PIPE |

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: SYMBOLS AND LEGEND

DATE: SEPTEMBER 2015

Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 800
Portland, Oregon 97204
PHONE: 503-255-0110
FAX: 503-255-0122

DESIGNED: MLM
DRAWN: DKH
CHECKED: TPB
APPROVED: TPB

NO. DATE REVISION

BY

SHEET G-3

3 of 167

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\GENERAL\14-1586-OR-GEN.dwg, C-4, 9/3/2015 9:58 AM HCM 20.0s (LMS Tech)

| | |
|----------|---|
| AAASHTO | AT AMERICAN ASSOCIATION OF STATE HIGHWAY & TRANSPORTATION OFFICIALS |
| AB | ANCHOR BOLT |
| ABAN (D) | ABANDON (ED) |
| ABS | ACRYLONITRILE BUTADIENE STYRENE |
| ABV | ABOVE |
| AC | ASPHALTIC CONCRETE |
| ACP | ASPHALTIC CONCRETE PAVING |
| ADJ | ADJUSTABLE |
| ADJC | ADJACENT |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AHR | ANCHOR |
| AL | ALUMINUM |
| ALIGN | ALIGNMENT |
| ALT | ALTERNATE |
| AMP | AMPERE |
| ANSI | AMERICAN NATIONAL STANDARDS INSTITUTE |
| APPROX | APPROXIMATE |
| APPVD | APPROVED |
| APWA | AMERICAN PUBLIC WORKS ASSOCIATION |
| ARCH | ARCHITECTURAL |
| ARV | AIR RELEASE VALVE |
| ASCE | AMERICAN SOCIETY OF CIVIL ENGINEERS |
| ASSN | ASSOCIATION |
| ASSY | ASSEMBLY |
| ASTM | AMERICAN SOCIETY FOR TESTING & MATERIALS |
| ATM | ATMOSPHERE |
| AUTO | AUTOMATIC |
| AUX | AUXILIARY |
| AVE | AVENUE |
| AVG | AVERAGE |
| AWWA | AMERICAN WATER WORKS ASSOCIATION |
| B&S | BELL & SPIGOT |
| BC | BOTTOM OF CURB / BOLT CIRCLE |
| BCR | BEGIN CURB RETURN |
| BD | BOARD |
| BETW | BETWEEN |
| BF | BOTH FACE |
| BFD | BACKFLOW PREVENTION DEVICE |
| BFILL | BACKFILL |
| BFV | BUTTERFLY VALVE |
| BHP | BRAKE HORSEPOWER |
| BKGD | BACKGROUND |
| BLDG | BUILDING |
| BLK | BLOCK |
| BLVD | BOULEVARD |
| BM | BENCHMARK / BEAM |
| BMP | BEST MANAGEMENT PRACTICE |
| BO | BLOWOFF |
| BOC | BACK OF CURB |
| BOW | BACK OF WALK |
| BR | BREAK |
| BS | BOTH SIDES |
| BSMT | BASEMENT |
| BTF | BOTTOM FACE |
| BTU | BRITISH THERMAL UNIT |
| BV | BALL VALVE |
| BW | BACK OF WALK / BOTH WAYS |
| C | CELSIUS |
| C TO C | CENTER TO CENTER |
| CARV | COMBINATION AIR RELEASE VALVE |
| CATV | CABLE TELEVISION |
| CB | CATCH BASIN |
| CCP | CONCRETE CYLINDER PIPE |
| CCW | COUNTER CLOCKWISE |
| CFM | CUBIC FEET PER MINUTE |
| CFS | CUBIC FEET PER SECOND |
| CHAN | CHANNEL |
| CHEM | CHEMICAL |
| CHFR | CHAMFER |
| CHKV | CHECK VALVE |
| CI | CAST IRON |
| CIP | CAST IRON PIPE |
| CIPC | CAST IN PLACE CONCRETE |
| CIR | CIRCLE |
| CISP | CAST IRON SOIL PIPE |
| CJ | CONSTRUCTION JOINT |
| CL or C | CENTER LINE |
| CL2 | CHLORINE |
| CLG | CEILING |
| CLJ | CONTROL JOINT |
| CLR | CLEAR |
| CLSM | CONTROLLED LOW STRENGTH MATERIAL |
| CMP | CORRUGATED METAL PIPE |
| CMU | CONCRETE MASONRY UNIT |
| CND | CONDUIT |
| CO | CLEANOUT |
| COL | COLUMN |
| COMB | COMBINATION |
| CONC | CONCRETE |
| CONN | CONNECTION |
| CONST | CONSTRUCTION |
| CONT | CONTINUOUS / CONTINUATION |
| CONTR | CONTRACT (OR) |
| COORD | COORDINATE |

| | |
|-----------|--------------------------------------|
| COP | COPPER |
| CORP | CORPORATION |
| CORR | CORRUGATED |
| COWG | CITY OF WEST LINN |
| CP | CONTROL POINT |
| CPLG | COUPLING (S) |
| CPVC | CHLORINATED POLYVINYL CHLORIDE |
| CR | CRUSHED ROCK |
| CS | COMBINED SEWER |
| CSP | CONCRETE SEWER PIPE |
| CT | COURT |
| CTL | CENTURY LINK |
| CTR | CENTER |
| CU | CUBIC |
| CULV | CULVERT |
| CV | CONTROL VALVE |
| CW | CLOCKWISE / COLD WATER |
| CY | CUBIC YARDS |
| CYL | CYLINDER LOCK |
| D | DRAIN |
| DC | DIRECT CURRENT |
| DEFL | DEFLECTION |
| DET | DETAIL |
| DI | DUCTILE IRON |
| DIA | DIAMETER |
| DIM | DIMENSION |
| DIR | DIRECTION |
| DIST | DISTANCE |
| DN | DOWN |
| DR | DRIVE |
| DS | DOWNSPOUT |
| DWG | DRAWING |
| DWL | DOWEL |
| DWV | DRAIN WASTE AND VENT |
| DWY / D/W | DRIVEWAY |
| EA | EACH |
| ECC | ECCENTRIC |
| ECR | END CURB RETURN |
| EF | EACH FACE |
| EIFS | EXTERIOR INSULATION FINISHING SYSTEM |
| EL | ELEVATION |
| ELB | ELBOW |
| ELEC | ELECTRICAL |
| ENCL | ENCLOSURE |
| EOP | EDGE OF PAVEMENT |
| EQ | EQUAL |
| EQL SP | EQUALLY SPACED |
| EQUIP | EQUIPMENT |
| ESMT | EASEMENT |
| EW | EACH WAY |
| EXC | EXCAVATE |
| EXIST | EXISTING |
| EXIST GR | EXISTING GRADE |
| EXP | EXPANSION |
| EXP BT | EXPANSION BOLT |
| EXP JT | EXPANSION JOINT |
| EXT | EXTERIOR |
| F | FAHRENHEIT |
| F TO F | FACE TO FACE |
| FAB | FABRICATE |
| FB | FLAT BAR |
| FCA | FLANGED COUPLING ADAPTER |
| FCO | FLOOR CLEANOUT |
| FD | FLOOR DRAIN |
| FDN | FOUNDATION |
| FEXT | FIRE EXTINGUISHER |
| FF | FAR FACE |
| FGL | FIBERGLASS |
| FH | FIRE HYDRANT |
| FIN FL | FINISH FLOOR |
| FIN GR | FINISH GRADE |
| FIPT | FEMALE IRON PIPE THREAD |
| FITG | FITTING |
| FL | FLOOR LINE |
| FLEX | FLEXIBLE |
| FLG | FLANGE |
| FLL | FLOW LINE |
| FLR | FLOOR |
| FM | FORCE MAIN |
| FO | FIBER OPTIC |
| FOC | FACE OF CONCRETE |
| FOF | FACE OF FINISH |
| FOM | FACE OF MASONRY |
| FOS | FACE OF STUDS |
| FPM | FEET PER MINUTE |
| FPS | FEET PER SECOND |
| FRP | FIBERGLASS REINFORCED PLASTIC |
| FT | FEET / FOOT |
| FTG | FOOTING |
| FUT | FUTURE |
| FW | FACE OF WALK |
| FXTR | FIXTURE |
| G | GAS |
| GA | GAUGE |
| GAL | GALLON |
| GALV | GALVANIZED |
| GC | GROOVED COUPLING |
| GFA | GROOVED FLANGE ADAPTER |
| GI | GALVANIZED IRON |
| GIP | GALVANIZED IRON PIPE |

| | |
|-------|--|
| GJ | GRIP JOINT |
| GL | GLASS |
| GLV | GLOBE VALVE |
| GND | GROUND |
| GPD | GALLONS PER DAY |
| GPH | GALLONS PER HOUR |
| GPM | GALLONS PER MINUTE |
| GPS | GALLONS PER SECOND |
| GR | GRADE |
| GR LN | GRADE LINE |
| GRTG | GRATING |
| GV | GATE VALVE |
| GRVL | GRAVEL |
| GYP | GYPSPUM |
| HB | HOSE BIBB |
| HC | HOLLOW CORE |
| HDPE | HIGH DENSITY POLYETHYLENE |
| HDR | HEADER |
| HDWE | HARDWARE |
| HGR | HANGER |
| HGT | HEIGHT |
| HH | HANDHOLD |
| HM | HOLLOW METAL |
| HNDRL | HAND RAIL |
| HOA | HAND-OFF-AUTO |
| HOR | HAND-OFF-REMOTE |
| HORIZ | HORIZONTAL |
| HP | HIGH PRESSURE / HORSEPOWER |
| HPG | HIGH PRESSURE GAS |
| HPT | HIGH POINT |
| HR | HOUR |
| HSB | HIGH STRENGTH BOLT |
| HV | HOSE VALVE |
| HVAC | HEATING, VENTILATION, AIR CONDITIONING |
| HWL | HIGH WATER LINE |
| HWY | HIGHWAY |
| HYD | HYDRANT |
| HYDR | HYDRAULIC |
| I&C | INSTRUMENTATION & CONTROL |
| I&AW | IN ACCORDANCE WITH |
| ID | INSIDE DIAMETER |
| IE | INVERT ELEVATION |
| IF | INSIDE FACE |
| IMPVT | IMPROVEMENT |
| IN | INCH |
| INCC | INCLUDE (D) (ING) |
| INFL | INFLUENT |
| INJ | INJECTION |
| INSTL | INSTALLATION / INSTALL |
| INSUL | INSULATION |
| INTER | INTERCEPTOR |
| INTR | INTERIOR |
| INV | INVERT |
| IP | IRON PIPE |
| IPT | IRON PIPE THREAD |
| IR | IRON ROD |
| IRRIG | IRRIGATION |
| JT | JOINT |
| JUNC | JUNCTION |
| KPL | KICK PLATE |
| KVA | KILOVOLT AMPERE |
| KW | KILOWATT |
| KWY | KEYWAY |
| L | LENGTH OF CURVE |
| LAB | LABORATORY |
| LAV | LAVATORY |
| LB | POUND |
| LF | LINEAL FOOT |
| LIN | LINEAL / LINEAR |
| LN | LANE |
| LOC | LOCATION |
| LONG | LONGITUDINAL |
| LP | LOW PRESSURE |
| LPT | LOW POINT |
| LRG | LARGE |
| LS | LONG SLEEVE / LUMP SUM |
| LT | LEFT |
| LVL | LEVEL |
| LWL | LOW WATER LINE |
| MAN | MANUAL |
| MATL | MATERIAL |
| MAX | MAXIMUM |
| MB | MAIL BOX |
| MCC | MOTOR CONTROL CENTER |
| MCP | MASTER CONTROL PANEL |
| MECH | MECHANICAL |
| MET | METAL |
| MFR | MANUFACTURER |
| MGD | MILLION GALLONS PER DAY |
| MH | MANHOLE |
| MIN | MINIMUM |
| MIPT | MALE IRON PIPE THREAD |
| MISC | MISCELLANEOUS |
| MJ | MECHANICAL JOINT |
| MON | MONUMENT / MONOLITHIC |

| | |
|----------|---|
| MOT | MOTOR |
| MP | MILEPOST |
| MSL | MEAN SEA LEVEL |
| MTD | MOUNTED |
| NA | NOT APPLICABLE |
| NC | NORMALLY CLOSED |
| NF | NEAR FACE |
| NIC | NOT IN CONTRACT |
| NO / NO. | NORMALLY OPEN / NUMBER |
| NOM | NOMINAL |
| NORM | NORMAL |
| NRS | NON-RISING STEM |
| NTS | NOT TO SCALE |
| O TO O | OUT TO OUT |
| OC | ON CENTER |
| OD | OUTSIDE DIAMETER |
| ODOT | OREGON DEPARTMENT OF TRANSPORTATION |
| OF | OVERFLOW / OUTSIDE FACE |
| OHP | OVERHEAD POWER |
| OPNG | OPENING |
| OPP | OPPOSITE |
| ORIG | ORIGINAL |
| OVHD | OVERHEAD |
| P&ID | PROCESS & INSTRUMENTATION DIAGRAM |
| PC | POINT OF CURVE |
| PCC | POINT OF COMPOUND CURVE |
| PCVC | POINT OF CURVATURE ON VERTICAL CURVE |
| PE | PLAIN END |
| PERF | PERFORATED |
| PERM | PERMANENT |
| PERP | PERPENDICULAR |
| PG | PRESSURE GAUGE |
| PGE | PORTLAND GENERAL ELECTRIC |
| PH | PIPE HANGER |
| PI | POINT OF INTERSECTION |
| PIVC | POINT OF INTERSECTION ON VERTICAL CURVE |
| PL or P | PROPERTY LINE / PLATE / PLASTIC |
| PLBG | PLUMBING |
| PNL | PANEL |
| POC | POINT OF CURVATURE |
| POLY | POLYETHYLENE |
| POT | POINT OF TANGENCY |
| PP | POWER POLE |
| PRC | POINT OF REVERSE CURVATURE |
| PRCST | PRECAST |
| PREP | PREPARATION |
| PRESS | PRESSURE |
| PRKG | PARKING |
| PROP | PROPOSED / PROPERTY |
| PRV | PRESSURE REDUCING VALVE |
| PS | PUMP STATION |
| PSIG | POUNDS PER SQUARE INCH GAGE |
| PSL | PIPE SLEEVE |
| PSPT | PIPE SUPPORT |
| PT | POINT OF TANGENCY |
| PTVC | POINT OF TANGENCY ON VERTICAL CURVE |
| PV | PLUG VALVE |
| PVC | POLYVINYL CHLORIDE |
| PVMT | PAVEMENT |
| PW | PUBLIC WORKS |
| PWR | POWER |
| QTY | QUANTITY |
| RAD | RADIUS |
| RAP | RECLAIMED ASPHALT PAVEMENT |
| RC | REINFORCED CONCRETE |
| RCP | REINFORCED CONCRETE PIPE |
| RD | ROAD / ROOF DRAIN |
| RDCR | REDUCER |
| REF | REFERENCE |
| REINF | REINFORCE (D) (ING) (MENT) |
| REQ'D | REQUIRED |
| RES | RESERVOIR |
| RESTR | RESTRAINED |
| RFC | RESTRAINED FLANGE COUPLING ADAPTER |
| RM | ROOM |
| RND | ROUND |
| RO | ROUGH OPENING |
| R/W | RIGHT OF WAY |
| RPPBD | REDUCED PRESSURE BACKFLOW PREVENTION DEVICE |
| RPM | REVOLUTIONS PER MINUTE |
| RR | RAILROAD |
| RST | REINFORCING STEEL |
| RT | RIGHT |
| SALV | SALVAGE |
| SAN | SANITARY |
| SC | SOLID CORE |
| SCHED | SCHEDULE |
| SD | STORM DRAIN |
| SDL | SADDLE |
| SDR | STANDARD DIMENSION RATIO |
| SECT | SECTION |
| SHLDR | SHOULDER |

| | |
|----------|--|
| SHT | SHEET |
| SIM | SIMILAR |
| SLP | SLOPE |
| SLV | SLEEVE |
| SOLN | SOLUTION |
| SP | SOIL PIPE / SEWER PIPE |
| SPCL | SPECIAL |
| SPEC (S) | SPECIFICATION (S) |
| SPG | SPACING |
| SPL | SPOOL |
| SPRT | SUPPORT |
| SQ | SQUARE |
| SQ FT | SQUARE FOOT |
| SQ IN | SQUARE INCH |
| SQ YD | SQUARE YARD |
| SS | SANITARY SEWER |
| SST | STAINLESS STEEL |
| ST | STREET |
| STA | STATION |
| STD | STANDARD |
| STL | STEEL |
| STOR | STORAGE |
| STR | STRAIGHT |
| STRUCT | STRUCTURE / STRUCTURAL |
| SUBMG | SUBMERGED |
| SUCT | SUCTION |
| SV | SOLENOID VALVE |
| S/W | SIDEWALK |
| SWD | SIDEWATER DEPTH |
| SWGR | SWITCH GEAR |
| SYMM | SYMMETRICAL |
| SYS | SYSTEM |
| T or TEL | TELEPHONE |
| T&B | TOP & BOTTOM |
| TAN | TANGENCY |
| TB | THRUST BLOCK |
| TBM | TEMPORARY BENCH MARK |
| TC | TOP OF CONCRETE / TOP OF CURB |
| TDH | TOTAL DYNAMIC HEAD |
| TEMP | TEMPERATURE / TEMPORARY |
| T&G | TONGUE & GROOVE |
| THK | THICKNESS |
| THRD | THREAD(ED) |
| THRU | THROUGH |
| TP | TEST PIT / TOP OF PAVEMENT / TURNING POINT |
| TRANS | TRANSITION |
| TSP | TRI-SODIUM PHOSPHATE |
| TST | TOP OF STEEL |
| TW | TOP OF WALL |
| TYP | TYPICAL |
| UG | UNDERGROUND |
| UGP | UNDERGROUND POWER |
| UH | UNIT HEATER |
| UN | UNION |
| UON | UNLESS OTHERWISE NOTED |
| USGS | UNITED STATES GEOLOGIC SURVEY |
| UTIL | UTILITY |
| V | VENT / VOLT |
| VAC | VACUUM |
| VAR | VARIABLE |
| VB | VACUUM BREAKER |
| VBOX | VALVE BOX |
| VC | VERTICAL CURVE |
| VERT | VERTICAL |
| VFD | VARIABLE FREQUENCY DRIVE |
| VOL | VOLUME |
| VCP | VITRIFIED CLAY PIPE |
| VTR | VENT THROUGH ROOF |
| W | WATER |
| W/ | WITH |
| W/IN | WITHIN |
| W/O | WITHOUT |
| W/W | WALL TO WALL |
| WD | WOOD |
| WF | WIDE FLANGE |
| WH | WALL HYDRANT |
| WHTR | WATER HEATER |
| WI | WROUGHT IRON |
| WM | WATER METER |
| WP | WORKING POINT / WATERPROOFING |
| WS | WATER SERVICE |
| WT | WEIGHT |
| WTP | WATER TREATMENT PLANT |
| WTRT | WATERTIGHT |
| WWF | WELDED WIRE FABRIC |
| WWTF | WASTEWATER TREATMENT FACILITY |
| WWTP | WASTEWATER TREATMENT PLANT |
| X SECT | CROSS SECTION |
| XFMR | TRANSFORMER |
| YD | YARD DRAIN/YARD |
| YH | YARD HYDRANT |
| YR | YEAR |
| ZN | ZINC |

| | | | | | | | | | |
|--|--|----------|--|-----|------|---------------|------------|--------------|-----------|
| BY | | REVISION | | NO. | DATE | DESIGNED: MLM | DRAWN: DKH | CHECKED: TPB | APPROVED: |
| | | | | | | | | | |
| <p>VERT: NONE HORIZ: NONE</p> <p>SCALE: NONE</p> <p>NOTICE</p> <p>IF THIS BAR DOES NOT MEASURE THE DRAWING IS NOT TO SCALE</p> | | | | | | | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: ABBREVIATIONS</p> | | | | | | | | | |
| <p>121 S.W. Salmon, Suite 900 Portland, Oregon 97204</p> <p>PHONE: 503-225-9010 FAX: 503-225-9022</p> <p>DATE: SEPTEMBER 2015</p> | | | | | | | | | |
| <p>MSA PROJECT: 14-1586</p> | | | | | | | | | |

GENERAL NOTES

- CONTRACTOR SHALL OBTAIN ALL NECESSARY LOCAL, COUNTY, STATE, AND UTILITY CONSTRUCTION PERMITS NOT OBTAINED BY THE OWNER, AND SHALL CONTACT EACH PERMITTING AGENCY AT LEAST TWO (2) BUSINESS DAYS PRIOR TO STARTING WORK. CONTRACTOR SHALL OBTAIN ALL REQUIRED LICENSES BEFORE STARTING CONSTRUCTION.
- THE LOCATIONS OF ALL EXISTING UNDERGROUND FACILITIES SHOWN ON THE PLANS ARE BASED ON A FIELD SURVEY AND INFORMATION SUPPLIED BY UTILITY COMPANIES. LOCATIONS ARE NOT GUARANTEED TO BE COMPLETE OR ACCURATE. THE CONTRACTOR SHALL VERIFY LOCATIONS, ELEVATIONS, TYPE AND SIZES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTING NEW PIPING/CONDUITS AND SHALL ADJUST NEW PIPING/CONDUITS AS REQUIRED. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY CONFLICTS NOT SHOWN ON THE PLANS AND SHALL KEEP EXISTING UTILITIES IN SERVICE AND PROTECT THEM DURING CONSTRUCTION. WHERE INTERRUPTION OF EXISTING FACILITIES IS REQUIRED, CONTRACTOR SHALL PROVIDE 72 HOUR NOTICE TO ENGINEER AND THE AFFECTED UTILITY. CONTRACTOR SHALL ARRANGE FOR THE RELOCATION OF ANY IN CONFLICT WITH THE PROPOSED CONSTRUCTION.
- THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS OF ORS 757.541 TO 757.571. THE CONTRACTOR SHALL NOTIFY EACH UNDERGROUND UTILITY AT LEAST 48 BUSINESS-DAY HOURS, BUT NOT MORE THAN 10 BUSINESS DAYS, PRIOR TO EXCAVATING, BORING, OR POTHOLING.
- NO ADDITIONAL PAYMENT SHALL BE MADE FOR UTILITY RELOCATION COORDINATION OR DELAYS CAUSED BY UTILITY CONFLICTS. ALL COSTS RELATED TO UTILITY COORDINATION AND RELOCATION, INCLUDING ADDITIONAL POTHOLING, ARE TO BE CONSIDERED INCIDENTAL AND INCLUDED IN THE UNIT PRICES OF THE BID.
- UTILITIES OR INTERFERING PORTIONS OF UTILITIES THAT ARE ABANDONED IN PLACE SHALL BE REMOVED BY THE CONTRACTOR TO THE EXTENT NECESSARY TO ACCOMPLISH THE WORK. THE CONTRACTOR SHALL PLUG THE REMAINING EXPOSED ENDS OF ABANDONED UTILITIES, UNLESS OTHERWISE REQUIRED BY THE ENGINEER, OR AS IDENTIFIED ON THE PLANS.
- CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION AND SEDIMENTATION CONTROL MEASURES DURING CONSTRUCTION (ANY TIME OF YEAR) PER THE REQUIREMENTS OF THE APPROVED 1200-CN PERMIT, CITY OF WEST LINN, CLACKAMAS COUNTY AND THE OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY.
- CONSTRUCTION SHALL BE CONFINED TO THE RIGHT-OF-WAY, EASEMENTS, OR OTHER AREAS AS SHOWN ON THE PLANS AND APPROVED FOR CONSTRUCTION. WORK SHALL NOT ENCR OACH BEYOND THE AREAS SHOWN ON THE PLANS WITHOUT PRIOR APPROVAL BY ENGINEER.
- ALL CONSTRUCTION AND MATERIALS SHALL CONFORM TO THE PLANS, PROJECT SPECIFICATIONS, CITY OF WEST LINN PUBLIC WORKS DESIGN STANDARDS AND APPLICABLE STANDARD SPECIFICATIONS AND DRAWINGS.
- CONTRACTOR SHALL KEEP AND MAINTAIN A CURRENT SET OF DRAWINGS ON SITE. CONTRACTOR TO KEEP ACCURATE "AS-BUILT" RECORD COPY OF PLANS. "AS-BUILT" PLANS TO BE RETURNED TO ENGINEER AT COMPLETION OF PROJECT.
- CONTRACTOR SHALL MAINTAIN ACCESS TO ALL HOMES AND BUSINESSES AT ALL TIMES. PROVIDE WRITTEN NOTICE TO ALL PROPERTY OWNERS AT LEAST TWO BUSINESS DAYS IN ADVANCE OF WORK IN AND/OR CROSSING OF DRIVEWAYS.
- CONTRACTOR SHALL NOTIFY THE ENGINEER AND OWNER 48 HOURS BEFORE STARTING CONSTRUCTION, AND 24 HOURS BEFORE RESUMING WORK AFTER SHUTDOWNS EXCEPT FOR NORMAL RESUMPTION OF WORK FOLLOWING SATURDAYS, SUNDAYS, OR HOLIDAYS. CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE A MINIMUM OF 48 HOURS PRIOR TO ANY TESTING OR REQUIRED INSPECTION.
- ANY ALTERATION OR VARIANCE FROM THESE PLANS, EXCEPT MINOR FIELD ADJUSTMENT NEEDED TO MEET EXISTING FIELD CONDITIONS, SHALL FIRST BE APPROVED BY THE ENGINEER. ANY ALTERATIONS OR VARIANCE FROM THESE PLANS SHALL BE DOCUMENTED ON CONSTRUCTION FIELD PRINTS AND TRANSMITTED TO THE ENGINEER. ANY PROPOSED CHANGES IN CONSTRUCTION PLANS MUST BE SUBMITTED IN WRITING AND APPROVED BY ENGINEER PRIOR TO COMMENCING WORK.
- CONTRACTOR SHALL PROTECT ALL PROPERTY CORNERS, SURVEY MONUMENTS AND CONTROL POINTS. SURVEY MONUMENTS OF THIS TYPE DISTURBED DURING CONSTRUCTION SHALL BE REPLACED AT CONTRACTOR'S EXPENSE, WITH APPROPRIATE SURVEYS FILED WITH THE COUNTY SURVEYOR.
- THE CONTRACTOR SHALL DISPOSE OF ALL REMOVED OR REPLACED MATERIAL AND EQUIPMENT IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS, EXCEPT THOSE ITEMS DESIGNATED BY THE OWNER FOR SALVAGING. SALVAGED ITEMS SHALL REMAIN THE PROPERTY OF THE OWNER, AND SHALL BE CAREFULLY REMOVED AND STORED AS DIRECTED.
- ALL STRUCTURES, LOTS, SWALES, DITCHES, CURBS, SPEED BUMPS, FENCES, WALLS, MAILBOXES, SIGNS, POLES, GUY WIRES, PIPING, AND UTILITIES DISTURBED DURING CONSTRUCTION TO BE RESTORED TO EXISTING CONDITION UNLESS OTHERWISE SPECIFIED. SUCH REPAIR SHALL BE CONSIDERED INCIDENTAL.
- ALL CONCRETE SHALL BE A MINIMUM OF 3000 PSI STRENGTH.
- "AS CONSTRUCTED" DRAWINGS SHALL BE SUBMITTED AS A CONDITION OF ACCEPTANCE OF THE WATER FACILITIES INSTALLED. PROVIDE "AS CONSTRUCTED" DRAWINGS INDICATING ALL CHANGES IN GRADE. ALIGNMENT FITTINGS AND MATERIALS INSTALLED AND ANY OTHER UTILITIES OR OBSTACLES NOT SO INDICATED ON THESE PLANS. "AS CONSTRUCTED" DRAWINGS SHALL BE "RED LINES" OF THE DESIGN DRAWINGS.

WATER SYSTEM NOTES

- AT THE END OF EACH WORK DAY ALL OPEN TRENCHES SHALL BE BACKFILLED AND ALL TRENCHES WITHIN STREETS SHALL BE TEMPORARILY PAVED OR COVERED TO THE SATISFACTION OF THE OWNER.
- CONTRACTOR SHALL COMPLY WITH ALL OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) REQUIREMENTS IN THE DISPOSAL OF SUPER CHLORINATED WATER. SEE TECHNICAL SPECIFICATIONS.
- CONTRACTOR SHALL PROVIDE TEMPORARY CONNECTIONS, BLOW-OFFS AND THRUST RESTRAINTS AS REQUIRED TO FACILITATE FLUSHING, TESTING AND DISINFECTION OF WATERLINES. TAPS ON WATER MAINS ARE NOT ALLOWED.
- CONNECTIONS TO EXISTING WATERLINES MAY REQUIRE TEMPORARY SHUTDOWNS OF EXISTING FACILITIES. THE CONTRACTOR SHALL COORDINATE THIS WORK WITH THE AFFECTED UTILITY AND PROVIDE A MINIMUM OF 72 HOURS ADVANCE NOTICE PRIOR TO PERFORMING THIS WORK.
- ALL VALVES AND FITTINGS SHALL BE CLASS 150. DUCTILE IRON PIPE SHALL BE CLASS 52 UNLESS OTHERWISE SPECIFIED.
- THE CONTRACTOR SHALL COMPLY WITH ALL CITY OF WEST LINN, AND CLACKAMAS COUNTY PERMIT REQUIREMENTS FOR WORK IN AND RESTORATION OF CITY AND COUNTY STREETS AND RIGHT-OF-WAYS. SEE SPECIAL PROVISIONS SECTION IN THE TECHNICAL SPECIFICATIONS FOR DETAILS.
- OPERATION OF WATER VALVES SHALL BE BY CITY OF WEST LINN STAFF ONLY.
- NO UNDERGROUND WORK SHALL BE "BURIED" UNTIL INSPECTED AND APPROVED BY THE ENGINEER.
- PIPE DEFLECTION IS LIMITED TO THE ONE-HALF OF THE MANUFACTURER'S RECOMMENDATIONS.
- UNLESS OTHERWISE NOTED ALL ON-SITE WATERLINES AND FITTING SHALL BE RESTRAINED.
- MINIMUM HYDROSTATIC TEST PRESSURE SHALL BE 150 PSI AT THE POINT OF HIGHEST ELEVATION OF THE PIPE BEING TESTED. MAXIMUM HYDROSTATIC TEST PRESSURE SHALL BE 180 PSI AT THE LOWEST ELEVATION OF THE PIPE BEING TESTED.
- FINAL LOCATIONS OF ALL VALVE BOXES, WATER QUALITY STATIONS, AIR RELEASE VALVES AND BLOWOFFS SHALL BE FIELD VERIFIED PRIOR TO CONSTRUCTION BY OWNER.
- THE USE OF CONCRETE THRUST BLOCKS IS ALLOWED ONLY WHERE SHOWN ON PLANS. REQUIRED THRUST RESTRAINT IN ALL OTHER LOCATIONS WILL BE ACCOMPLISHED WITH APPROVED JOINT RESTRAINT SYSTEM.
- ALL FLANGE CONNECTIONS TO BE PROVIDED WITH FULL-FACE GASKETS.
- PROVIDE TWO SHEETS OF 8 MIL POLYETHYLENE ENCASEMENT FOR ALL PIPING WITHIN 10 FT OF EXISTING GAS MAIN ACCORDING TO ANSI/AWWA C105/A21.5.
- COMPLY WITH OAR CHAPTER 333 RULES FOR REQUIRED WATERLINE - SEWER LINE SEPARATION AND CROSSING REQUIREMENTS.
- ALL PIPING SHALL HAVE A MINIMUM OF 3 FEET OF COVER FROM TOP OF PIPE TO STREET GRADE OR OTHER FINISH GRADE, UNLESS OTHERWISE SHOWN OR APPROVED BY ENGINEER.

SURVEY NOTES


- TOPOGRAPHIC MAP WAS COMPLETED BY HDJ DESIGN GROUP, PLLC. CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION SURVEYS. SEE CONTRACT DOCUMENT FOR SURVEY REQUIREMENTS.
- THE ELEVATION DATUM FOR THIS SURVEY IS NAVD 88 (CITY OF WEST LINN DOES NOT CURRENTLY HAVE BENCHMARK OR DATUM SYSTEM). ELEVATION=447.33'; HDJ CONTROL POINT NUMBER: 1 THE BENCHMARK IS A MAG NAIL WITH WASHER LOCATED INSIDE THE BOLTON RESERVOIR COMPLEX ON THE OUTSIDE EDGE OF A CONCRETE CURB APRON, APPROXIMATELY 11.2 FEET NORTHEAST OF A FIRE HYDRANT AND APPROXIMATELY 20.5 FEET SOUTHWEST OF THE SOUTHEAST CORNER OF THE MAIN NORTHERN FACILITY BUILDING.
- THE HORIZONTAL DATUM FOR THIS SURVEY IS NAD 83 (2011), STATE PLANE OREGON NORTH (ZONE 3601).
- THE UNDERGROUND UTILITIES SHOWN HEREON WERE BASED ON UTILITY LOCATE PAINT MARKS SUPPLIED BY THE OREGON UTILITY NOTIFICATION CENTER AS WELL AS SURFACE EVIDENCE AND PRIVATE AS-BUILT RECORDS. HOWEVER, LACKING EXCAVATION, THE EXACT LOCATION OF UNDERGROUND FEATURES CANNOT BE ACCURATELY, COMPLETELY AND RELIABLY DEPICTED.

DRAINAGE NOTES

- PROVISIONS SHALL BE MADE BY THE CONTRACTOR TO KEEP ALL EXISTING UTILITIES IN SERVICE AND TO PROTECT THEM DURING CONSTRUCTION. CONTRACTOR SHALL PROPERLY DIVERT ALL STORM FLOWS AS NECESSARY TO ACCOMPLISH WORK. CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE CONSTRUCTION DOES NOT INCREASE DITCH OR OVERLAND FLOWS OR FLOODING RISKS.
- ALL NON-METAL STORM DRAIN PIPING SHALL HAVE ELECTRICALLY CONDUCTIVE TRACER WIRE.
- ALL MANHOLE INVERT ELEVATIONS (IE IN, IE OUT) SHOWN ON PLANS, ARE PROJECTED TO MANHOLE CENTER RATHER THAN MANHOLE FACE.
- ALL PIPE CONNECTIONS TO MANHOLES, CATCH BASINS AND OTHER STRUCTURES SHALL BE MADE WITH NON-SHRINK GROUT, PVC SAND COLLARS OR KOR-N-SEAL BOOT AS REQUIRED.
- WHENEVER STORM DRAIN PIPING CROSSES PROPOSED WATERLINES, MAINTAIN A MINIMUM 12-INCH CLEARANCE.
- WHEN STORM DRAIN PIPING CONNECTIONS ARE LOCATED AT CATCH BASIN CORNER, CATCH BASIN SHALL BE CAST-IN-PLACE OR PRE-CAST CATCH BASIN DESIGNED TO ACCOMMODATE PIPE ENTRANCE AT THE CORNER.
- WHEN REPLACING MANHOLES, CATCH BASINS, AND PIPE MAINS, ALL EXISTING CONNECTIONS SHALL BE RECONNECTED INCLUDING PIPE MAINS, LATERALS AND SUBGRADE PIPING UNLESS OTHERWISE DIRECTED BY ENGINEER. ALL CONNECTIONS OF EXISTING PIPING SHALL BE ACCOMPLISHED USING APPROVED CONNECTION METHODS & MATERIALS.
- MAINLINE STORM DRAIN PIPING SHALL BE TV INSPECTED.
- ALL MANHOLES AND CATCH BASINS INSTALLED SHALL HAVE SUFFICIENT CLEARANCE TO PROVIDE ACCESS FOR TV INSPECTION CAMERAS.
- CONTRACTOR SHALL MATCH SLOPE AND ALIGNMENT OF EXISTING PIPE WHEN CONNECTING TO EXISTING PIPING.

STREET IMPROVEMENT NOTES


- CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL PLAN TO THE CITY FOR APPROVAL. A COPY OF THE APPROVED TRAFFIC CONTROL PLAN SHALL BE PROVIDED TO THE ENGINEER AND AVAILABLE AT THE WORK SITE. THE CITY RESERVES THE RIGHT TO ADD TO OR MODIFY TRAFFIC CONTROL REQUIREMENTS AS MAY BE NECESSARY TO EFFECTIVELY CONTROL TRAFFIC AND TO ASSURE PUBLIC SAFETY.
- CONTRACTOR SHALL PROTECT TRAFFIC AT ALL TIMES DURING CONSTRUCTION. CONTRACTOR SHALL ERECT AND MAINTAIN BARRICADES, WARNING SIGNS, TRAFFIC CONES PER CITY REQUIREMENTS IN ACCORDANCE WITH MUTCD (INCLUDING OREGON SUPPLEMENTS). ALL TRAFFIC CONTROL MEASURES SHALL BE APPROVED AND IN PLACE PRIOR TO ANY CONSTRUCTION ACTIVITY.
- FOR STREET IMPROVEMENTS, ADJUST ALL MANHOLES, CLEANOUTS AND VALVE BOXES TO FINISH GRADE. FOR MANHOLE RAISES, MANHOLE RINGS SHALL BE GROUTED ON THE INSIDE WITH NON-SHRINK GROUT.
- TRENCH COMPACTION: TESTS OF TRENCH FILL MATERIALS SHALL BE PER THE ODOT MANUAL OF FIELD TEST PROCEDURES (MFTP) AND MADE ON EACH LIFT OF FILL. TESTS SHALL BE TAKEN AT THE LOCATION AND FREQUENCY ESTABLISHED BY THE ENGINEER.
- ROADWAY MATERIALS COMPACTION: COMPACT PER THE MFTP. TESTS SHALL BE TAKEN AT THE LOCATION AND FREQUENCY ESTABLISHED BY THE ENGINEER.
- ALL REFERENCED ODOT STANDARD DRAWINGS ARE INCLUDED AS PART OF THE CONTRACT DOCUMENTS.
- OVER-EXCAVATION OF UNSUITABLE MATERIALS AND BACKFILL WITH SUBGRADE STABILIZATION SHALL BE APPROVED BY THE ENGINEER ON AN AS-NEEDED BASIS.
- SAWCUTTING OF EXISTING SURFACES, WHICH INCLUDES ASPHALTIC CONCRETE AND CONCRETE SURFACES, SHALL BE CONSIDERED INCIDENTAL AND INCLUDED IN THE UNIT PRICES OF THE BID.



Know what's below.
Call before you dig.

| | | | | | |
|--|-------------------------------|----------------------|---|---------------|--------------------|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: GENERAL NOTES | DATE: SEPTEMBER 2015 | Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Shannon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9022 | BY | |
| | | | | NO. | DATE |
| REVISION | | DESIGNED: MLM | CHECKED: TPB | APPROVED: TPB | REVISIONS 12-31-16 |
| SCALE: VERT: NONE HORIZ: NONE | | DRAWN: DKH | | | |
| NOTICE IF THIS BAR DOES NOT MATCH THE DRAWING, THEN IT IS NOT TO SCALE | | | | | |
| PROJECT NO. PW 14-06 | | | | | |
| SHEET NO. G-5 | | | | | |
| PROJECT: 14-1586 | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\GENERAL\14-1586-OR-GEN.dwg G-6 9/3/2015 9:58 AM HCM 20.0s (LMS Tech)



PLAN
SCALE: 1" = 150'

NOTE:
THE PROJECT OVERVIEW IS PROVIDED TO ILLUSTRATE THE WORK LIMITS AND BREAKDOWN OF WORK SCHEDULES AND DOES NOT IDENTIFY WORK OR MATERIALS REQUIRED FOR CONSTRUCTION.

| | | | |
|--|--|------------------------------------|----|
| | NO. DATE | REVISION | BY |
| | DESIGNED: MLM DRAWN: BAW CHECKED: TPB APPROVED: TPB | | |
| VERT: AS SHOWN SCALE: AS SHOWN | | HORIZ: AS SHOWN SCALE: AS SHOWN | |
| NOTICE IF THIS BAR DOES NOT MATCH THE PLAN, THE DRAWING IS NOT TO SCALE. | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | |
| PROJECT OVERVIEW | | | |
| | | DATE: SEPTEMBER 2015 | |
| 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022 | | SHEET G-6 6 of 167 | |

ESC PLAN FOR 1200-C SITES

SHEET INDEX

EROSION AND SEDIMENT CONTROL PLANS

- ESC-1 EROSION AND SEDIMENT CONTROL COVER SHEET
- ESC-2 EROSION AND SEDIMENT CONTROL SCHEDULES A & B - INITIAL CLEARING AND GRADING
- ESC-3 EROSION AND SEDIMENT CONTROL SCHEDULES A & B - FINAL GRADING
- ESC-4 EROSION AND SEDIMENT CONTROL SCHEDULES C - TYPICAL PIPELINE INSTALLATION MEASURES
- ESC-5 EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 1
- ESC-6 EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 2
- ESC-7 EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 3
- ESC-8 EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 4
- ESC-9 EROSION AND SEDIMENT CONTROL ALL SCHEDULES - STANDARD DETAILS - 1
- ESC-10 EROSION AND SEDIMENT CONTROL ALL SCHEDULES - STANDARD DETAILS - 2

OWNER:

CITY OF WEST LINN
CONTACT: KHUI LE, CIVIL ENGINEER II
22500 SALAMO, RD
WEST LINN, OR 97068
PHONE: (503) 722-5517

PLANNING / ENGINEERING:

MURRAY, SMITH & ASSOCIATES
CONTACT: JUSTIN FORD, P.E.
121 SW SALMON, SUITE 900
PORTLAND, OR 97204
PHONE: (503) 225-9010

NARRATIVE DESCRIPTIONS:

EXISTING SITE CONDITIONS

* WATER RESERVOIR, PUMP STATION BUILDING; CITY OF WEST LINN ROADWAYS AND RIGHTS-OF-WAY

DEVELOPED CONDITIONS

* WATER RESERVOIR, PUMP STATION BUILDING, ASSOCIATED UTILITIES (WATER AND STORM PIPING), WATER MAIN, SIDEWALK, AND STREET IMPROVEMENTS.

NATURE OF CONSTRUCTION ACTIVITY AND ESTIMATED TIME TABLE

- * MOBILIZATION & PIPING IMPROVEMENTS (12/2015-4/2016)
- * DEMOLITION, MASS EXCAVATION & GROUND IMPROVEMENT (4/2016-9/2016)
- * RESERVOIR CONSTRUCTION (9/2016-5/2017)

DISTURBED AREAS = SCHEDULES A & B: RESERVOIR & PUMP STATION = 2.8 ACRES
SCHEDULE C: WATER MAIN = 0.7 ACRES
SCHEDULE D: SIDEWALK AND ROAD IMPROVEMENTS = 1.7 ACRES

TOTAL DISTURBED AREA = 5.2 ACRES

SITE SOIL CLASSIFICATION:

LANDSLIDE DEPOSITS, SILT (PORTLAND HILLS), ALLUVIAL DEPOSITS, FINE GRAINED SAND, CLAYEY SILT, DECOMPOSED BASALT.

RECEIVING WATER BODIES:

BOLTON CREEK AND MADDAK CREEK DRAINAGE BASINS

ATTENTION EXCAVATORS:

OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THESE RULES FROM THE CENTER BY CALLING 503-232-1987. IF YOU HAVE ANY QUESTIONS ABOUT THE RULES, YOU MAY CONTACT THE CENTER. YOU MUST NOTIFY THE CENTER AT LEAST TWO BUSINESS DAYS, BEFORE COMMENCING AN EXCAVATION. CALL 503-246-6699.

PERMITTEE'S SITE INSPECTOR:

NAME: _____
COMPANY/AGENCY: _____
PHONE: _____
FAX: _____
E-MAIL: _____
DESCRIPTION OF EXPERIENCE: _____

THE PERMITTEE IS REQUIRED TO MEET ALL THE CONDITIONS OF THE 1200C PERMIT. THIS ESCP AND GENERAL CONDITIONS HAVE BEEN DEVELOPED TO FACILITATE COMPLIANCE WITH THE 1200C PERMIT REQUIREMENTS. IN CASES OF DISCREPANCIES OR OMISSIONS, THE 1200C PERMIT REQUIREMENTS SUPERCEDE REQUIREMENTS OF THIS PLAN.

INSPECTION FREQUENCY:

| SITE CONDITION | MINIMUM FREQUENCY |
|--|--|
| 1. ACTIVE PERIOD | DAILY WHEN STORMWATER RUNOFF, INCLUDING RUNOFF FROM SHOWELT, IS OCCURRING. AT LEAST ONCE EVERY TWO WEEKS, REGARDLESS OF WHETHER OR NOT RUNOFF IS OCCURRING. |
| 2. PRIOR TO THE SITE BECOMING INACTIVE OR IN ANTICIPATION OF SITE INACCESSIBILITY. | ONCE TO ENSURE THAT EROSION AND SEDIMENT CONTROL MEASURES ARE IN WORKING ORDER. ANY NECESSARY MAINTENANCE AND REPAIR MUST BE MADE PRIOR TO LEAVING THE SITE. |
| 3. INACTIVE PERIODS GREATER THAN FOURTEEN (14) CALENDAR DAYS. | ONCE EVERY TWO (2) WEEKS. |
| 4. PERIODS DURING WHICH THE SITE IS INACCESSIBLE DUE TO INCLEMENT WEATHER. | IF PRACTICAL, INSPECTIONS MUST OCCUR DAILY AT A RELEVANT AND ACCESSIBLE DISCHARGE POINT OR DOWNSTREAM LOCATION. |

- * HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS. (SCHEDULE A.B.C.I.(3))
- * ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS.
- * INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS.
- * RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, RETAIN THE ESCP AT THE CONSTRUCTION SITE OR AT ANOTHER LOCATION. (SCHEDULE B.2.A)

LOCAL AGENCY-SPECIFIC EROSION CONTROL NOTES:

1. WHEN RAINFALL AND RUNOFF OCCURS DAILY INSPECTIONS OF THE EROSION AND SEDIMENT CONTROLS AND DISCHARGE OUTFALLS MUST BE PROVIDED BY SOME ONE KNOWLEDGEABLE AND EXPERIENCED IN THE PRINCIPLES, PRACTICES, INSTALLATION, AND MAINTENANCE OF EROSION AND SEDIMENT CONTROLS WHO WORKS FOR THE PERMITTEE.
2. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND CREATION OF BARE GROUND FROM OCTOBER 1 THROUGH MAY 31 EACH YEAR.
3. DURING WET WEATHER PERIOD, TEMPORARY STABILIZATION OF THE SITE MUST OCCUR AT THE END OF EACH WORK DAY.
4. SEDIMENT CONTROLS MUST BE INSTALLED AND MAINTAINED ON ALL DOWN GRADIENT SIDES OF THE CONSTRUCTION SITE AT ALL TIMES DURING CONSTRUCTION. THEY MUST REMAIN IN PLACE UNTIL PERMANENT VEGETATION OR OTHER PERMANENT COVERING OF EXPOSED SOIL IS ESTABLISHED.
5. ALL ACTIVE INLETS MUST HAVE SEDIMENT CONTROLS INSTALLED AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION. UNLESS OTHERWISE APPROVED, A SURFACE MOUNTED AND ATTACHABLE, U-SHAPED FILTER BAG IS REQUIRED FOR ALL CURB INLET CATCH BASINS.
6. SIGNIFICANT AMOUNTS OF SEDIMENT WHICH LEAVES THE SITE MUST BE CLEANED UP WITHIN 24 HOURS AND PLACED BACK ON THE SITE AND STABILIZED OR PROPERLY DISPOSED. THE CAUSE OF THE SEDIMENT RELEASE MUST BE FOUND AND PREVENTED FROM CAUSING A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DEPARTMENT OF STATE LANDS REQUIRED TIME FRAME.
7. SEDIMENT MUST NOT BE INTENTIONALLY WASHED INTO STORM SEWERS, DRAINAGE WAYS, OR WATER BODIES.
8. SEDIMENT MUST BE REMOVED FROM BEHIND ALL SEDIMENT CONTROL MEASURES WHEN IT HAS REACHED A HEIGHT OF 1/3RD THE BARRIER HEIGHT, AND PRIOR TO THE CONTROL MEASURES REMOVAL.
9. CLEANING OF ALL STRUCTURES WITH SUMPS MUST OCCUR WHEN THE SEDIMENT RETENTION CAPACITY HAS BEEN REDUCED BY 50% AND AT COMPLETION OF PROJECT.
10. ANY USE OF TOXIC OR OTHER HAZARDOUS MATERIALS MUST INCLUDE PROPER STORAGE, APPLICATION, AND DISPOSAL.
11. THE PERMITTEE MUST PROPERLY MANAGE HAZARDOUS WASTES, USED OILS, CONTAMINATED SOILS, CONCRETE WASTE, SANITARY WASTE, LIQUID WASTE, OR OTHER TOXIC SUBSTANCES DISCOVERED OR GENERATED DURING CONSTRUCTION.
12. THE APPLICATION RATE OF FERTILIZERS USED TO REESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS. NUTRIENT RELEASES FROM FERTILIZERS TO SURFACE WATERS MUST BE MINIMIZED. TIME RELEASE FERTILIZERS SHOULD BE USED AND CARE SHOULD BE MADE IN APPLICATION OF FERTILIZERS WITHIN ANY WATER WAY RIPARIAN ZONE.
13. DESIGNATED PERSON SHALL BE RESPONSIBLE FOR PROPER INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL MEASURES, IN ACCORDANCE WITH CURRENT CITY OF WEST LINN PUBLIC WORKS STANDARDS AND STATE, AND FEDERAL REGULATIONS.
14. PRIOR TO ANY LAND DISTURBING ACTIVITIES, THE BOUNDARIES OF THE CLEARING LIMITS, VEGETATED BUFFERS, AND ANY SENSITIVE AREAS SHOWN ON THIS PLAN SHALL BE CLEARLY DELINEATED IN THE FIELD. UNLESS OTHERWISE APPROVED, NO DISTURBANCE IS PERMITTED BEYOND THE CLEARING LIMITS. THE PERMITTEE MUST MAINTAIN THE DELINEATION FOR THE DURATION OF THE PROJECT. NOTE: VEGETATED CORRIDORS TO BE DELINEATED WITH ORANGE CONSTRUCTION FENCE OR APPROVED EQUAL.
15. PRIOR TO ANY LAND DISTURBING ACTIVITIES, THE BMP'S THAT MUST BE INSTALLED ARE GRAVEL CONSTRUCTION ENTRANCE, PERIMETER SEDIMENT CONTROL, AND INLET PROTECTION. THESE BMP'S MUST BE MAINTAINED FOR THE DURATION OF THE PROJECT.
16. IF VEGETATIVE SEED MIXES ARE SPECIFIED, SEEDING MUST TAKE PLACE NO LATER THAN SEPTEMBER 1ST; THE TYPE AND PERCENTAGES OF SEED IN THE MIX ARE AS IDENTIFIED ON THE PLANS OR AS SPECIFIED BY THE DESIGN ENGINEER.
17. WATER-TIGHT TRUCKS MUST BE USED TO TRANSPORT SATURATED SOILS FROM THE CONSTRUCTION SITE. AN APPROVED EQUIVALENT IS TO DRAIN THE SOIL ON SITE AT A DESIGNATED LOCATION USING APPROPRIATE BMP'S; SOIL MUST BE DRAINED SUFFICIENTLY FOR MINIMAL SPILLAGE.
18. ALL PUMPING OF SEDIMENT LADEN WATER MUST BE DISCHARGED OVER AN UNDISTURBED, PREFERABLY VEGETATED AREA, AND THROUGH A SEDIMENT CONTROL BMP (I.E. FILTER BAG).
19. THE ESC PLAN MUST BE KEPT ON SITE. ALL MEASURES SHOWN ON THE PLAN MUST BE INSTALLED PROPERLY TO ENSURE THAT SEDIMENT LADEN WATER DOES NOT ENTER A SURFACE WATER SYSTEM, ROADWAY, OR OTHER PROPERTIES.
20. THE ESC MEASURES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE MEASURES SHALL BE UPGRADED AS NEEDED TO MAINTAIN COMPLIANCE WITH ALL REGULATIONS.
21. WRITTEN ESC LOGS ARE SUGGESTED TO BE MAINTAINED ONSITE AND AVAILABLE TO CITY OF WEST LINN INSPECTORS UPON REQUEST.
22. IN AREAS SUBJECT TO WIND EROSION, APPROPRIATE BMP'S MUST BE USED WHICH MAY INCLUDE THE APPLICATION OF FINE WATER SPRAYING, PLASTIC SHEETING, MULCHING, OR OTHER APPROVED MEASURES.
23. ALL EXPOSED SOILS MUST BE COVERED DURING WET WEATHER PERIOD.

STANDARD EROSION AND SEDIMENT CONTROL PLAN DRAWING NOTES:


1. ALL PERMIT REGISTRANTS MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (SCHEDULE A.B.)
2. SUBMISSION OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISIONS IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT. (SCHEDULE A.12.C.II)
3. PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (SCHEDULE A.B.C.I.(1)(D))
4. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED. (SCHEDULE A.7.B.II(1) AND A.7.B.II(3))
5. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (SCHEDULE A.8.C.I.(6))
6. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES AND FOR ALL ROADWAYS INCLUDING GRAVEL ROADWAYS. (SCHEDULE A.8.C.I.(2))
7. IMPLEMENT THE FOLLOWING BMP'S WHEN APPLICABLE: WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (SCH A 7.E.II)
8. IF A STORMWATER TREATMENT SYSTEM (FOR EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED, SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN PLAN APPROVAL BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (SCHEDULE A.9.D)
9. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR. (SCHEDULE A 7.B)
10. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE GROUND HEIGHT, AND BEFORE BMP REMOVAL. (SCHEDULE A.9.C.II)
11. THE ENTIRE SITE MUST BE TEMPORARILY STABILIZED USING VEGETATION OR A HEAVY MULCH LAYER, TEMPORARY SEEDING, OR OTHER METHOD SHOULD ALL CONSTRUCTION ACTIVITIES CEASE FOR 30 DAYS OR MORE. (SCHEDULE A.7.F.I)
12. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR AN ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (SCHEDULE A.7.F.II)

BMP MATRIX FOR CONSTRUCTION PHASES:

REFER TO DEQ GUIDANCE MANUAL FOR A LIST OF AVAILABLE BMP'S.

| | CLEARING | MASS GRADING | UTILITY INSTALLATION | STREET CONSTRUCTION | FINAL STABILIZATION | WET WEATHER (OCT. 1- MAY 31ST) |
|------------------------------|----------|--------------|----------------------|---------------------|---------------------|--------------------------------|
| EROSION PREVENTION | | | | | | |
| PRESERVE NATURAL VEGETATION | **X | X | X | X | X | X |
| GROUND COVER | | | | | X | X |
| PLASTIC SHEETING | | | | | | X |
| DUST CONTROL | X | X | X | X | | X |
| TEMPORARY/ PERMANENT SEEDING | | X | X | X | X | X |
| MATTING | | | | | X | X |
| SEDIMENT CONTROL | | | | | | |
| SEDIMENT FENCE (PERIMETER) | **X | X | X | X | | X |
| SEDIMENT FENCE (INTERIOR) | | | X | X | | X |
| BIO BAGS | | X | X | X | | X |
| INLET PROTECTION | **X | X | X | X | | X |
| DEWATERING (GENERAL) | | | X | X | | X |
| STRAW WATTLES | | | X | X | | X |
| FILTER BERM | X | X | X | X | | X |
| RUN-OFF CONTROL | | | | | | X |
| CONSTRUCTION ENTRANCE | **X | X | X | X | | X |
| CHECK DAMS | **X | X | X | X | X | |
| OUTLET PROTECTION | X | X | X | X | | X |
| SURFACE ROUGHENING | | | | | | X |
| POLLUTION PREVENTION | | | | | | |
| PROPER SIGNAGE | X | X | X | X | X | X |
| HAZ WASTE MGMT | X | X | X | X | X | X |
| SPILL KIT ON-SITE | X | X | X | X | X | X |
| CONCRETE WASH OUT AREA | X | X | X | X | | X |

** SIGNIFIES BMP THAT WILL BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY.



VICINITY MAP

SCALE: 1"=500'

PROJECT LOCATIONS:

RESERVOIR & PUMP STATION - SCHEDULES A AND B - NORTH OF SKYLINE DRIVE AVE AND WEST OF SKYLINE CIRCLE IN THE CITY OF WEST LINN.

WATER MAIN AND STREET IMPROVEMENTS - SCHEDULES C AND D - PRIMARILY WITHIN THE FOLLOWING RIGHTS-OF-WAY: CLARK STREET, SKYLINE CIRCLE, SKYLINE DRIVE, EASY STREET, BROADWAY STREET, AND BUSE STREET.

PROPERTY DESCRIPTIONS:

RESERVOIR & PUMP STATION - SCHEDULES A AND B - TOWNSHIP 2 SOUTH, RANGE 1 EAST, SECTION 25, TAXLOT 7100.

WATER MAIN AND STREET IMPROVEMENTS - SCHEDULES C AND D - CITY OF WEST LINN ROADWAYS: CLARK STREET, SKYLINE CIRCLE, SKYLINE DRIVE, EASY STREET, BROADWAY STREET, AND BUSE STREET.

RATIONALE STATEMENT

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMP'S WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS, TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS, AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN, AN ACTION PLAN WILL BE SUBMITTED.

JHF
INITIAL


| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |
| | | |




SCALE: VERT: AS SHOWN
HORIZ: AS SHOWN
NOTICE: IF THIS SEAL DOES NOT COVER THE ENTIRE DRAWING, IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE: EROSION AND SEDIMENT CONTROL COVER SHEET

Murray, Smith & Associates, Inc.
Engineers/Planners
121 SW Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022
DATE: SEPTEMBER 2015
PROJECT: 14-1586
SHEET: ESC-1
X OF 167



g:\pdx_projects\4\1586 - bolton reservoir replacement\CAD\Sheets\ESC\4-1586-OR-ESC-2_3.dwg ESC-2 8/31/2015 12:58 PM JHF 20.0s (LMS Tech)



LEGEND

- EXISTING CONTOURS (1')
- EXISTING CONTOURS (5')
- INLET PROTECTION
- DRAINAGE FLOW DIRECTION
- SEDIMENT FENCING (PERIMETER)
- TREES TO BE REMOVED

PRE-CONSTRUCTION CLEARING NOTES:

1. ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
2. SEDIMENT BARRIERS APPROVED FOR USE INCLUDE SEDIMENT FENCE, BERMS CONSTRUCTED OUT OF MULCH, CHIPPINGS, OR OTHER SUITABLE MATERIAL, STRAW WATTLES, OR OTHER APPROVED MATERIALS.
3. SENSITIVE RESOURCES INCLUDING, BUT NOT LIMITED TO, TREES, WETLANDS, AND RIPARIAN PROTECTION AREAS SHALL BE CLEARLY DELINEATED WITH ORANGE CONSTRUCTION FENCING OR CHAIN LINK FENCING IN A MANNER THAT IS CLEARLY VISIBLE TO ANYONE IN THE AREA. NO ACTIVITIES ARE PERMITTED TO OCCUR BEYOND THE CONSTRUCTION BARRIER.
4. CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, STREET SWEEPING, AND VACUUMING, MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT. SEE DETAIL SHEET ESC-10.
5. RUN-ON AND RUN-OFF CONTROLS SHALL BE IN PLACE AND FUNCTIONING PRIOR TO BEGINNING SUBSTANTIAL CONSTRUCTION ACTIVITIES. RUN-ON AND RUN-OFF CONTROL MEASURES INCLUDE: SLOPE DRAINS (WITH OUTLET PROTECTION), CHECK DAMS, SURFACE ROUGHENING, AND BANK STABILIZATION.
6. LIMIT SPEED OF VEHICLES ON SITE AND MOISTEN HAUL ROADS AS NECESSARY TO CONTROL DUST.

CONST ENTRANCE, SEE PRE-CONSTRUCTION CLEARING NOTE 4, THIS SHT

PLAN
SCALE: 1"=30'

| | | | | | | |
|--|--|---|--------------------------|--|-----------|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: EROSION AND SEDIMENT CONTROL SCHEDULES A & B - INITIAL CLEARING AND GRADING</p> | <p>DATE: SEPTEMBER 2015</p> | <p>NO. DATE REVISION</p> | <p>DESIGNED: JHF DRAWN: RLF CHECKED: AHG APPROVED: TPB</p> | <p>BY</p> | |
| | | <p>SCALE: VERT: AS SHOWN HORIZ: AS SHOWN</p> <p>NOTICE</p> <p>IF THIS BAR DOES NOT FIT THE DRAWING, THE DRAWING IS NOT TO SCALE</p> | | | | |
| | | | | | | |
| <p>MSA PROJECT: 14-1586</p> | | | | | | |
| <p>PHONE: 503-225-0010 FAX: 503-225-0022</p> | | | | | | |
| <p>SHEET ESC-2</p> | | | | | | |
| <p>X of 167</p> | | | | | | |

GRADING, STREET AND UTILITY EROSION AND SEDIMENT CONSTRUCTION NOTES:


- SEED USED FOR TEMPORARY OR PERMANENT SEEDING SHALL BE COMPOSED OF ONE OF THE FOLLOWING MIXTURES, UNLESS OTHERWISE AUTHORIZED:
 - VEGETATED CORRIDOR AREAS REQUIRE NATIVE SEED MIXES. SEE RESTORATION PLAN FOR APPROPRIATE SEED MIX.
 - DWARF GRASS MIX (MINIMUM 100 LB/AC)
 - DWARF PERENNIAL RYEGRASS (80% BY WEIGHT)
 - CREeping RED FESCUE (20% BY WEIGHT)
 - STANDARD HEIGHT GRASS MIX (MINIMUM 100 LB/AC)
 - ANNUAL RYEGRASS (40% BY WEIGHT)
 - TURF-TYPE FESCUE (60% BY WEIGHT)
- SLOPES AND DISTURBED AREAS TO RECEIVE TEMPORARY OR PERMANENT SEEDING SHALL HAVE THE SURFACE ROUGHENED BY MEANS OF TRACK-WALKING OR THE USE OF OTHER APPROVED IMPLEMENTS. SURFACE ROUGHENING IMPROVES SEED BEDDING AND REDUCES RUN-OFF VELOCITY.
- LONG TERM SLOPE AND DISTURBED AREAS STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED MIX AND APPLICATION RATE. SEE SPECIFICATIONS. IN ADDITION, ALL SLOPES OF 2:1 OR GREATER SHALL RECEIVE MATTING.
- TEMPORARY SLOPE AND DISTURBED AREAS STABILIZATION MEASURES SHALL INCLUDE: COVERING EXPOSED SOIL WITH PLASTIC SHEETING, STRAW MULCHING, WOOD CHIPS, OR OTHER APPROVED MEASURES.
- STOCKPILED SOIL OR STRIPPINGS SHALL BE PLACED IN A STABLE LOCATION AND CONFIGURATION. DURING "WET WEATHER" PERIODS, STOCKPILES SHALL BE COVERED WITH PLASTIC SHEETING OR STRAW MULCH. SEDIMENT FENCE IS REQUIRED AROUND THE PERIMETER OF THE STOCKPILE.
- EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES. SLOPES EXCEEDING 25% MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES.
- AREAS SUBJECT TO WIND EROSION SHALL USE APPROPRIATE DUST CONTROL MEASURES INCLUDING THE APPLICATION OF A FINE SPRAY OF WATER, PLASTIC SHEETING, STRAW MULCHING, OR OTHER APPROVED MEASURES. SEDIMENT FENCES SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES INCLUDING, BUT NOT LIMITED TO, TIRE WASHES, STREET SWEEPING, AND VACUUMING MAY BE REQUIRED TO INSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- ACTIVE INLETS TO STORM WATER SYSTEMS SHALL BE PROTECTED THROUGH THE USE OF APPROVED INLET PROTECTION MEASURES. ALL INLET PROTECTION MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED AS NEEDED.
- SATURATED MATERIALS THAT ARE HAULED OFF-SITE MUST BE TRANSPORTED IN WATER-TIGHT TRUCKS TO ELIMINATE SPILLAGE OF SEDIMENT AND SEDIMENT-LADEN WATER.
- AN AREA SHALL BE PROVIDED FOR THE WASHING OUT OF CONCRETE TRUCKS IN A LOCATION THAT DOES NOT PROVIDE RUN-OFF THAT CAN ENTER THE STORM WATER SYSTEM. IF THE CONCRETE WASH-OUT AREA CAN NOT BE CONSTRUCTED GREATER THAN 50' FROM ANY DISCHARGE POINT, SECONDARY MEASURES SUCH AS BERM OR TEMPORARY SETTLING PITS MAY BE REQUIRED. THE WASH-OUT SHALL BE LOCATED WITHIN SIX FEET OF TRUCK ACCESS AND BE CLEANED WHEN IT REACHES 50% OF THE CAPACITY.
- SWEEPINGS FROM EXPOSED AGGREGATE CONCRETE SHALL NOT BE TRANSFERRED TO THE STORM WATER SYSTEM. SWEEPINGS SHALL BE PICKED UP AND DISPOSED IN THE TRASH.
- AVOID PAVING IN WET WEATHER WHEN PAVING CHEMICALS CAN RUN-OFF INTO THE STORM WATER SYSTEM.
- USE BMPS SUCH AS CHECK-DAMS, BERMS, AND INLET PROTECTION TO PREVENT RUN-OFF FROM REACHING DISCHARGE POINTS.
- COVER CATCH BASINS, MANHOLES, AND OTHER DISCHARGE POINTS WHEN APPLYING SEAL COAT, TACK COAT, ETC. TO PREVENT INTRODUCING THESE MATERIALS TO THE STORM WATER SYSTEM.

EROSION AND SEDIMENT CONTROL BMP IMPLEMENTATION:

- ALL BASE ESC MEASURES (INLET PROTECTION, PERIMETER SEDIMENT CONTROL, GRAVEL CONSTRUCTION ENTRANCES, ETC.) MUST BE IN PLACE, FUNCTIONAL, AND APPROVED IN AN INITIAL INSPECTION, PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
- "STOCK PILE AREA" SHALL BE DESIGNATED PRIOR TO EXCAVATION CUT ACTIVITIES.
- ALL "SEDIMENT BARRIERS (TO BE INSTALLED AFTER GRADING)" SHALL BE INSTALLED IMMEDIATELY FOLLOWING ESTABLISHMENT OF FINISHED GRADE AS SHOWN ON THESE PLANS.
- LONG TERM SLOPE STABILIZATION MEASURES "INCLUDING SEEDING, JUTE MATTING, WATTLES, AND ROCK CHECK DAMS" SHALL BE IN-PLACE OVER ALL EXPOSED SOILS BY OCTOBER 1.
- THE STORM WATER FACILITIES SHALL BE CONSTRUCTED AND LANDSCAPED PRIOR TO THE STORM WATER SYSTEM FUNCTIONING AND SITE PAVING.
- INLET PROTECTION SHALL BE IN-PLACE IMMEDIATELY FOLLOWING PAVING ACTIVITIES.

EROSION CONTROL NOTES

- EMERGENCY EROSION CONTROL MATERIALS MUST BE KEPT ON SITE AT ALL TIMES.
- INSTALL, INSPECT, CLEAN, AND MAINTAIN SEDIMENT FENCE TO PREVENT SEDIMENT LADEN WATER FROM LEAVING THE SITE THROUGHOUT CONSTRUCTION. SEDIMENT FENCE SHALL BE INSTALLED PARALLEL TO SLOPE CONTOURS. ADDITIONAL SEDIMENT FENCE MAY BE REQUIRED BASED ON SITE CONDITIONS AND MEANS AND METHODS DEVELOPED BY CONTRACTOR. OVERLAY SEDIMENT FENCE 6" MINIMUM.
- INSPECT, CLEAN, AND MAINTAIN GRAVEL CONSTRUCTION ENTRANCE TO PREVENT SEDIMENT AND SEDIMENT LADEN WATER FROM LEAVING THE SITE THROUGHOUT CONSTRUCTION.
- ADDITIONAL TRACKING CONTROL MEASURES SUCH AS A WHEEL WASH MAY BE NECESSARY IF CONSTRUCTION ENTRANCE IS NOT SUFFICIENT.
- PROTECT CULVERTS FROM SEDIMENT BY INSTALLING FILTER FABRIC AND/OR BIOBAGS.
- ON-SITE RUNOFF ACCUMULATION INTO LOW POINTS SHALL BE PUMPED BY THE CONTRACTOR TO A SUITABLE LOCATION, IF REQUIRED.
- INSTALL SLOPE MATTING ON ALL SLOPES 2:1 OR GREATER.



LEGEND

- | | | | |
|----------------------------------|--|-------------------------|--|
| INLET PROTECTION | | EXISTING CONTOURS (1') | |
| DRAINAGE FLOW DIRECTION | | EXISTING CONTOURS (5') | |
| SEDIMENT FENCING (PERIMETER) | | PROPOSED CONTOURS (2') | |
| TREES TO REMAIN AND BE PROTECTED | | PROPOSED CONTOURS (10') | |


CONST ENTRANCE, SEE GRADING, STREET AND UTILITY EROSION AND SEDIMENT CONST NOTE 8, THIS SH

PLAN
SCALE: 1"=30'

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-2_3.dwg ESC-3 8/31/2015 12:58 PM JHF 20.0s (LMS Tech)


| | | | | | |
|--|---|---|--|--|-------------------------------------|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: EROSION AND SEDIMENT CONTROL SCHEDULES A & B - CONSTRUCTION AND FINAL GRADING</p> | <p>DATE: SEPTEMBER 2015</p> | <p>DESIGNED: JHF DRAWN: RLF CHECKED: ATG APPROVED: TTB</p> | <p>BY: _____ NO. DATE _____ REVISION _____</p> | <p>SHEET ESC-3 X of 167</p> |
| | | <p>NOTICE IF THIS BAR DOES NOT SHOW UP THEN DRAWING IS NOT TO SCALE</p> | | | |
| <p>VERT: AS SHOWN SCALE: _____ HORIZ: AS SHOWN</p> | | | | | |
| | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-4.dwg ESC-4 8/31/2015 12:58 PM JHF 20.0s (LMS Tech)



KEY NOTES:

- ① INSTALL TYPE 5 INLET PROTECTION WITH TYPE 4 INLET PROTECTION WHEN CURB OPENINGS ARE PRESENT





NOTES:


1. BEST MANAGEMENT PRACTICES (BMPs) SHOWN ARE THOSE OF A TYPICAL URBAN ROADWAY WITH PIPE ALIGNMENT IN PAVEMENT. PROVIDE BMPs AS NECESSARY TO SATISFY REQUIREMENTS OF THE 1200-C PERMIT.
2. WATTLES, PLASTIC SHEETING, AND SEDIMENT FENCE MUST BE KEPT ONSITE AS AN EMERGENCY EROSION AND SEDIMENT CONTROL BMPs.
3. GRAPHIC SYMBOLS ARE APPROXIMATE. PLACE EROSION CONTROL MEASURES AS REQUIRED OR DIRECTED.
4. SEE SHEETS ESC-9 AND ESC-10 FOR EROSION AND SEDIMENT CONTROL STANDARD DETAILS.
5. FOR ACCESS POINTS ONTO PAVED SURFACES, INSTALL CONSTRUCTION ENTRANCES OR CONSTRUCT AGGREGATE ROAD BASE AND GEOTEXTILE PER THE TYPICAL STREET SECTIONS, WHEN MUD AND DIRT TRACKING IS STILL EVIDENT, TAKE ADDITIONAL STEPS TO ELIMINATE TRACKING BY HOSEING OFF TIRES BEFORE VEHICLES LEAVE THE SITE. PERFORM TIRE WASHING ON GRAVEL PADS.

LEGEND

- EXISTING CONTOURS (1')
- EXISTING CONTOURS (5')
- INLET PROTECTION
- DRAINAGE FLOW DIRECTION
- PROPOSED WATERLINE

| | | | | | |
|--|--|--|-----------------------------------|-----------|---|
|  | <p>VERT: 1"=5'</p> <p>HORIZ: 1"=20'</p> <p>SCALE</p> | <p>NOTICE</p> <p>IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE</p> | <p>NO. DATE</p> <p>REVISION</p> | <p>BY</p> | <p>SHEET</p> <p>ESC-4</p> <p>X of 167</p> |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | | | | | |
| <p>SHEET TITLE: EROSION AND SEDIMENT CONTROL SCHEDULE C - TYPICAL PIPELINE INSTALLATION MEASURES</p> | | | | | |
| <p style="text-align: center;">  </p> <p style="font-size: small; text-align: center;"> 121 S.W. Salmon, Suite 900 PHONE 503-225-0010 Portland, Oregon 97204 FAX 503-225-0022 </p> | | | | | |
| <p style="text-align: right;">DATE: SEPTEMBER 2015</p> | | | | | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC-14-1586-OR-ESC-5-8.dwg ESC-5 9/1/2015 8:59 AM JHF 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'

- NOTES:**
1. WATTLES, PLASTIC SHEETING, AND SEDIMENT FENCE MUST BE KEPT ONSITE AS EMERGENCY ESC BMPS.
 2. INSTALL INLET PROTECTION TO ALL EXISTING STORM INLETS PRIOR TO CONSTRUCTION ACTIVITIES. MAINTAIN INLET PROTECTION UNTIL REMOVAL OF INLETS. INSTALL INLET PROTECTION ON ALL NEWLY CONSTRUCTED INLETS.
 3. INSTALL INLET PROTECTION TO ALL EXISTING STORM INLETS ON FIRWOOD DRIVE AND FIRWOOD COURT (NOT SHOWN) PRIOR TO CONSTRUCTION.
 4. GRAPHIC SYMBOLS ARE APPROXIMATE. PLACE EROSION CONTROL MEASURES AS REQUIRED OR DIRECTED.
 5. SEE SHEETS ESC-9 AND ESC-10 FOR STANDARD EROSION AND SEDIMENT CONTROL DETAILS.
 6. FOR ACCESS POINTS ONTO PAVED SURFACES, INSTALL CONSTRUCTION ENTRANCES OR CONSTRUCT AGGREGATE ROAD BASE AND GEOTEXTILE PER THE TYPICAL STREET SECTIONS. WHEN MUD AND DIRT TRACKING IS STILL EVIDENT, TAKE ADDITIONAL STAPES TO ELIMINATE TRACKING BY HOSEING OFF TIRES BEFORE VEHICLES LEAVE THE SITE. PERFORM TIRE WASHING ON GRAVEL PADS.

MATCHLINE - STA S15+20
SEE THIS SHEET - BOTTOM LEFT




PLAN
SCALE: 1" = 20'

LEGEND

- EXISTING CONTOURS (1')
- EXISTING CONTOURS (5')
- PROPOSED CONTOURS (1')
- PROPOSED CONTOURS (5')
- INLET PROTECTION
- DRAINAGE FLOW DIRECTION
- SEDIMENT FENCING
- PLASTIC MESH FENCE (NO WORK ZONE)
- CHECK DAM
- MATTING


KEY NOTES:

1. INSTALL INLET PROTECTION
2. INSTALL SEDIMENT FENCE
3. CONCRETE TRUCK WASHOUT, LOCATION PER CONTRACTOR, 10' SQUARE MIN
4. INSTALL SLOPE MATTING
5. INSTALL TEMP ORANGE PLASTIC FENCE

| | | | | | |
|---|--|-----------------|-----------------|-----------|--------------------------------------|
|  | <p>DESIGNED: JHF DRAWN: RLF CHECKED: AHG APPROVED: TPB</p> | <p>NO. DATE</p> | <p>REVISION</p> | <p>BY</p> | <p>SHEET ESC-5 11 of 167</p> |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | | | | | |
| <p>SHEET TITLE: EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 1</p> | | | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9022</p> | | | | | |
| <p>DATE: SEPTEMBER 2015</p> | | | | | |
| <p>MSA PROJECT: 14-1586</p> | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-5_8.dwg ESC-6 9/1/2015 8:59 AM JHF 20.0s (LMS Tech)

SEE THIS SHEET - BOTTOM LEFT
MATCHLINE - STA S20+80



PLAN
SCALE: 1" = 20'


- NOTES:
1. WATTLES, PLASTIC SHEETING, AND SEDIMENT FENCE MUST BE KEPT ONSITE AS EMERGENCY ESC BMPS.
 2. GRAPHIC SYMBOLS ARE APPROXIMATE. PLACE EROSION CONTROL MEASURES AS REQUIRED OR DIRECTED.
 3. SEE SHEETS ESC-9 AND ESC-10 FOR STANDARD EROSION AND SEDIMENT CONTROL DETAILS.
 4. FOR ACCESS POINTS ONTO PAVED SURFACES, INSTALL CONSTRUCTION ENTRANCES OR CONSTRUCT AGGREGATE ROAD BASE AND GEOTEXTILE PER THE TYPICAL STREET SECTIONS. WHEN MUD AND DIRT TRACKING IS STILL EVIDENT, TAKE ADDITIONAL STAPES TO ELIMINATE TRACKING BY HOISING OFF TIRES BEFORE VEHICLES LEAVE THE SITE. PERFORM TIRE WASHING ON GRAVEL PADS.

- KEY NOTES:
- 1 INSTALL INLET PROTECTION
 - 2 INSTALL SEDIMENT FENCE
 - 3 INSTALL ROCK CHECK DAMS
 - 4 INSTALL TEMP ORANGE PLASTIC FENCE
 - 5 INSTALL SLOPE MATTING
 - 6 INSTALL CHANNEL MATTING




SCALE: VERT: 1"=5'
HORIZ: 1"=20'
NOTICE
IF THIS BAR DOES NOT SHOW UP THEN DRAWING IS NOT TO SCALE

| | | | |
|-----------|---------|----------|-----------|
| NO. | DATE | REVISION | BY |
| DESIGNED: | JHF | | |
| DRAWN: | RLF | | |
| CHECKED: | AHC/WLM | | |
| APPROVED: | TPB | | |
| SHEET | | | ESC-6 |
| PROJECT | | | 12 of 167 |



PLAN
SCALE: 1" = 20'




PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE:
EROSION AND SEDIMENT CONTROL
SCHEDULE D - PLAN 2

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Shannon, Suite 900
Portland, Oregon 97204
PHONE 503-225-9010
FAX 503-225-9022

DATE: SEPTEMBER, 2015
MSA PROJECT: 14-1586


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-5_8.dwg ESC-7 9/1/2015 8:59 AM JHF 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'

NOTES:

1. WATTLES, PLASTIC SHEETING, AND SEDIMENT FENCE MUST BE KEPT ONSITE AS EMERGENCY ESC BMPS.
2. INSTALL INLET PROTECTION TO ALL EXISTING STORM INLETS PRIOR TO CONSTRUCTION ACTIVITIES. MAINTAIN INLET PROTECTION UNTIL REMOVAL OF INLETS. INSTALL INLET PROTECTION ON ALL NEWLY CONSTRUCTED INLETS.
3. GRAPHIC SYMBOLS ARE APPROXIMATE. PLACE EROSION CONTROL MEASURES AS REQUIRED OR DIRECTED.
4. SEE SHEETS ESC-9 AND ESC-10 FOR STANDARD EROSION AND SEDIMENT CONTROL DETAILS.
5. FOR ACCESS POINTS ONTO PAVED SURFACES, INSTALL CONSTRUCTION ENTRANCES OR CONSTRUCT AGGREGATE ROAD BASE AND GEOTEXTILE PER THE TYPICAL STREET SECTIONS. WHEN MUD AND DIRT TRACKING IS STILL EVIDENT, TAKE ADDITIONAL STEPS TO ELIMINATE TRACKING BY HOSING OFF TIRES BEFORE VEHICLES LEAVE THE SITE. PERFORM TIRE WASHING ON GRAVEL PADS.



PLAN
SCALE: 1" = 20'

KEY NOTES:


- ① INSTALL INLET PROTECTION
- ② INSTALL SEDIMENT FENCE
- ③ INSTALL ROCK CHECK DAMS
- ④ INSTALL TEMP ORANGE PLASTIC FENCE
- ⑤ INSTALL SLOPE MATTING
- ⑥ INSTALL CHANNEL MATTING

LEGEND

- EXISTING CONTOURS (1') - - - - - 459
- EXISTING CONTOURS (5') - - - - - 460
- PROPOSED CONTOURS (1') - - - - - 459
- PROPOSED CONTOURS (5') - - - - - 460
- INLET PROTECTION
- DRAINAGE FLOW DIRECTION
- SEDIMENT FENCING
- PLASTIC MESH FENCE (NO WORK ZONE)
- CHECK DAM
- MATTING

| | | | | | |
|--|---|---|---|--------------------------|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 3</p> | <p>DATE: SEPTEMBER 2015</p> | <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 PORTLAND, OREGON 97204 PHONE: 503-255-9110 FAX: 503-255-9122</p> | <p>NO. DATE REVISION</p> | <p>DESIGNED: JHF DRAWN: RLF CHECKED: AHG/MLM APPROVED: TPB</p> |
| <p>VERT: 1" = 5' HORIZ: 1" = 20'</p> <p>SCALE</p> | | <p>NOTICE</p> <p>IF THIS BAR DOES NOT MATCH THE DRAWING, THEN DRAWING IS NOT TO SCALE</p> | | | |
| <p>BY: _____ SHEET: ESC-7</p> <p>13 of 167</p> | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-5_8.dwg ESC-8 9/1/2015 8:59 AM JHF 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

LEGEND

- EXISTING CONTOURS (1')
- EXISTING CONTOURS (5')
- PROPOSED CONTOURS (1')
- PROPOSED CONTOURS (5')
- INLET PROTECTION
- DRAINAGE FLOW DIRECTION
- SEDIMENT FENCING
- PLASTIC MESH FENCE (NO WORK ZONE)
- CHECK DAM
- MATTING

KEY NOTES:

- ① INSTALL INLET PROTECTION
- ② INSTALL SEDIMENT FENCE
- ③ CONCRETE TRUCK WASHOUT, LOCATION PER CONTRACTOR, 10' SQUARE MIN
- ④ INSTALL SLOPE MATTING
- ⑤ INSTALL TEMP ORANGE PLASTIC FENCE




PLAN
SCALE: 1" = 20'

NOTES:


1. WATTLES, PLASTIC SHEETING, AND SEDIMENT FENCE MUST BE KEPT ONSITE AS EMERGENCY ESC BMPs.
2. INSTALL INLET PROTECTION TO ALL EXISTING STORM INLETS PRIOR TO CONSTRUCTION ACTIVITIES. MAINTAIN INLET PROTECTION UNTIL REMOVAL OF INLETS. INSTALL INLET PROTECTION ON ALL NEWLY CONSTRUCTED INLETS.
3. GRAPHIC SYMBOLS ARE APPROXIMATE. PLACE EROSION CONTROL MEASURES AS REQUIRED OR DIRECTED.
4. SEE SHEETS ESC-9 AND ESC-10 FOR STANDARD EROSION AND SEDIMENT CONTROL DETAILS.
5. FOR ACCESS POINTS ONTO PAVED SURFACES, INSTALL CONSTRUCTION ENTRANCES OR CONSTRUCT AGGREGATE ROAD BASE AND GEOTEXTILE PER THE TYPICAL STREET SECTIONS. WHEN MUD AND DIRT TRACKING IS STILL EVIDENT, TAKE ADDITIONAL STEPS TO ELIMINATE TRACKING BY HOISING OFF TIRES BEFORE VEHICLES LEAVE THE SITE. PERFORM TIRE WASHING ON GRAVEL PADS.

| | | | |
|--|---------------|--|-----------|
| | DESIGNED: JHF | SHEET | ESC-8 |
| | DRAWN: RLF | CHECKED: ATG/MLM | 14 of 167 |
| NO. DATE | REVISION | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: EROSION AND SEDIMENT CONTROL SCHEDULE D - PLAN 4</p> | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204</p> | | <p>DATE: SEPTEMBER 2015</p> | |
| <p>MSA PROJECT: 14-1586</p> | | <p>PHONE: 503-225-0110 FAX: 503-225-0022</p> | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-9-10.dwg ESC-9 9/1/2015 11:44 AM HCM 20.0s (LMS Tech)




MATTING - SLOPE INSTALLATION
DETAIL DRAWING 4-1
REVISED 01-09




MATTING - CHANNEL INSTALLATION
DETAIL DRAWING 4-2
REVISED 01-09




PLASTIC SHEETING
DETAIL DRAWING 4-3
REVISED 01-09




CHECK DAM - ROCK
DETAIL DRAWING 4-4
REVISED 01-09



OUTLET PROTECTION - RIP RAP
DETAIL DRAWING 4-7
REVISED 01-09



SURFACE ROUGHENING - CAT TRACKING
DETAIL DRAWING 4-10
REVISED 01-09




SURFACE ROUGHENING - STAIR STEPPING/GROOVING
DETAIL DRAWING 4-11
REVISED 01-09

Professional Engineer Seal for Justin Meyer, License No. 21530, State of Oregon. Includes revision table with columns for No., Date, and Revision.


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE: EROSION AND SEDIMENT CONTROL ALL SCHEDULES - STANDARD DETAILS - 1
Murray Smith & Associates, Inc. Engineers/Planners
121 S.W. Salmon, Suite 900 Portland, Oregon 97204
DATE: SEPTEMBER 2015
SHEET: ESC-9 of 167

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\ESC\14-1586-OR-ESC-9-10.dwg ESC-10 9/1/2015 11:44 AM HCM 20.0s (LMS Tech)





NOTES:

1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT.
2. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
3. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.
4. WHERE RUNOFF CONTAINING SEDIMENT LADEN WATER IS LEAVING THE SITE VIA THE CONSTRUCTION ENTRANCE, OTHER MEASURES SHALL BE IMPLEMENTED TO DIVERT RUNOFF THROUGH AN APPROVED FILTERING SYSTEM.
5. **DIMENSIONS**
SINGLE FAMILY
 20' LONG BY 20' WIDE 8" DEEP OF 3/4" MINUS CLEAN ROCK.
COMMERCIAL
 50' LONG BY 20' WIDE 3'-6" CLEAN ROCK,
 GOVERNING AUTHORITY MAY REQUIRE GEOTEXTILE FABRIC TO PREVENT SUB-SOIL PUMPING.




NOTES:

1. ADDITIONAL MEASURES MUST BE CONSIDERED DEPENDING ON SOIL TYPES.
2. BIO-FILTER BAGS SHOULD BE STAKED WHERE APPLICABLE USING (2) 1"x2" WOODEN STAKES OR APPROVED EQUAL PER BAG.
3. WHEN USING 30" BIO-BAGS TO PROTECT A CATCH BASIN YOU MUST HAVE 4 BAGS AND THEY SHALL BE OVERLAPPED BY 6".




NOTES:

1. BURY BOTTOM OF FILTER FABRIC 6" VERTICALLY BELOW FINISHED GRADE.
2. 2" x 2" FIR, PINE OR STEEL FENCE POSTS.
3. POSTS TO BE INSTALLED ON UPHILL SIDE OF SLOPE.
4. COMPACT BOTH SIDES OF FILTER FABRIC TRENCH.
5. PANELS MUST BE PLACED ACCORDING TO SPACING ON DETAIL NO. 940



NOTE:

1. ACCESSIBLE CURB INLET CATCH BASINS MUST BE BLOCKED WHEN USING FULL FABRIC BIO-FILTER BAGS. SIZE OF FULL FABRIC BIO-FILTER BAGS TO BE DETERMINED BY MANUFACTURER.




NOTES:

1. STAKING SPECIFICATIONS:
 a. 1"x2" WOODEN STAKES
 b. ADDITIONAL STAKES MAY BE INSTALLED ON DOWNHILL SIDE OF WATTLES, ON STEEP SLOPE OR HIGHLY ERODIBLE SOILS.
2. SPACING IN ACCORDANCE WITH DETAIL 940.

| | | | |
|---|---|--|---|
| | PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: EROSION AND SEDIMENT CONTROL ALL SCHEDULES - STANDARD DETAILS - 2 | PROJECT NO. 14-1586-OR-ESC-10 SHEET ESC-10 X of 167 |
| SCALE: VERT. 1"=5' HORIZ. 1"=20' NOTICE: IF THIS BAR DOES NOT DRAWING IS NOT TO SCALE | PROJECT NO. 14-1586-OR-ESC-10 SHEET ESC-10 X of 167 | | |
| MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022 | | | |
| DATE: SEPTEMBER 2015 | | | |

G:\PDX_Projects\141586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV.dwg, C-A1 9/3/2015 4:14 PM DKH 20.0s (LMS Tech)





- NOTES:**
- SEE SHEET SPECIFICATIONS FOR SEQUENCING.
 - PROVIDE TEMPORARY SHORING AS NECESSARY TO PROTECT EXISTING STRUCTURES AND TREES, SEE SHEET C-A2.
 - PROVIDE CONSTRUCTION ENTRANCE, SEE SHEET ESC-10.
 - CITY OWNED PROPERTY, 6123 SKYLINE DRIVE, LOCATED ADJACENT TO THE RESERVOIR SITE, MAY BE USED FOR CONSTRUCTION STAGING.
 - CITY OWNED PROPERTY, 6175 SKYLINE DRIVE MAY BE USED AS A TEMPORARY CONSTRUCTION OFFICE.

- FENCING NOTES:**
- OWNER HAS APPROXIMATELY 160 LF OF EXISTING DECORATIVE METAL FENCE. SUPPLIER SHALL MATCH FENCE STYLE. DECORATIVE METAL FENCE SHALL BE AEGIS II MAJESTIC BY AMERISTAR. CONTRACTOR SHALL TRANSPORT FENCING FROM CITY FACILITIES FOR INSTALLATION.
 - COORDINATE FENCE REMOVAL WITH ADJACENT PROPERTY OWNERS. PROVIDE 2 WEEK WRITTEN NOTICE TO CITY PRIOR TO REMOVAL OF FENCING.
 - PROVIDE FENCING STOP TO ALLOW ROLL BACK ACCESS TO UTILITY EASEMENT.

| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |

DESIGNED: MLM
DRAWN: DKH
CHECKED: TPB
APPROVED: TPB

SHEET C-A1
17 of 167



PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: RESERVOIR SITE LAYOUT PLAN

Murray Smith & Associates, Inc.
Engineers/Planners


121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022

DATE: SEPTEMBER 2015

MSA PROJECT: 14-1586

PLAN
SCALE: 1"=30'

c:\pdx_projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DEMO.dwg C-A2 9/3/2015 4:16 PM DKH 20.0s (LMS Tech)



TREE PROTECTION NOTES

TREE REMOVAL NOTES

- ONLY THOSE TREES IDENTIFIED FOR REMOVAL MAY BE REMOVED.
- TREE LOCATIONS APPROXIMATE.
- CONTRACTOR SHALL COMPLY WITH CITY TREE REMOVAL PERMIT, TO BE OBTAINED BY OWNER.
- TREE REMOVAL AND CLEARING SHALL BE COMPLETED BETWEEN AUGUST 1 AND JANUARY 31, TO AVOID BIRD NESTING SEASON.

BEFORE CONSTRUCTION BEGINS

- FENCING:
 - FURNISH AND INSTALL APPROVED TREE PROTECTION FENCING AROUND EACH TREE OR GROVE OF TREES TO BE RETAINED.
 - THE FENCING SHALL BE INSTALLED PRIOR TO THE GROUND BEING CLEARED IN ORDER TO PROTECT THE TREES AND SOIL AROUND THE TREES FROM ANY DISTURBANCE.
 - FENCING SHALL BE PLACED AT THE EDGE OF THE ROOT PROTECTION ZONE. ROOT PROTECTION ZONES WILL BE ESTABLISHED BY THE PROJECT ARBORIST BASED IN THE NEEDS OF THE SITE AND THE TREE TO BE PROTECTED. THE TREE PROTECTION ZONE WILL BE APPROXIMATELY 15' FROM THE CENTER OF THE TREE IN ALL DIRECTIONS.
 - FENCING SHALL REMAIN IN THE LOCATION AS ESTABLISHED BY THE PROJECT ARBORIST AND NOT MOVED WITHOUT WRITTEN PERMISSION FROM THE PROJECT ARBORIST UNTIL THE END OF THE PROJECT.

SIGNAGE:

- ALL TREE PROTECTION FENCING SHALL HAVE SIGNAGE AS FOLLOWS:

TREE PROTECTION ZONE
DO NOT REMOVE OR ADJUST THE APPROVED LOCATION OF THIS TREE PROTECTION FENCING
Please contact the project arborist or owner if alternations to the approved location of the tree protection fencing are necessary.

- SIGNAGE SHOULD BE PLACE AS TO BE VISIBLE FROM ALL SIDES OF TREE PROTECTION AREA AND SPACED EVERY 75 FEET.

DURING CONSTRUCTION


- PROTECTION GUIDELINES WITHIN THE ROOT PROTECTION ZONE:
 - ENTRY INTO THE TREE PROTECTION AREAS IS PROHIBITED EXCEPT BY THE PROJECT ARBORIST UNLESS THROUGH WRITTEN PERMISSION OF THE PROJECT ARBORIST.
 - NO TRAFFIC SHALL BE ALLOWED WITHIN THE ROOT PROTECTION ZONE. NO VEHICLE, HEAVY EQUIPMENT, OR REPEATED FOOT TRAFFIC SHALL BE ALLOWED WITHIN THE ROOT PROTECTION ZONE.
 - STORAGE OF MATERIALS INCLUDING, BUT NOT LIMITED TO, SOIL, CONSTRUCTION MATERIAL, OR WASTE FROM THE SITE WILL NOT BE ALLOWED WITHIN THE TREE PROTECTION ZONE. WASTE INCLUDES, BUT IS NOT LIMITED TO, CONCRETE WASH OUT, GASOLINE, DIESEL, PAINT, CLEANER, THINNERS, ETC.
 - CONSTRUCTION TRAILERS SHALL BE NOT PARKED/PLACED WITHIN THE ROOT PROTECTION ZONE WITHOUT WRITTEN APPROVAL FROM THE PROJECT ARBORIST.
 - VEHICLES SHALL NOT BE PARKED WITHIN THE ROOT PROTECTION AREAS.
 - NO ACTIVITY SHALL BE ALLOWED THAT WILL CAUSE SOIL COMPACTION WITHIN THE ROOT PROTECTION ZONE.
- TREES TO REMAIN SHALL BE PROTECTED FROM ANY CUTTING, SKINNING OR BREAKING OF BRANCHES, TRUNKS OR ROOTS.
- PRIOR TO CUTTING ROOTS FROM EXISTING TREES THAT ARE TO BE RETAINED, THE PROJECT ARBORIST SHALL BE NOTIFIED TO EVALUATE AND OVERSEE THE PROPER CUTTING OF ROOTS WITH SHARP CUTTING TOOLS. CUT ROOTS SHALL BE IMMEDIATELY COVERED WITH SOIL OR MULCH TO PREVENT DRYING OF THE ROOT.
- NO GRADE CHANGES SHALL OCCUR WITHIN THE ROOT PROTECTION ZONE.
- ANY NECESSARY DEVIATION OF THE ROOT PROTECTION ZONE SHALL BE APPROVED BY THE PROJECT ARBORIST OR THE OWNER, PRIOR TO IMPLEMENTING CHANGES.
- PROVIDE WATER TO TREES DURING THE SUMMER MONTHS. TREE(S) THAT WILL HAVE HAD ROOT SYSTEM(S) CUT BACK WILL NEED SUPPLEMENTAL WATER TO OVERCOME THE LOSS OF ABILITY TO ABSORB NECESSARY MOISTURE DURING THE SUMMER MONTHS.
- ANY NECESSARY PASSAGE OF UTILITIES THROUGH THE ROOT PROTECTION ZONE SHALL BE BY MEANS OF TUNNELING UNDER ROOTS BY HAND DIGGING OR BORING.

AFTER CONSTRUCTION

- CAREFULLY LANDSCAPE IN THE AREA OF THE TREE. DO NOT ALLOW TRENCHING WITHIN THE ROOT PROTECTION ZONE. CAREFULLY PLANT NEW PLANTS WITHIN THE ROOT PROTECTION ZONE. AVOID CUTTING THE ROOTS OF THE EXISTING TREES.
- DO NOT PLACE IRRIGATION WITHIN THE ROOT PROTECTION ZONE OF EXISTING TREES UNLESS IT IS DRIP IRRIGATION FOR A SPECIFIC PLANTING OR CLEARED BY THE PROJECT ARBORIST.
- PROVIDE FOR ADEQUATE DRAINAGE OF THE AREA AROUND THE RETAINED TREES.
- PRUNING OF THE TREES SHALL BE COMPLETED AS ONE OF THE LAST STEPS OF THE LANDSCAPING PROCESS BEFORE THE FINAL PLACEMENT OF TREES, SHRUBS, GROUND COVERS, MULCH OR SEEDING.

| | | | |
|---|---------------|--------------|----------------------|
| BY: | NO.: | DATE: | REVISION: |
| SHEET: | DESIGNED: MLM | CHECKED: TPB | APPROVED: TPB |
| C-A2 | DRAWN: DKH | CHECKED: TPB | APPROVED: TPB |
| 18 of 167 | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: RESERVOIR SITE TREE REMOVAL AND PROTECTION PLAN | | | |
| MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 PHOENIX 503-255-9010 Portland, Oregon 97204 FAX 503-255-9022 | | | |
| DATE: SEPTEMBER 2015 | | | MSA PROJECT: 14-1586 |

G:\PDX_Proj\14-1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-C1V DEMO.dwg C-A3 9/3/2015 4:16 PM DKH 20.0s (LMS Tech)



DEMOLITION SEQUENCING NOTES:

SEE SPECIFICATIONS FOR SEQUENCING NOTES.

NOTES:

1. PROVIDE 72 HOURS NOTICE PRIOR TO REQUESTED SERVICE SHUTDOWNS. COORDINATE RESERVOIR DRAINING AND WATER MAIN SHUTDOWNS WITH CITY.
2. PRIOR TO TAKING THE 8" PVC MAIN OFFLINE, THE CITY WILL ISOLATE FROM MAIN NORTH OF THE RESERVOIR SITE.
3. EXISTING CONCRETE RESERVOIR HAS SLOPED SIDES, OVERFLOW ELEVATION OF 445' AND FLOOR ELEVATION OF 430'.

REMOVE & DISPOSE ALL CONC & AC SURFACING AT 6175 & 6123 SKYLINE DR

WS TO BE RELOCATED BY CITY CREWS

ABAN WS

REMOVE EXIST FH ASSY, FURNISH & INSTALL 1-6" PLUG

SEE DET 2, SHT C-A8

PLAN
SCALE: 1"=30'

DEMOLISH & REMOVE EXIST 2.5 MG CONC RES W/ LINER


DEMOLISH & REMOVE EXIST VALVE VAULTS

DEMOLISH & REMOVE OLD PUMP STATION STRUCTURES

REMOVE 18" STL W, SEE SHT C-C2 FOR CONT, SEE NOTE 2

ABAN 4" CI W, SEE SHT C-C2 FOR CONT

| | |
|---------------|-----------|
| BY | |
| NO. | DATE |
| REVISION | |
| DESIGNED: MAM | |
| DRAWN: BAW | |
| CHECKED: TPB | |
| APPROVED: TPB | |
| SHEET | C-A3 |
| | 19 of 167 |



SCALE: VERT. AS SHOWN, HORIZ. AS SHOWN
NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE: RESERVOIR SITE DEMOLITION PLAN



MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-0022
DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

| STORMWATER FACILITY GRADING POINTS | | | |
|------------------------------------|-----------|-----------|------------|
| NO. | ELEVATION | NORTHING | EASTING |
| 1 | 438.00 | 627634.96 | 7656015.89 |
| 2 | 425.00 | 627671.89 | 7655999.88 |
| 3 | 441.00 | 627670.24 | 7655967.91 |
| 4 | 425.00 | 627677.78 | 7656047.46 |
| 5 | 435.00 | 627669.36 | 7656065.62 |
| 6 | 425.11 | 627706.72 | 7656045.12 |
| 7 | 435.00 | 627726.15 | 7656049.74 |
| 8 | 442.24 | 627639.11 | 7655979.19 |
| 9 | 420.00 | 627660.12 | 7656267.22 |
| 10 | 421.00 | 627655.07 | 7656265.02 |
| 11 | 420.00 | 627686.69 | 7656209.94 |
| 12 | 421.00 | 627680.22 | 7656207.26 |
| 13 | 422.00 | 627692.17 | 7656212.54 |

| EDGE OF PAVEMENT ELEVATION TABLE | | | | EDGE OF GRAVEL ELEVATION TABLE | | | |
|----------------------------------|-----------|-------|-----------|--------------------------------|-----------|-------|-----------|
| POINT | ELEVATION | POINT | ELEVATION | POINT | ELEVATION | POINT | ELEVATION |
| 1 | 460.68 | 14 | 440.00 | 26 | 457.75 | 33 | 442.65 |
| 2 | 451.00 | 15 | 448.25 | 27 | 456.99 | 36 | 442.90 |
| 3 | 448.17 | 16 | 447.35 | 28 | 440.67 | 37 | 444.10 |
| 4 | 448.89 | 17 | 447.43 | 29 | 439.01 | 38 | 444.65 |
| 5 | 452.00 | 18 | 447.29 | 30 | 439.59 | 39 | 444.80 |
| 6 | 445.12 | 19 | 448.05 | 31 | 439.80 | 40 | 435.00 |
| 7 | 446.16 | 20 | 448.03 | 32 | 439.95 | 41 | 429.10 |
| 8 | 446.95 | 21 | 448.32 | 33 | 439.95 | 42 | 425.50 |
| 9 | 440.05 | 22 | 451.50 | 34 | 441.97 | | |
| 10 | 439.95 | 23 | 457.86 | | | | |
| 11 | 439.95 | 24 | 460.43 | | | | |
| 12 | 439.90 | 25 | 440.30 | | | | |
| 13 | 439.85 | | | | | | |

| EDGE OF PAVEMENT CURVE TABLE | | | | | |
|------------------------------|---------------------------|---------------------------|------------|---------|---------|
| NO. | PC | PT | DELTA | RADIUS | LENGTH |
| 1 | N627435.61 E7656009.40 | N627412.72 E7655951.33 | 87°49'53" | 45.00' | 68.98' |
| 2 | N627434.67 E7656090.89 | N627435.61 E7656009.40 | 43°29'03" | 110.00' | 83.48' |
| 3 | N627433.70 E7656129.17 | N627434.67 E7656090.89 | 45°02'00" | 50.00' | 39.30' |
| 4 | N627570.23 E7656274.48 | N627574.29 E7656275.83 | 5°47'03" | 42.43' | 4.28' |
| 5 | N627582.57 E7656236.74 | N627579.57 E7656261.69 | 11°47'45" | 122.29' | 25.18' |
| 6 | N627548.97 E7656247.23 | N627567.98 E7656236.50 | 103°43'54" | 15.00' | 27.16' |
| 7 | N627477.58 E7656198.62 | N627484.90 E7656218.53 | 90°00'00" | 15.00' | 23.56' |
| 8 | N627512.58 E7655970.01 | N627508.68 E7656131.36 | 143°24'20" | 85.00' | 212.75' |
| 9 | N627487.88 E7655957.11 | N627509.08 E7655958.53 | 41°29'17" | 30.00' | 21.72' |

| EDGE OF GRAVEL CURVE TABLE | | | | | |
|----------------------------|---------------------------|---------------------------|------------|---------|---------|
| NO. | PC | PT | DELTA | RADIUS | LENGTH |
| 10 | N627630.98 E7656076.52 | N627509.08 E7655958.53 | 121°57'51" | 97.00' | 206.48' |
| 11 | N627515.20 E7656145.78 | N627498.17 E7656154.09 | 78°21'14" | 15.00' | 20.51' |
| 12 | N627541.24 E7656168.97 | N627528.83 E7656147.96 | 108°51'09" | 15.00' | 28.50' |
| 13 | N627538.69 E7656174.74 | N627540.78 E7656190.34 | 62°59'02" | 15.07' | 16.57' |
| 14 | N627567.59 E7656225.83 | N627568.84 E7656232.14 | 47°45'55" | 7.94' | 6.62' |
| 15 | N627585.18 E7656183.84 | N627580.95 E7656214.81 | 34°16'51" | 53.04' | 31.73' |
| 16 | N627580.95 E7656214.81 | N627582.57 E7656236.74 | 10°18'51" | 122.29' | 22.01' |
| 17 | N627579.57 E7656261.69 | N627608.29 E7656250.37 | 68°29'49" | 27.43' | 32.79' |
| 18 | N627640.26 E7656209.11 | N627671.31 E7656183.69 | 18°30'00" | 124.83' | 40.31' |



| ACCESS ROAD ALIGNMENT AND CURVE TABLE | | | | | | |
|---------------------------------------|-------------|------------|--------|--------|-------------|------------|
| LINE/CURV E NO. | START POINT | END POINT | RADIUS | LENGTH | BEARING | Δ |
| L1 | STA RA0+00 | STA RA0+42 | N/A | 42.00 | N24°34'27"E | N/A |
| C1 | STA RA0+42 | STA RA1+21 | 50.00 | 79.30 | N/A | 90°52'03" |
| C2 | STA RA1+21 | STA RA6+93 | 91.00 | 571.75 | N/A | 360°00'00" |
| L2 | STA RB0+00 | STA RB0+91 | N/A | 91.25 | S65°11'02"E | N/A |
| L3 | STA RB0+91 | STA RB2+27 | N/A | 136.22 | N24°48'58"E | N/A |
| C3 | STA RB2+27 | STA RB2+74 | 34.93 | 46.96 | N/A | 77°01'58" |
| L4 | STA RB2+74 | STA RB3+27 | N/A | 52.11 | N52°13'59"W | N/A |
| C4 | STA RB3+27 | STA RB3+64 | 119.48 | 37.25 | N/A | 17°51'46" |

PLAN
SCALE: 1"=30'

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

RESERVOIR SITE GRADING AND
ACCESS ROAD PAVING PLAN

DATE: SEPTEMBER 2014

BY: [Signature]

NO. DATE

REVISION

DESIGNED: M.L.C.
DRAWN: S.C.
CHECKED: T.P.E.
APPROVED: T.P.E.

REVISIONS 12-31-16

REGISTERED PROFESSIONAL ENGINEER
STATE OF OREGON
MICHAEL L. CROOK

SCALE: VERT. AS SHOWN
HORIZ. AS SHOWN


THIS DRAWING IS NOT VALID UNLESS IT IS SIGNED AND SEALED BY THE ENGINEER.

Murray Smith & Associates, Inc.
Engineers/Planners
171 St. Helens, Suite 300
Helena, Oregon 97031
PHONE: 503-293-9010
FAX: 503-293-9022



MSA

SHEET C-A4
20 of 167

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A5 9/3/2015 4:22 PM DKH 20.0s (LMS Tech)




TYPICAL RAP SURFACE SECTION AROUND RESERVOIR
SCALE: NTS




- NOTES:**
1. MINIMUM SLOPE OF DRAINAGE DITCH TO BE 1%.
 2. GEOTEXTILE FABRIC TO BE INSTALLED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS USING U-SHAPED WIRE STAPLES.


2' WIDE DRAINAGE DITCH
SCALE: NTS




RESERVOIR FRENCH DRAIN DETAIL
SCALE: 1"=1'-0"



TYPICAL ASPHALT SURFACE SECTION AROUND RESERVOIR
SCALE: NTS



TYPICAL ASPHALT PAVEMENT DETAIL
SCALE: NTS



TYPICAL RAP SURFACE DETAIL
SCALE: NTS

| | | | |
|---------------|--------------|---------------|------|
| BY | REVISION | NO. | DATE |
| | | | |
| | | | |
| | | | |
| DESIGNED: MLM | CHECKED: TPB | APPROVED: TPB | |
| DRAWN: DKH | | | |
| SHEET | | | |
| C-A5 | | | |
| 21 of 167 | | | |

REGISTERED PROFESSIONAL ENGINEER
STATE OF OREGON
MICHAEL L. LINDSEY
LICENSE NO. 6664
RENEWALS 12-31-16

SCALE: VERT. AS SHOWN, HORIZ. AS SHOWN

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: ACCESS ROAD DETAILS

MSA Murray, Smith & Associates, Inc.
Engineers/Planners
21 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-235-9010
FAX: 503-235-9022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV RES.dwg C-A6 9/3/2015 5:59 PM DKH 20.0s (LMS Tech)



UNDERDRAIN SYSTEM TO MONITORING MANHOLE DETAIL 1


SCALE: 1/2" = 1'-0"

RING DRAIN & FOUNDATION DRAIN HPT DETAIL 2

SCALE: 1/2" = 1'-0"

NOTES:

- CAP RING DRAIN AND FOUNDATION DRAIN AT HIGH POINTS AND SLOPE AT APPROXIMATELY 1% IN EACH DIRECTION AROUND TANK TO LOW POINT. ROUTE TO MONITORING MANHOLE AT 2% SLOPE, SEE DETAIL 1, SHEET C-A11.
- OBTAIN GEOTECHNICAL ENGINEER'S APPROVAL OF FINAL SUBGRADE PRIOR TO PLACEMENT OF LEVELING COURSE, GEOTEXTILE, DRAIN ROCK AND STRUCTURAL FILL.
- ALL DRAIN PIPING ENTERING MONITORING MANHOLE TO HAVE RESTRAINED FLAP VALVES ON INLET, SEE SPECIFICATIONS.
- FIVE-FOOT SPAN OF ONE-FOOT DEPTH 3/4"-0" CRUSHED ROCK TO BE PROVIDED ADJACENT TO FOOTING TO ALLOW FOR SECURING OF FOOTING FORM SUPPORT STAKES. PROVIDE 3-INCH DEPTH OF 3/4"-0" CRUSHED ROCK UNDER ENTIRE CONCRETE FOUNDATION.
- RESERVOIR COLUMNS NOT SHOWN FOR CLARITY.
- COMPACTED CRUSHED ROCK FILL AND AGGREGATE PIER INSTALLATION SHALL EXTEND 20' BEYOND THE EDGE OF RESERVOIR FOOTING ON NORTH SIDE, 10' BEYOND ON ALL OTHER SIDES. SEE SHEET C-A1 FOR PROPOSED LIMITS OF FILL AND AGGREGATE PIERS. SEE GEOTECHNICAL REPORT.




RESERVOIR SECTION A

SCALE: 1" = 10' HORIZ, 1" = 10' VERT

| | | | | | | | |
|--|----------------|-----------------|--|--|------------|--------------|---------------|
| BY | REVISION | NO. | DATE | DESIGNED: MLM | DRAWN: DKH | CHECKED: TPB | APPROVED: TPB |
| | | | | | | | |
| | | | | | | | |
| SCALE | VERT: AS SHOWN | HORIZ: AS SHOWN | NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: RESERVOIR SECTION AND UNDERDRAIN DETAILS | | | | | | | |
| Murray, Smith & Associates, Inc. Engineers & Planners 21 S.W. Salmon, Suite 900 Portland, Oregon 97204 | | | | DATE: SEPTEMBER 2015 MSA PROJECT: 14-1586 | | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV RES.dwg C-A7 9/3/2015 4:23 PM DKH 20.0s (LMS Tech)



PLAN
SCALE: 1"=10'

| | | |
|-----|------|----------|
| NO. | DATE | REVISION |
| | | |
| | | |
| | | |




VERT: AS SHOWN
 HORIZ: AS SHOWN
 SCALE
 NOTICE
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06
 SHEET TITLE: RESERVOIR PIPING AND FLOOR PLAN



MSA
 Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900 PHONE 503-225-0910
 Portland, Oregon 97204 FAX 503-225-0922
 DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586

G:\PDX_Projects\14-1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV.dwg C-A8 9/3/2015 3:50 PM DKH 20.0s (LMS Tech)



NOTES:

1. ALL ON-SITE WATER PIPING VALVES AND FITTINGS SHALL BE RESTRAINED.
2. FLEX-TENDS TO HAVE A MINIMUM 16" EXPANSION FOR 18" AND 24" DIAMETER AND 12" EXPANSION FOR 12" DIAMETER AND BE WRAPPED IN POLYETHYLENE PER MANUFACTURER'S RECOMMENDATIONS.
3. FINISH GRADE ON MANHOLE LIDS, VAULTS AND VALVE BOXES PER PROFILES.
4. SEE SHEET C-A9 FOR WATER PIPING SCHEDULE.



| | |
|----------|-----------|
| BY | |
| NO. | DATE |
| DESIGNED | MLM |
| DRAWN | DKH |
| CHECKED | TPB |
| APPROVED | TPB |
| SHEET | C-A8 |
| | 24 of 167 |



| | |
|--|-------|
| VERT. AS SHOWN | SCALE |
| HORIZ. AS SHOWN | |
| NOTICE | |
| IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | |


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
RESERVOIR SITE WATER PIPING PLAN AND DETAILS

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900 PHONE 503-225-9010
Portland, Oregon 97204 FAX 503-225-9022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-C1.V.dwg C-A9 9/3/2015 3:54 PM DKH 20.0s (LMS Tech)



PROFILE - 24" PUMP STATION SUCTION LINE - ALIGNMENT 'D'

SCALE: 1"=20' HORIZ, 1"=10' VERT

WATER PIPING SCHEDULE

RESERVOIR INLET/OUTLET:

- ① STA A0+62
N627573.31, E7656132.72
FURNISH & INSTALL:
1-24" BFV, FLG
1-24" FLEX EXP JT, FLGxMJ
1-1J-2, SEE DET 2, SHT DET-11
- ② STA A1+00
N627565.64, E7656157.84 (NW CORNER)
FURNISH & INSTALL:
CONC VALVE VAULT,
SEE SHT C-A12
- ③ STA A1+78
N627525.19, E7656237.83
CONNECT TO 24" DI
FURNISH & INSTALL:
1-24" DI LS, MJ
1-24" DI SPL, PE, LENGTH AS REQ'D
- ④ STA A1+84=STA E4+56
N627522.34, E7656244.04
FURNISH & INSTALL:
1-24" DI CROSS, MJ
1-24" BFV, MJ
1-24" DI PLUG, MJ, TEMP
- ⑤ STA A1+98
N627516.70, E7656256.37
FURNISH & INSTALL:
1-24" DI 45° HORIZ BEND, MJ
- ⑥ STA A2+09
N627506.01, E7656260.35
FURNISH & INSTALL:
1-24" DI 45° HORIZ BEND, MJ
- ⑦ STA A1+84, 5' RT
N627518.21, E7656242.15
FURNISH & INSTALL:
1-24" BFV, MJ

PUMP STATION SUCTION:


- ⑧ STA D2+05
N627495.37, E7656231.71
CONNECT TO EXIST 24" DI,
REMOVE EXIST 24"x18" DI TEE,
FURNISH & INSTALL:
1-24" DI LS, MJ
2-24" FLGxMJ ADAPTERS
1-24" IJ, SEE DET 3, SHT DET-10
- ⑨ STA D1+84
N627514.08, E7656240.27
FURNISH & INSTALL:
1-24" DI TEE, MJ
1-24" BFV, MJ
1-24" DI PLUG, MJ, TEMP
- ⑩ STA D1+78
N627516.94, E7656234.06
CONNECT TO 24" DI
FURNISH & INSTALL:
1-24" DI LS, MJ
1-24" DI SPL, PE, LENGTH AS REQ'D
- ⑪ STA D0+72
N627561.10, E7656137.76
FURNISH & INSTALL:
1-24" BFV, FLG
1-24" FLEX EXP JT, FLGxMJ
1-1J-2, SEE DET 2, SHT DET-11

12" WATER MAIN:

- ⑫ STA E4+45
N627532.62, E7656248.75
FURNISH & INSTALL:
1-24"x12" RDCR, PE
1-12" DI 45° HORIZ BEND, MJ,
ROLLED DOWN
1-12" BFV, MJ
1-12" DI SPL, PE, LENGTH AS REQ'D
- ⑬ STA E4+15
N627560.12, E7656238.51
FURNISH & INSTALL:
1-12" DI 22½° HORIZ BEND, MJ,
ROLLED UP
- ⑭ STA E1+60
N627747.10, E7656064.66
FURNISH & INSTALL:
1-12" DI 22½° HORIZ BEND, MJ
- ⑮ STA E1+14
N627766.59, E7656022.72
CONNECT TO 12" DI
REMOVE 12" DI PLUG
FURNISH & INSTALL:
1-12" DI SPL, PE,
LENGTH AS REQ'D
1-12" DI LS, MJ
- ⑯ STA E1+00
N627772.33, E7656010.22
CONNECT TO EXIST 6" CI
FURNISH & INSTALL:
2-6" FLGxMJ ADAPTERS
1-6" DI SPL, PE, LENGTH AS REQ'D
1-6" IJ, SEE DET 3, SHT DET-10
1-6" CAP, MJ, TEMP
1-12"x6" RDCR, MJ
1-12" DI SPL, PE,
LENGTH AS REQ'D
1-12" BFV, MJ
1-12" DI PLUG, MJ, TEMP

NOTE:

1. ALL WATER PIPING AND VALVING SHALL BE RESTRAINED.



PROFILE - 12" WATER MAIN - ALIGNMENT 'E'


SCALE: 1"=20' HORIZ, 1"=10' VERT

| | | | | | | | | | | | | | | | |
|---|--|----------------------|--|---|--|----------------------|--|---|--|--|--|---------------------------------------|--|----------------------|--|
| BY | | REVISION | | NO. | | DATE | | DESIGNED: M/M | | DRAWN: D/KH | | CHECKED: T/PB | | APPROVED: T/PB | |
| PROJECT NAME: CITY OF WEST LINN, OREGON | | PROJECT NO. PW 14-06 | | SHEET TITLE: RESERVOIR SITE WATER PIPING PROFILES AND CALL-OUTS | | DATE: SEPTEMBER 2015 | | Murray, Smith & Associates, Inc. Engineers/Planners | | 21 S.W. Salmon, Suite 400 Portland, Oregon 97204 | | PHONE: 503-224-9010 FAX: 503-224-9022 | | MSA PROJECT: 14-1586 | |
| | | | | | | | | | | | | | | | |
| <p>VERT. AS SHOWN HORIZ. AS SHOWN</p> <p>SCALE: 1"=20' HORIZ, 1"=10' VERT</p> <p>NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | | | | | | | | | | | |
| <p>RESERVOIR INLET/OUTLET:</p> <p>PUMP STATION SUCTION:</p> <p>12" WATER MAIN:</p> | | | | | | | | | | | | | | | |
| <p>NOTE:</p> <p>1. ALL WATER PIPING AND VALVING SHALL BE RESTRAINED.</p> | | | | | | | | | | | | | | | |
| <p>PROFILE - 24" PUMP STATION SUCTION LINE - ALIGNMENT 'D'</p> <p>SCALE: 1"=20' HORIZ, 1"=10' VERT</p> | | | | | | | | | | | | | | | |
| <p>PROFILE - 12" WATER MAIN - ALIGNMENT 'E'</p> <p>SCALE: 1"=20' HORIZ, 1"=10' VERT</p> | | | | | | | | | | | | | | | |
| <p>WATER PIPING SCHEDULE</p> | | | | | | | | | | | | | | | |

C:\FDX_Projects\14-1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV.dwg C-A10 9/3/2015 3:57 PM DKH 20.0s (LMS Tech)

NOTES:

1. FOR RESERVOIR PIPING LAYOUT, SEE SHEET C-A7.
2. FOR SITE WATER PIPING PLANS, SEE SHEET C-A8.
3. FLEXTENDS TO HAVE A MINIMUM 16" EXPANSION FOR 18" DIAMETER AND 12" EXPANSION FOR 12" DIAMETER, AND BE WRAPPED IN POLYETHYLENE PER MANUFACTURERS RECOMMENDATIONS.
4. PROVIDE FLAP VALVES AT MANHOLE ENTRANCE FOR ALL DRAIN LINES AND OVERFLOW FROM RESERVOIR AND VAULT. RESTRAIN FLAP VALVES TO PIPING.




PLAN
SCALE: 1"=30'

STORMWATER & DRAIN PIPING SCHEDULE


- RESERVOIR OVERFLOW & DRAIN:**
- 1 N627600.79, E7656114.90 FURNISH & INSTALL: 1-12" 90° HORIZ BEND, MJ 1-12" BFV, FLG 2-12" DI SPL, LENGTH AS REQ'D
 - 2 STA F5+14 N627596.21, E7656121.20 FURNISH & INSTALL: 1-18" FLEX EXP JT, FLGxMJ 1-18"x12" DI TEE, FLG
 - 3 STA F4+13 N627677.72, E7656180.56 MH-1, DECHLORINATION MH FURNISH & INSTALL: 1-48" MH, SEE SHT C-A11
 - 4 N627607.25, E7656110.85 N627609.87, E7656110.42 6" HDPE RES FDN & RING DRAINS, SEE SHTS C-A6 & C-A7
 - 5 STA F4+03 N627685.44, E7656173.79 MH-2, MONITORING MH FURNISH & INSTALL: 1-48" MH, SEE SHT C-A11
 - 6 N627616.95, E7656021.63 FURNISH & INSTALL: 1-6" HDPE TEE IE=438.0%
 - 7 N627435.70, E7656115.88 CB-1 FURNISH & INSTALL: 1-CB, PER CITY STD DWG WL-603 RIM=447.0 IE 12" RCP OUT(N)=443.0
 - 8 N627539.86, E7656158.04 CB-2 FURNISH & INSTALL: 1-CB, PER CITY STD DWG WL-603 RIM=443.4 IE 12" RCP IN(S)=439.9 IE 12" RCP OUT(NW)=439.7
 - 9 N627567.93, E7656265.19 CB-3 FURNISH & INSTALL: 1-CB, TYPE G-2 RIM = 440.0 IE 12" RCP OUT(W)=438.0
 - 10 N627624.40, E7656102.55 MH-2 FURNISH & INSTALL: 1-48" MH W/ BEEHIVE INLET RIM=439.0 IE 12" RCP IN(E)=437.0 IE 12" RCP IN(SE)=437.0 IE 12" RCP OUT(W)=436.5
 - 11 N627630.02, E7656016.76 MH-3, SEDIMENTATION MH FURNISH & INSTALL: RIM=439.0 IE 12" RCP IN(E)=436.3 IE 6" HDPE IN(S)=436.3 IE 12" RCP OUT(NW)=436.1 SEE CITY STD DWG WL-607, SHT C-A13
 - 12 N627635.03, E7656015.91 STORMWATER OUTFALL TO POND, SEE CITY STD DWG WL-614, SHT C-A15
 - 13 N627657.12, E7656055.46 FURNISH & INSTALL: POND OUTLET, SEE CITY STD DWG WL-610, SHT C-A13
 - 14 N627673.72, E7656205.92 STORMWATER OUTFALL TO SWALE, SEE CITY STD DWG WL-614, SHT C-A15
 - 15 N627685.31, E7656209.34 FURNISH & INSTALL: SWALE OUTLET, SEE DET 1, SHT C-A14
 - 16 STA F3+39 N627737.36, E7656135.66 MH-4, TERMINAL DRAINAGE MH FURNISH & INSTALL: 1-48" MH
 - 17 STA F1+20 N627906.11, E7655996.60 STORMWATER OUTFALL TO CREEK W/ GRATE & ARMORING, SEE CITY STD DWG WL-614, SHT C-A15
 - 18 N627706.29, E7656053.77 DETENTION FACILITY LEAK DETECTION PIPE CONN FURNISH & INSTALL: 1-4" HDPE IE=427.0 PROVIDE SEAL PER DET SW-360, SHT C-A15
 - 19 N627688.75, E7656204.32 SWALE FACILITY LEAK DETECTION PIPE CONN FURNISH & INSTALL: 1-4" HDPE IE=422.0 PROVIDE SEAL PER DET SW-360, SHT C-A15
 - 20 N627646.77, E7656194.17 MH-5 FURNISH & INSTALL: 1-48" SDMH RIM=430 GROUND=429% IE 12" RCP IN(SW)=422.3 IE 12" RCP OUT(N)=422.1
- RESERVOIR FOUNDATION & RING DRAINS:**
- FRENCH DRAIN:**
- STORMWATER FACILITIES:**
- 1 N627491.07, E7655931.22 FURNISH & INSTALL: 1-6" HDPE CAP IE=416.0
 - 2 N627416.21, E7656094.92 FURNISH & INSTALL: 1-6" HDPE CAP IE=416.0
 - 3 N627453.64, E7656013.07 FURNISH & INSTALL: 1-6" HDPE TEE IE=415.0
 - 4 N627630.07, E7656093.75 TRANSITION TO NON-PERF HDPE IE=413.0 END DRAINAGE TRENCH FURNISH & INSTALL: 1-TRENCH DAM, SEE DET 3, SHT C-A16

| | | | | | | | | | | | | | | | | | | | | | |
|---|--|----------|--|-----|--|------|--|----------------|--|-----------------------------|--|--------------|--|---------------|--|-------|--|-------|--|-----------|--|
| BY | | REVISION | | NO. | | DATE | | DESIGNED: M/LM | | DRAWN: DKH | | CHECKED: TPB | | APPROVED: TPB | | SHEET | | C-A10 | | 26 of 167 | |
| | | | | | | | | | | | | | | | | | | | | | |
| <p>VERT: AS SHOWN HORIZ: AS SHOWN</p> <p>SCALE</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | | | | | | | | | | | | | | | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: RESERVOIR SITE DRAIN PIPING PLAN AND CALL-OUTS</p> | | | | | | | | | | | | | | | | | | | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-255-9010 FAX 503-255-9022</p> | | | | | | | | | | <p>DATE: SEPTEMBER 2015</p> | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |


C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV.dwg C-A11 9/3/2015 4:32 PM DKH 20.0s (LMS Tech)




PROFILE - DRAIN LINE - ALIGNMENT 'F'
SCALE: 1"=30' HORIZ, 1"=10' VERT



RESERVOIR MONITORING MANHOLE (1)
SCALE: 1/2"=1'-0"



RESERVOIR DECHLORINATION MANHOLE (2)
SCALE: 1/2"=1'-0"




NOTE:
1. CONTRACTOR SHALL PROVIDE 2 BASKETS COMPLETE AS SHOWN IN DETAIL WITH PROJECT.


DECHLORINATION TABLET BASKET (3)
SCALE: NTS

| | | | | | |
|---|------------|--------------|-----------------------------|----------|-------|
| BY | | REVISION | | NO. DATE | |
| DESIGNED: MLM | DRAWN: DKH | CHECKED: TPB | APPROVED: TPB | SHEET | C-A11 |
| | | | | | |
| <p>VERT: AS SHOWN HORIZ: AS SHOWN</p> <p>SCALE</p> <p>NOTICE</p> <p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: RESERVOIR SITE DRAIN PIPING PROFILES AND MANHOLE DETAILS</p> | | | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners</p> | | | <p>DATE: SEPTEMBER 2015</p> | | |
| <p>MSA</p> | | | | | |
| <p>MSA PROJECT: 14-1586</p> | | | | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-CA12.dwg C-A12 9/3/2015 11:10 AM DKT 20.0s (LMS Tech)



PLAN
SCALE: 1/2" = 1'-0"



SECTION A-A
SCALE: 1/2" = 1'-0"


NOTE: VAULT FLOOR DRAIN ROTATED FOR CLARITY.

MATERIAL LIST

- ① 24" DI PIPE, FLGxPE, LENGTH AS REQ'D
- ② 24" RESTR FLG ADAPTER
- ③ 32" DIA MH ACCESS
- ④ 24"x16" DI TEE, FLG
- ⑤ 16" SWING CHKV, FLG, SEE SPECS
- ⑥ 16" DI PIPE, FLGxPE, LENGTH AS REQ'D
- ⑦ 16" RESTR FLG ADAPTER
- ⑧ PRE-CAST CONC PANEL VAULT, 12'x16', OLDCASTLE OR APPV'D EQ
- ⑨ PIPE PENETRATION, TYP, SEE DET 4, SHT C-A17
- ⑩ 4'x8' DOUBLE LEAF AL HATCH, BILCO JD-AL OR EQ, SEE SPECS
- ⑪ PIPE SUPPORTS, (TYP) STAND-ON MODEL S89 OR EQ, SEE NOTES
- ⑫ 12" FLR DR, PRE-CAST IN VAULT
- ⑬ GALV STL ACCESS LADDER, PER VAULT MFR, W/ 1" AL PULL-UP EXTENSION
- ⑭ PRESS TRANSDUCER ASSY, SEE DET 1, THIS SHT
- ⑮ WALL PENETRATION, SEE DET 5, SHT C-A17
- ⑯ 3/4" HDPE SENSING LINE, ROUTE TO RES, SEE C-A7

NOTES:

1. ALL PIPING SHALL BE RESTRAINED UNLESS OTHERWISE SHOWN.
2. WALL PENETRATIONS FOR PIPING TO BE PRECAST IN VAULTS, PROVIDE LINK-SEAL, SEE SPECIFICATIONS.
3. ANCHORS FOR SMALL PIPING SUPPORTS IN VAULT TO BE EXPANSION BOLTS AND SIZED APPROPRIATELY FOR THE SPECIFIED SUPPORT (3/8" MINIMUM DIAMETER), SEE SPECIFICATIONS.
4. PAINT PIPING AND SPECIALS IN VAULT, SEE SPECIFICATIONS. UNLESS NOTED OTHERWISE, PROVIDE A MINIMUM OF 9" CLEARANCE BETWEEN ALL FLANGE FACES AND VAULT WALL.
5. PIPE SUPPORTS ARE SHOWN IN SOME LOCATIONS. CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE LOCATION AND NUMBER OF ALL ADDITIONAL SUPPORTS TO PROPERLY SUPPORT PIPING, VALVES AND EQUIPMENT CONNECTIONS TO PREVENT DEFLECTION AND STRESSES.
6. PROVIDE RESTRAINED MECHANICAL JOINT ON PIPING, 2' FROM OUTSIDE EDGE OF VAULTS, TYP.



NOTES:


1. ALL 1/2" PIPE SHALL BE COPPER, TYPE K, THREADED.
2. FITTINGS SHALL BE BRASS, IPS THREADED.
3. INSTALL ASSEMBLY ON UNISTRUT FRAME MOUNTED TO VAULT WALL WITH 4" WALL OFFSET.

PRESSURE TRANSDUCER ASSEMBLY
SCALE: NTS

| | | | | | | | | | | |
|---|--|----------|--|-----|------|--|---------------|------------|--------------|--------------------------|
| BY | | REVISION | | NO. | DATE | | DESIGNED: MLM | DRAWN: DKH | CHECKED: TPB | APPROVED: TPB |
| | | | | | | | | | | |
| <p>SCALE: VERT: AS SHOWN HORIZ: AS SHOWN</p> <p>NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | | | | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: VALVE VAULT PLAN AND SECTION</p> | | | | | | | | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 800 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022</p> | | | | | | | | | | |
| | | | | | | | | | | DATE: SEPTEMBER 2015 |
| | | | | | | | | | | SHEET C-A12 28 of 167 |

C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A13 9/3/2015 11:45 AM DKT 20.0s (LMS Tech)

THIS DETAIL DRAWING SHALL NOT BE ALTERED OR CHANGED IN ANY MANNER EXCEPT BY THE CITY ENGINEER. IT IS THE RESPONSIBILITY OF THE USER TO ACQUIRE THE MOST CURRENT VERSION OF THE DETAIL.



- NOTE:
1. ALL PRECAST SECTIONS SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-478.
 2. DISTANCE FROM TOP OF OVERFLOW TO MH RIM SHALL BE BASED ON OVERFLOW CAPACITY CALC'S BY DESIGN ENGINEER. ASSUME ORIFICE CONTROL.
 3. 72" MINIMUM DIA. MANHOLE REQUIRED FOR OUTLET OR INLET > 21".
 4. NO STEPS REQUIRED.


POLLUTION/FLOW CONTROL MANHOLE

| | |
|--|-------------|
| | 2010 |
| | DRAWING NO. |
| | WL-607A |

DRAWING WL-607A NOTES

1. SEDIMENTATION MANHOLE
2. PROVIDE 48" DIAMETER MANHOLE.
3. SEE SHEET C-A10 FOR INLET, OUTLET, RIM, AND FLOOR ELEVATIONS.
4. REPLACE MANHOLE FRAME AND COVER WITH 24" DITCH INLET WITH BEEHIVE GRATE, NEENAH FOUNDRY R-2560 SERIES OR EQUAL.

THIS DETAIL DRAWING SHALL NOT BE ALTERED OR CHANGED IN ANY MANNER EXCEPT BY THE CITY ENGINEER. IT IS THE RESPONSIBILITY OF THE USER TO ACQUIRE THE MOST CURRENT VERSION OF THE DETAIL.



- NOTE:
1. CONNECTING PIPE AND TEE SHALL BE 4", 6", OR 8" AWWA C-900 OR ASTM 3034 PVC AND ONE SIZE LARGER THAN THE ORIFICE OPENING.
 2. MAXIMUM ORIFICE OPENING SHALL BE 6" DIAMETER.
 3. STRUCTURES SHALL CONFORM TO STANDARD DRAWING NO. 390 DITCH INLET.
 4. FRAME AND GRATE SHALL CONFORM TO STANDARD DRAWING NO. 400, DITCH INLET FRAME AND GRATE.
 5. PLATE AND GUIDE SHALL BE SECURED FLUSH AGAINST WALL OF STRUCTURE AS APPROVED.
 6. MAINTAINANCE ACCESS REQUIRED TO WITHIN 10' OF CENTER OF BOTH STRUCTURES.


STANDARD DETENTION POND OUTLET

| | |
|--|-------------|
| | DATE: |
| | 2010 |
| | DRAWING NO. |
| | WL-610 |
| | FILE NO. |

DRAWING WL-610 NOTES

1. POND OUTLET STRUCTURE.
2. CONNECTING PIPE AND TEE SHALL BE 4" DIAMETER.
3. LOWER GRATE INLET EL=425.25
4. OVERFLOW GRATE INLET EL=434.0
5. STORM SEWER OUT: 12" RCP IE(OUT)=423.0
6. FOR ORIFICE PLATE, SEE DRAWING WL-611.

THIS DETAIL DRAWING SHALL NOT BE ALTERED OR CHANGED IN ANY MANNER EXCEPT BY THE CITY ENGINEER. IT IS THE RESPONSIBILITY OF THE USER TO ACQUIRE THE MOST CURRENT VERSION OF THE DETAIL.



- NOTE:
- FOR MULTIPLE ORIFICE APPLICATION, A 3" MIN. SPACER IS REQUIRED AS SHOWN. SPACER TO MATCH PLATE GUIDE DIMENSIONS, WIDTH, MATERIAL WITH A WATER TIGHT SEAL.

PLATE AND GUIDE


| | |
|--|-------------|
| | DATE: |
| | 2010 |
| | DRAWING NO. |
| | WL-611 |
| | FILE NO. |

DRAWING WL-611 NOTES

1. POND OUTLET, OUTLET CONTROL PLATE.
2. PROVIDE ORIFICE PLATE WITH ORIFICE SIZE AND ELEVATIONS SHOWN BELOW.

| DIA | ELEV |
|------|-------|
| 1.5" | 432.0 |
| 1.0" | 430.0 |
| 1.0" | 425.5 |

| | |
|-----------|-----|
| BY | |
| NO. | |
| DATE | |
| REVISION | |
| DESIGNED: | MLM |
| DRAWN: | DKH |
| CHECKED: | TPB |
| APPROVED: | TPB |




| | |
|--|-------|
| VERT. AS SHOWN | SCALE |
| HORIZ. AS SHOWN | |
| NOTICE | |
| IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | |

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06
 SHEET TITLE: STORMWATER DETENTION FACILITY DETAILS


| | |
|--|----------------|
| | DATE: |
| | SEPTEMBER 2015 |
| 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-255-9010 FAX: 503-255-9022 | |

| | |
|--|---------|
| | DATE: |
| | 14-1586 |


C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A14 9/3/2015 11:45 AM DKT 20.0s (LMS Tech)



SWALE OUTLET DETAIL 1
 SCALE: 3/8"=1'-0"



CONCRETE FLOW SEPARATOR DETAIL 2
 SCALE: 1"=1'-0"



TYPICAL SWALE SECTION 3
 SCALE: 1"=1'-0"

- NOTES:
1. SEE LANDSCAPING DETAILS FOR STORMWATER SWALE PLANTINGS.
 2. SLOPE SWALE 1%.
 3. FORM CONCRETE FLOW SEPARATOR ON GEOTEXTILE OVER LINER.

| | | | |
|---------------|------------|--------------|---------------|
| BY | REVISION | NO. | DATE |
| | | | |
| DESIGNED: MLM | DRAWN: RLF | CHECKED: TPB | APPROVED: TPB |
| SHEET | | | 30 of 167 |
| C-A14 | | | |





| | |
|----------------|--|
| VERT. AS SHOWN | HORIZ. AS SHOWN |
| SCALE | NOTICE |
| 0 | IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE |


PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06
 SHEET TITLE:
STORMWATER SWALE DETAILS

MSA Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900 Portland, Oregon 97204
 PHONE 503-255-8010 FAX 503-255-8022
 DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586

C:\PDX_Projects\14_1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A15 9/3/2015 11:45 AM DKT 20.0s (LMS Tech)



BEEHIVE GRATE



24" x 4" REVERSIBLE MANHOLE FRAME

DESIGNER INFORMATION

- If connecting to a combination sewer main install a flap valve or approved equal to prevent odor emissions.
- Size inlet based on calculated flows & manufacturers recommendations.
- Wire rope between 1/8"-3/16" diameter, stainless steel, 7 strands of 19 wires.

CONSTRUCTION NOTES

- Secure grate in place with 5/4" of wire rope. Loop ends of wire rope around U-bolt and grate. Crimp each end of wire rope with 3" overlap.
- Drill 2" deep holes into pipe and epoxy #4 rebar U-bolt (2' x 4") in holes.
- Grate to be cast iron, ASTM A48 CL30.

- DRAWING NOT TO SCALE -


STORMWATER MANAGEMENT MANUAL TYPICAL DETAILS

- Green Streets -
Beehive Inlet Grate
Overflow Inlets




NUMBER
SW-350

- CONSTRUCTION NOTES**
- ADHERE 30 MIL LINER TO CONCRETE WITH TOP COAT TC MOLDABLE SEALANT, OR APPROVED EQUAL.
 - SECURE LINER TO CONCRETE WITH 2" ALUMINUM FLAT BAR, PLACED AS DIRECTED (CURB SIDE OR ENTIRE FACILITY).
 - ATTACH FLAT BAR WITH CONCRETE HIT ANCHORS, 24" O.C.
 - TRIM EXCESS LINER TO THE TOP OF THE FLAT BAR.



LINER ATTACHMENT



PIPE BOOT

DESIGNER INFORMATION

- Liner materials to be HDPE or PVC. Liner to extend from top of topsoil to the bottom of excavation.
- 3" of concrete is required on all sides of attachment. Adjust sidewalk depth as necessary.
- Liner required when face of new curb is less than 2' from OD of adjacent water main.
- Liner required on neighborhood collectors and higher street classifications.
- Liner may be required on local streets with transit routes, higher traffic volumes, or when a facility is adjacent to travel lane at the discretion of the City Engineer.
- In the Columbia South Shore Well Field Wellhead Protection Area or areas with contaminated soils the facility must be completely lined with a 40 mil liner unless facility's bottom and sides are monolithic concrete.
- Liners may be required near basements or other underground structures.
- Trees allowed in lined facilities only at the discretion of City of Portland staff.

- DRAWING NOT TO SCALE -


STORMWATER MANAGEMENT MANUAL TYPICAL DETAILS

- Green Streets -
Liner Attachment & Pipe Boot Detail
Miscellaneous



NUMBER
SW-360

THIS DETAIL DRAWING SHALL NOT BE ALTERED OR CHANGED IN ANY MANNER EXCEPT BY THE CITY ENGINEER. IT IS THE RESPONSIBILITY OF THE USER TO ACQUIRE THE MOST CURRENT VERSION OF THE DETAIL.



D = PIPE DIAMETER
W = BOTTOM WIDTH OF CHANNEL
P = WETTED PERIMETER OF CHANNEL

| DESIGN VELOCITY FT./SEC | ROCK CLASSIFICATION BY WEIGHT |
|-------------------------|-------------------------------|
| 6 - 10 | 200 LBS. |
| 10 - 12 | 1/4 TON |
| 12 - 14 | 1/2 TON |
| 14 - 16 | 1 TON |
| 16 - 18 | 2 TON |

SELECTION OF RIP RAP (SEE NOTE 1)

NOTE:

- DIMENSIONS FOR RIP RAP APPLY TO FLOWS
 - < 2 CFS RIP RAP FOR FLOWS
 - > 2 CFS MUST BE DESIGNED BY AN ENGINEER
 - FLOWS > 20 FPS SHALL USE ENERGY DISSIPATOR
- TYPE OF RIP RAP
 - A. REGULAR QUARRY STONE CLASS 50-200
 - B. COBBLESTONE
 - C. CONCRETE (ONLY ALLOWED UPON APPROVAL OF THE CITY)
- PLACEMENT
 - A. MINIMUM DEPTH = 1 1/2 TIMES AVERAGE STONE SIZE.
 - B. ROCKS SHALL BE PLACED TO PROVIDE A MINIMUM OF VOIDS.
 - C. SURFACE ROCKS OR CONCRETE SHALL PROTRUDE AT LEAST 1/2 THEIR VERTICAL DIMENSION.
 - D. RIP RAP IS TO BE PLACED OVER A NATURAL BEDDING, OR IT MAY BE GROUTED OR PLACED OVER A GRAVEL BEDDING AS REQUIRED BY THE CITY.

STORM SEWER OUTFALL



DATE: 2010
DRAWING NO. WL-614
FILE NO.

DRAWING WL-614 NOTES

- A. POND INLET ARMORING:
- PEAK RUNOFF < 1 CFS.
 - PIPE DIA=12"
 - PIPE IE=437.0
 - REFER TO CITY STANDARD DRAWING WL-613 FOR ENDWALL.
 - RIP RAP SHALL BE 200 LBS, 25'L, 6'W WITH 2' MINIMUM DEPTH.
- B. SWALE INLET ARMORING:
- PEAK RUNOFF < 1 CFS.
 - PIPE DIA=12"
 - PIPE IE=422.0
 - ENDWALL NOT REQ'D
 - RIP RAP SHALL BE 200 LBS, 10'L, 6'W, WITH 2' MINIMUM DEPTH.
- C. CREEK OUTFALL ARMORING:
- PEAK RUNOFF 7,000 GPM (EMERGENCY OVERFLOW).
 - RIP RAP SHALL BE 1 TON, 10'L, 6'W, WITH 2' MINIMUM DEPTH.
 - REPLACE ENDWALL WITH CITY STANDARD DITCH INLET, CITY STANDARD DRAWING WL-603.

RIM=354%
GROUND=353%
IE (1N)=352%

BY: _____ SHEET C-A15 31 of 167

REVISION: _____

NO. DATE _____

DESIGNED: MLM
DRAWN: RLF
CHECKED: TPB
APPROVED: TPB

RENEWED 12-31-16

SCALE: VERT: AS SHOWN, HORIZ: AS SHOWN

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06


STORMWATER DETAILS

Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900 PHONE 503-225-9010
Portland, Oregon 97204 FAX 503-225-9022


DATE: SEPTEMBER 2015

MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A16 9/3/2015 11:45 AM DKT 20.0s (LMS_Tech)



PLAN




ELEVATION

NOTES:

1. CONCRETE ANCHOR BLOCKS SHALL BE CONSTRUCTED USING FORMS. REMOVE FORMS PRIOR TO BACKFILLING TRENCH.
2. ALL CONCRETE SHALL BE COMMERCIAL GRADE CONCRETE, 3000 PSI COMPRESSIVE STRENGTH OR GREATER.
3. CENTER TO CENTER MAX SPACING OF CONCRETE ANCHOR BLOCKS SHALL BE 35'.
4. TWO (2) HDPE FLEX RESTRAINT DEVICES TO BE ATTACHED BY THE METHOD OF ELECTROFUSION TO OPPOSING EXTERIOR SIDES OF HDPE PIPE, AND PER MANUFACTURER'S RECOMMENDATIONS. PROVIDE A MINIMUM OF 3" OF CONCRETE COVER OVER RESTRAINT DEVICE WITHIN ANCHOR BLOCK. SEE SPECIFICATIONS.
5. FURNISH & INSTALL FILTER FABRIC ON 5" SQUARE WIRE MESH INLET COVER PRIOR TO INSTALLING INLET COVER OVER 3" WEEPHOLE'S INLET END. FILTER FABRIC SHALL BE MIRAFI 140N, OR APPROVED EQUAL.


CONCRETE ANCHOR BLOCK (1)
SCALE: NTS



NOTE:

1. INSTALL DRAINAGE TRENCH AFTER COMPLETING AGGREGATE PIERS IMPROVEMENTS.

DRAINAGE TRENCH DETAIL (2)
SCALE: NTS



NOTE:

1. CONSTRUCT TRENCH DAMS WITH BENTONITE, DO NOT USE TOPSOIL FOR FILLING.

DRAINAGE TRENCH - TRENCH DAM (3)
SCALE: NTS

| | |
|----------------|-----------|
| BY | |
| NO. | DATE |
| REVISION | |
| DESIGNED: MLM | |
| DRAWN: DKH/RLF | |
| CHECKED: TPB | |
| APPROVED: TPB | |
| SHEET | C-A16 |
| | 32 of 167 |





| | |
|--|-------|
| VERT. AS SHOWN | SCALE |
| HORIZ. AS SHOWN | |
| NOTICE | |
| IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | |

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE: MISCELLANEOUS SITEWORK DETAILS

MSA
Murray, Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE 503-255-9010
FAX 503-255-9022
DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A17 9/3/2015 11:45 AM DKT 20.0s (LMS Tech)



This drawing reveals the copyrighted intellectual property of Columbia Cascade Company. Not for use by others without our express, written authorization. Authorization for use is hereby granted to architects, landscape architects and similar design professionals solely for the purpose of specifying TimberForm products.


COLUMBIA CASCADE COMPANY
Makers of TimberForm®, PipeLine®, RePlay®, TimberForm®-2, InterPlay®, CycLoops® and CycLoops® Products.
1300 S.W. Sixth Avenue, Suite 210 Portland, Oregon 97201-3454 Telephone 503/223-1157 Facsimile 503/223-4530 U.S.A. WWW.TIMBERFORM.COM

Title: **TIMBERFORM MODEL NO. 2561 8 x 8 TIMBER BOLLARD**

Scale: 3/4" = 1'-0" (20:1)
Drawn by: AT 07-04-10
Checked by: [blank]


Sheet 1 of 1

BOLLARD DETAIL (1)
SCALE: NTS




NOTES:
1. STRUCTURAL FILL MATERIALS PLACED ON EXISTING SLOPES STEEPER THAN 5H:1V SHALL PROCEED IN HORIZONTAL LIFTS FROM A MAXIMUM 8-FT WIDE HORIZONTAL BENCH EXCAVATED INTO THE FACE OF EXISTING SLOPE AT THE TOE OF THE NEW FILL SLOPE.
2. FILL SLOPES SHALL BE OVERBUILT THEN CUT BACK TO FINAL GRADE.

TYPICAL DETAIL FOR FILLING ON SLOPES (2)
SCALE: NTS




NOTE:
1. SEAL ALL WALL PIPE PENETRATIONS WITH LINK SEAL TYPE SEAL UNLESS OTHERWISE NOTED. FOR PIPE SIZES TOO SMALL FOR LINK SEALS, SEAL WITH EPOXY SEALANT.

WALL PIPE PENETRATION (4)
SCALE: NTS



NOTES:
1. SUPPORTS AND HARDWARE SHALL BE TYPE 304 STAINLESS STEEL.
2. PROVIDE INSULATING WASHERS.

S89 PIPE SUPPORT AT FLANGE (3)
SCALE: NTS



CONDUIT/SMALL PIPE WALL PENETRATION (5)
SCALE: NTS

| | |
|----------|-----------|
| BY | |
| NO. | |
| DATE | |
| DESIGNED | MLM |
| DRAWN | DKH |
| CHECKED | TPB |
| APPROVED | TPB |
| SHEET | C-A17 |
| | 33 of 167 |



| | |
|--|-------|
| VERT. AS SHOWN | SCALE |
| HORIZ. AS SHOWN | |
| NOTICE | |
| IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | |


PROJECT NAME: **CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06**

SHEET TITLE: **MISCELLANEOUS DETAILS**

MSA Murray Smith & Associates, Inc. Engineers/Planners
121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586


G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV.DETS.dwg C-A18 9/3/2015 11:45 AM DKT 20.0s (LWS Tech)




NOTE:

1. CHAIN LINK FABRIC SHALL BE BLACK PVC COATED.

CHAIN LINK FENCE ①
SCALE: NTS C-A1



CHAIN LINK GATE ②
SCALE: NTS C-A1




VERT: AS SHOWN
HORIZ: AS SHOWN
SCALE
NOTICE
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE: FENCING DETAILS - 1


MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE 503-225-9010
FAX 503-225-9022
DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

| | | | |
|-----------|------|----------|--------|
| NO. | DATE | REVISION | BY |
| DESIGNED: | MJM | | |
| DRAWN: | DKH | | |
| CHECKED: | TPB | | |
| APPROVED: | TPB | | |
| SHEET | | | C-A18 |
| 34 | | | of 167 |


G:\PDX\Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-CIV DETS.dwg C-A19 9/3/2015 11:45 AM DKT 20.0s (LMS Tech)



DOUBLE GATE SECTION (1)
SCALE: 3/4"=1'-0"




TYP PILASTER DETAIL (2)
SCALE: 3"=1'-0"



TYPICAL PILASTER SECTION (3)
SCALE: NTS

- NOTES:**
1. CONTRACTOR SHALL VERIFY SOIL CONDITIONS AT THE FOOTINGS AND MAKE ANY NECESSARY CORRECTIONS TO PLACE THE FOOTINGS ON FIRM NATIVE SOIL OR STRUCTURAL FILL COMPACTED TO 95% OF MAXIMUM DENSITY AT OPTIMUM MOISTURE PER ASTM D698 OR ASTM D1557. THE COMPACTION SHALL BE VERIFIED BY THE ENGINEER.
 2. CONCRETE SHALL BE 3,000 PSI MINIMUM AT 28 DAYS. MIXING, PLACING AND CURING OF CONCRETE SHALL BE IN ACCORDANCE WITH ACI 318 AND 1BC SECTION 1903. ALL CONCRETE SHALL HAVE A MAXIMUM WATER/CONCRETE RATION 0.45.
 3. ALL NON-SHRINK GROUT SHALL BE NON-METALLIC GROUT CONFORMING TO ASTM C1107, AND SHALL HAVE A SPECIFIED MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 5,000 PSI.
 4. GROUT SOLID.
 5. HOOK ALL REINFORCING THAT CANNOT BE EXTENDED.
 6. TYPICAL REINFORCING SHOWN. REFER TO DETAILS FOR SPECIFIC OR ADDITIONAL REINFORCING.
 7. LAP ALL REINFORCING A MINIMUM OF 46 BAR DIAMETERS.



TYPICAL PANEL SECTION (4)
SCALE: 3/4"=1'-0"

| | | | | | | | |
|----|----------|-----|------|---------------|------------------|---------------|-----------|
| BY | REVISION | NO. | DATE | DESIGNED: MLM | CHECKED: RLF/DKH | APPROVED: TPB | SHEET |
| | | | | | | | C-A19 |
| | | | | | | | 35 of 167 |

REGISTERED PROFESSIONAL ENGINEER
MICHAEL L. L. RENEWS 12-31-16

SCALE: VERT: AS SHOWN, HORIZ: AS SHOWN
NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: FENCING DETAILS - 2


Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE 503-225-9010
FAX 503-225-0022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

C:\WORK\Projects\41100 - Bolton Reservoir Replacement\MSA\Sheet\Profile - RA - PW - A-20 - REVISED - 12/29/06 - 10:29 AM - K - 2009 (11/18) (REV)



ACCESS ROAD - ALIGNMENT 'RA' PROFILE
 SCALE: 1"=30' HORIZ, 1"=10' VERT




ACCESS ROAD - ALIGNMENT 'RB' PROFILE
 SCALE: 1"=30' HORIZ, 1"=10' VERT

| | | | | | |
|--|--|------------------------------------|------|----------|----|
| | | NO. | DATE | REVISION | BY |
| | | | | | |
| | | DESIGNED: JHF | | | |
| | | DRAWN: JLF/TKC | | | |
| | | CHECKED: YLJ | | | |
| | | APPROVED: TPS | | | |
| | | SHEET C-A20 36 of 167 | | | |


| | |
|---|--|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: RESERVOIR SITE ACCESS ROAD VERTICAL PROFILES |
|---|--|

| | |
|--|--|
| | DATE: SEPTEMBER 2005 PHONE 503-225-0950 FAX 503-225-0922 121 SW Salmon, Suite 900 Portland, Oregon 97205 |
|--|--|


g:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED A\14-1586-OR-A-ARCH.dwg A-A1 9/3/2015 1:50 PM DKH 20.0s (LMS Tech)



RESERVOIR EIFS PLAN
SCALE: 1/16" = 1'-0"




RESERVOIR WALL EIFS DETAIL
SCALE: NTS




WALL SECTION A
SCALE: 3/8" = 1'-0"

- NOTES:**
1. ALL 2" EIFS SECTIONS AND CUTOUTS TO HAVE 1" BEVELED EDGES.
 2. ALL SURFACES STANDARD SHOTCRETE SMOOTH FINISH.



RESERVOIR ELEVATION 2
SCALE: 1/16" = 1'-0"



RESERVOIR ART DECO EXTERIOR FINISH 3
SCALE: 1/4" = 1'-0"

BY: [] REVISION: [] SHEET: A-A1 37 of 167

NO. DATE: [] DESIGNED: MLM DRAWN: DKH CHECKED: TPB APPROVED: TPB


REGISTERED PROFESSIONAL
MICHAEL L. PETERSON
NO. 66840
RENEWED 12-31-16
RENEWS 12-31-16

VERT: AS SHOWN HORIZ: AS SHOWN SCALE: [] NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE.

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
RESERVOIR EXTERIOR FINISH WORK


Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900 PHONO 503-235-9010
Portland, Oregon 97204 FAX 503-235-9022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586



LEGEND


- STORMWATER QUALITY PLANTINGS: SIDE SLOPES
- STORMWATER QUALITY PLANTINGS: TREATMENT AREA
- PLANTING AREAS
- ROUGH SEED
- EXISTING TREES TO REMAIN



SHRUB PLANTING TEMPLATE
1" = 30'

KEY NOTES

- 1. PROTECT EXISTING TREES IN THIS AREA. REPAIR AND REPLACE ALL EXISTING PLANTING AREAS DAMAGED BY CONSTRUCTION ACTIVITIES. WORK SHALL BE DONE TO THE OWNER'S SATISFACTION. THIS IS A REQUIREMENT FOR ALL SITE WORK ASSOCIATED WITH THE PROJECT WHETHER SPECIFICALLY INDICATED OR OTHERWISE OCCURRING DURING THE COURSE OF NORMAL CONSTRUCTION ACTIVITIES.



PLANT SCHEDULE: GENERAL LANDSCAPE

| SYMBOL | BOTANICAL NAME | COMMON NAME | SIZE | SPACING | QUANTITY | E/D | COMMENTS |
|---------------|----------------------------|-------------------------|---------------|----------|----------|-----|----------------------------------|
| TREES | | | | | | | |
| | ACER CIRCINATUM | VINE MAPLE | 2" CAL. | AS SHOWN | 20 | D | BRANCHED AT 4'-0"; NARROW FORM |
| | CALOCEDRUS DECURRENS | INCENSE CEDAR | 6-8FT. | AS SHOWN | 22 | E | |
| | PSEUDOTSUGA MENZIESII | DOUGLAS FIR | 6-8FT. | AS SHOWN | 14 | I | |
| | QUERCUS GARRYANA | OREGON WHITE OAK | 2" CAL. | AS SHOWN | 6 | D | |
| | PICEA ENLEMANNII | ENLEMANN SPRUCE | 6-8FT. | AS SHOWN | 17 | E | |
| | THUJA PLICATA | WESTERN RED CEDAR | 6-8FT. | AS SHOWN | 12 | L | |
| SHRUBS | | | | | | | |
| | GASH GAULTHERIA SHALLON | SALAL | #1 | 36" O.C. | | E | |
| | MANE MAHONIA NERVOSA | DULL OREGON GRAPE | #1 | 24" O.C. | | E | |
| | OECE OEMLARIA CERASIFORMIS | OCEAN SPRAY | #5 | 36" O.C. | | D | |
| | POMU POLYSTICHUM MUNIUM | SWORDFERN | #1 | 36" O.C. | | E | |
| SEED | | | | | | | |
| | HYDROSEED PROTOME 710 | FLOWERING XERISCAPE MIX | 2 LBS/1000 SF | | | | |
| BULBS | | | | | | | |
| | LILIUM COLUMBIANUM | TIGER LILY | BULB | | 200 | | PLANT IN CLUSTERS SEE SHEET L-07 |

PLANT SCHEDULE: STORMWATER QUALITY SWALE (380 SF)

| SYMBOL | BOTANICAL NAME | COMMON NAME | SIZE | SPACING | QUANTITY | E/D | COMMENTS |
|-------------------|-----------------------|-----------------------|--------------|----------|----------|-----|--|
| HERBACEOUS | | | | | | | |
| | JUNCUS PATENS | SPREADING RUSH | 4" POT | 12" O.C. | 218 | E | PLANT IN SAME SPECIES GROUPS OF 5-7 PLANTS |
| | SCIRPUS MICROCARPUS | SMALL FRUITED BULRUSH | 4" POT | 12" O.C. | 219 | E | |
| SEED | | | | | | | |
| | HYDROSEED PROTOME 440 | NATIVE BIO-FILTER MIX | 1 LB/1000 SF | | | | |

PLANT SCHEDULE: STORMWATER QUALITY DETENTION FACILITY (6,000 SF)

| SYMBOL | BOTANICAL NAME | COMMON NAME | SIZE | SPACING | QUANTITY | E/D | COMMENTS |
|----------------------------------|-----------------------|-----------------------|--------------|---------|----------|-----|--|
| TREATMENT AREA (1,080 SF) | | | | | | | |
| HERBACEOUS | | | | | | | |
| | JUNCUS PATENS | SPREADING RUSH | PLUGS | 6/SF | 621 | E | PLANT IN SAME SPECIES GROUPS OF 5-7 PLANTS |
| | SCIRPUS MICROCARPUS | SMALL FRUITED BULRUSH | PLUGS | 6/SF | 621 | E | |
| SEED | | | | | | | |
| | HYDROSEED PROTOME 440 | NATIVE BIO-FILTER MIX | 1 LB/1000 SF | | | | |

SIDE SLOPES (4,920 SF)

| | | | | | | | |
|----------------------------|--------------------------|-----------------------|--------------|----------|-------|---|--|
| TREES | | | | | | | |
| | ACER CIRCINATUM | VINE MAPLE | #2/2' HT. | SINGLE | 10 | D | |
| | FRAXINUS LATIFOLIA | OREGON ASH | #2/3' HT. | SINGLE | 7 | D | |
| LARGE SHRUBS | | | | | | | |
| | CORNUS SERICEA | RED-TWIG DOGWOOD | #1 | 36" O.C. | 98 | D | PLANT IN SAME SPECIES GROUPS OF 5-7 PLANTS |
| | ROSA NUTKANA | NOOTKA ROSE | #1 | 48" O.C. | 99 | D | |
| MEDIUM/SMALL SHRUBS | | | | | | | |
| | MAHONIA AQUIFOLIUM | OREGON GRAPE | #1 | 36" O.C. | 148 | D | |
| | SYMPHORICARPOS ALBA | SNOWBERRY | #1 | 36" O.C. | 147 | D | |
| GROUNDCOVER | | | | | | | |
| | ARCTOSTAPHYLOS LIVA-URSI | KINNIKINNICK | 4" POT | 12" O.C. | 1,722 | E | |
| | MAHONIA REPENS | CREeping MAHONIA | 4" POT | 12" O.C. | 1,722 | E | |
| SEED | | | | | | | |
| | HYDROSEED PROTOME 440 | NATIVE BIO-FILTER MIX | 1 LB/1000 SF | | | | |

PLANTING NOTES

1. CONTRACTOR TO VERIFY LOCATION OF EXISTING TREES INDICATED TO REMAIN PRIOR TO SOIL PREPARATION. PROTECT ALL TREES AND SHRUBS INDICATED TO REMAIN. COORDINATE WITH THE OWNER'S REPRESENTATIVE.
2. PLANTING AREAS TO BE SUFFICIENTLY CLEANED OF ALL CONSTRUCTION MATERIALS, INCLUDING IMPORTED ROCK, TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE BEFORE BEGINNING ANY LANDSCAPE WORK.
3. IDENTIFY ALL PLANTING AREAS IN FIELD WITH WHITE FIELD-MARKING CHALK OR APPROVED EQUAL. PLANTING BEDS TO BE ADJUSTED AND APPROVED BY OWNER'S REPRESENTATIVE PRIOR TO PLANT LOCATION.
4. FOR PLANTING OCCURRING IN MASSES OF SAME SPECIES PLANT, LABELING REFERS TO ALL ADJACENT IDENTICAL SYMBOLS. REFER TO DETAILS AND LEGEND FOR SPACING INFORMATION.
5. THE OWNER'S REPRESENTATIVE WILL APPROVE INDIVIDUAL PLANT MATERIAL AND LOCATION OF PLANT MATERIAL PRIOR TO INSTALLATION. REFER TO SPECIFICATIONS FOR PROCEDURE.
6. SHRUBS AND GROUNDCOVER TO BE PLANTED A MINIMUM OF ONE HALF THEIR ON CENTER SPACING AWAY FROM PAVEMENT EDGES; UNLESS OTHERWISE NOTED.
7. PROVIDE ROOT BARRIER AROUND ALL TREES WITHIN 5' OF PAVING, CURBS, WALLS, BUILDINGS, UTILITY DUCTS AND OTHER APPURTENANCES.
8. PLANT QUANTITIES INDICATED ARE FOR THE CONVENIENCE OF THE CONTRACTOR ONLY. CONTRACTOR IS RESPONSIBLE FOR PROVIDING PLANTS IN QUANTITIES AND LOCATIONS SHOWN ON DRAWINGS.
9. PROVIDE JUTE NETTING ON ALL SLOPES WITH GRADIENT OF 2:1 OR GREATER AS DIRECTED IN THE FIELD BY THE OWNER'S REPRESENTATIVE. STAPLE FABRIC TO GROUND WITH METAL STAKES AT 4' O.C. SEE EROSION CONTROL MATTING DETAIL IN THESE DRAWINGS.

WATER QUALITY PLANTING REQUIREMENTS
(Per City of Portland Stormwater Management Manual)

STORMWATER QUALITY SWALE:
TOTAL AREA=380 SF
PLANTS REQUIRED: 115 herbaceous/100SF=437

DETENTION FACILITY:
TOTAL AREA=6,000 SF
TREATMENT AREA=1,080 SF
PLANTS REQUIRED: 115 Herbaceous Plants/100 SF = 1,242

SIDE SLOPES=4,920 SF
TREES REQUIRED (Ev. or Decid.): 1 TREE/300 SF= 17
SHRUBS REQUIRED:
Large Shrubs: 4/100 SF=197
Medium to Small Shrubs: 6/100 SF=295
Groundcover: 70/100 SF=3,444

REGISTERED
586
Chelsea M. McCann
LANDSCAPE ARCHITECT
OREGON

NOTICE
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

LANDSCAPE PLAN
RESERVOIR SITE

DESIGNED: JP/KD
DRAWN: KD
CHECKED: JP/KD
APPROVED: CM

NO. DATE

REVISION


BY

SHEET
L-1
55 of 167


WALKER
111 SW OAK SUITE 200
PORTLAND, OR 97204
503-228-3122

Murray, Smith & Associates, Inc.
Engineers/Planners
121 S. Main, Suite 400
Portland, Oregon 97204
PHONE 503-225-4410
FAX 503-225-4422


DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586,0601



3 SHRUB AND GROUND COVER PLANTING
SCALE: 3/4" = 1'-0"




1 CONIFER TREE PLANTING
SCALE: 3/8" = 1'-0"



NOTE:
- SEE PLANT SCHEDULE FOR EACH PLANT'S APPROPRIATE O.C. SPACING.
- PLANTING PLAN SHOWING INDIVIDUAL LOCATION OF A SHRUB AND OR GROUND COVER TAKE PRECEDENT OVER THIS DETAIL.



4 SHRUB AND GROUND COVER TRIANGULAR SPACING
SCALE: 3/4" = 1'-0"



2 DECIDUOUS TREE PLANTING
SCALE: 3/8" = 1'-0"


G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED_B\14-1586-OR-B-ARCH.dwg A-BI 9/3/2015 11:04 AM DKH 20.0s (LMS Tech)

NOTE:
 1. FIELD VERIFY EXISTING DIMENSIONS AND LOCATIONS PRIOR TO MANUFACTURING TRUSSES AND ROOF COMPONENTS MODIFICATION.




| | | | |
|--|----------|---|------------|
| | NO. DATE | DESIGNED: AMB | BY |
| | | DRAWN: DKH | SHEET A-BI |
| | | CHECKED: JSJ | 57 of 167 |
| | | APPROVED: JSJ | |
| <p>SCALE: VERT: AS SHOWN, HORIZ: AS SHOWN</p> <p>NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | | | |
| <p>SHEET TITLE: EXISTING ROOF DEMO PLAN AND PROPOSED ROOF PLAN</p> | | | |
| | | <p>DATE: SEPTEMBER 2015</p> | |
| <p>121 S.W. Salmon, Suite 900 Portland, Oregon 97204</p> | | <p>PHONE: 503-253-9010 FAX: 503-253-9022</p> | |
| <p>MSA PROJECT: 14-1586</p> | | | |


c:\pdx_projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED_B\14-1586-OR-B-ARCH.dwg A-B2 9/3/2015 11:04 AM DKH 20.0s (LMS Tech)




SOUTH ELEVATION
SCALE: 1/4"=1'-0"



EAST ELEVATION
SCALE: 1/4"=1'-0"




NORTH ELEVATION
SCALE: 1/4"=1'-0"



WEST ELEVATION
SCALE: 1/4"=1'-0"

- NOTES:**
1. INSTALL NEW ROOF SYSTEM ON EXISTING BUILDING STRUCTURE, SEE STRUCTURAL SHEETS.
 2. ATTIC ACCESS DOOR SHALL BE EQUIPPED WITH MORTISED/BUTT HINGES AND LOCKING DEAD-BOLT.

| | | | |
|-----------|------|----------|----|
| NO. | DATE | REVISION | BY |
| | | | |
| DESIGNED: | AMR | | |
| DRAWN: | DKH | | |
| CHECKED: | JSJ | | |
| APPROVED: | JSJ | | |



| | | |
|-------|--|-----------------|
| SCALE | VERT: AS SHOWN | HORIZ: AS SHOWN |
| | | |
| | NOTICE | |
| | IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | |


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: **ARCHITECTURAL ELEVATIONS**

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Sullivan, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022


DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED_B\14-1586-OR-B-ARCH.dwg A-B3 9/3/2015 11:04 AM DKH 20.0s (LMS Tech)




SECTION A-A2
SCALE: 3/4"=1'-0"

NOTE:
1. PAINT ALL EXPOSED SURFACES.



GABLE END DETAIL 1
SCALE: 1 1/2"=1'-0"




NOTES:
1. VERIFY ALL EXISTING ROOF LAYOUT AND COMPONENTS DIMENSIONS.
2. LOOSE FILL CELLULOSE OR PERLITE INSULATION OVER EXISTING INSULATED ROOFING TO MEET CURRENT OEESC REQUIREMENTS.
3. PROVIDE AND INSTALL SKYLIGHT HATCH TO ALLOW CLEARANCE OF PUMP ASSEMBLY THROUGHOUT ENTIRE ACCESS OPENING.


PUMP ACCESS SKYLIGHT 2
SCALE: 3/4"=1'-0"

| LOUVER SCHEDULE | | | | |
|-----------------|--------------------|---------|------|-----------------|
| TAG | TYPE | SIZE | CFM | MAKE & MODEL NO |
| L-1 | PENTHOUSE, EXHAUST | 36"X36" | 4750 | GREENHECK - WRH |
| L-2 | PENTHOUSE, EXHAUST | 36"X36" | 4750 | GREENHECK - WRH |
| L-3 | PENTHOUSE, EXHAUST | 18"X18" | 1120 | GREENHECK - WRH |

LOUVER SCHEDULE NOTES:
1. EQUIPMENT MANUFACTURERS AND MODEL NUMBERS PROVIDED AS BASIS OF DESIGN. APPROVED EQUAL MANUFACTURERS EQUIPMENT WILL BE CONSIDERED.
2. LOUVER SIZES GIVEN ARE FOR REFERENCE ONLY AND SHALL BE FIELD VERIFIED PRIOR TO ORDERING OR FABRICATION OF EQUIPMENT. HVAC CONTRACTOR SHALL COORDINATE WITH THE GENERAL CONTRACTOR TO VERIFY SIZES AND LOCATIONS OF OPENINGS.



ROOF RIDGE 3
SCALE: 1 1/2"=1'-0"



PENTHOUSE LOUVER CURB DETAIL 4
SCALE: 3/4"=1'-0"

BY: _____ SHEET: A-B3 59 of 167

NO. DATE _____ DESIGNED: AMB DRAWN: DKH CHECKED: JSJ APPROVED: JSJ

REVISION _____

REGISTERED PROFESSIONAL ENGINEER
ALEX M. BAIRD
RENEWED 12-31-15

VERT: AS SHOWN SCALE: _____ HORIZ: AS SHOWN SCALE: _____ NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: ARCHITECTURAL DETAILS - 1

Murray Smith & Associates, Inc.
Engineers/Planners
12 S.W. Salmon, Suite 900 PORTLAND, OREGON 97204
PHONE: 503-255-9010 FAX: 503-255-9022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED-OR-SCH-C-C1.dwg C-C1 9/3/2015 10:26 AM HCM 20.0s (LMS Tech)




NOTE:
 1. KEY MAP IS PROVIDED AS AN INDEX FOR THE PLAN SHEET LAYOUT ONLY AND DOES NOT IDENTIFY WORK OR MATERIALS REQUIRED FOR CONSTRUCTION.

PLAN
 SCALE: 1"=150'

| | | | |
|---|--|---|--------------------------|
| | NO. DATE | REVISION | BY |
| | DESIGNED: MLM DRAWN: HCM/BAW CHECKED: LLA APPROVED: TPB | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: WATER MAIN REPLACEMENT KEY MAP | | SCALE: VERT. AS SHOWN HORIZ. AS SHOWN NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE. | |
| | MSA PROJECT: 14-1586 PHONE: 503-235-9010 121 S.W. Salmon, Suite 300 Portland, Oregon 97204 FAX: 503-235-9022 | DATE: SEPTEMBER 2015 | SHEET: C-C1 80 of 167 |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\1-1586-OR-SCH-C-P-P.dwg C-C2 9/3/2015 3:44 PM DKT 20.0s (LMS Tech)




PLAN - 'A' & 'B' LINE

SCALE: 1"=20'

NOTES:


- WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
- CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
- ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
- CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.
- REMOVE AND DISPOSE OF EXISTING 18" STEEL WATER MAIN AND REPLACE WITH NEW 24" DUCTILE IRON WATER MAIN IN THE SAME TRENCH FROM APPROXIMATELY STA A2+10 TO STA A5+76. SEE SPECIFICATIONS FOR ABANDONING REMAINING PIPE IN PLACE.
- REPLACE EXISTING SANITARY SEWER WITH NEW DUCTILE IRON SANITARY SEWER MAIN FOR 10 FEET ON EITHER SIDE OF CROSSING WITH NEW WATER MAIN. SEE CITY STANDARD DETAIL WL-409.
- EXISTING 4" CAST IRON WATERLINE SHALL BE ABANDONED IN PLACE TO LIMITS SHOWN. A GROUT CAP SHALL BE INSTALLED A MINIMUM OF 2 FEET ON EACH END OF THE PIPE BEING ABANDONED IN PLACE. SEE SPECIFICATIONS FOR MORE INFORMATION REGARDING ABANDONING EXISTING PIPELINES.



PROFILE - 'A' & 'B' LINE

SCALE: 1"=20' HORIZ, 1"=5' VERT

| | |
|-----------|-----------|
| BY | |
| NO. | DATE |
| REVISION | |
| DESIGNED: | BCF |
| DRAWN: | HCM |
| CHECKED: | LJA |
| APPROVED: | TPB |
| SHEET | C-C2 |
| | 81 of 167 |



SCALE: VERT. 1"=5' HORIZ. 1"=20'

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE: WATER MAIN REPLACEMENT
 ALIGNMENT 'A' & 'B' PLAN AND PROFILE
 STA A1+00 TO STA A4+60


MSA
 Murray, Smith & Associates, Inc.
 Engineers/Planners
 21 S.W. Salmon, Suite 400
 Portland, Oregon 97204
 PHONE: 503-225-9010
 FAX: 503-225-9022

DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586

G:\PDX_Projects\141586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED\C-14-1586-OR-SCH-C-P-P.dwg, C-C3 9/3/2015 3:44 PM, DKT 20.0s (LMS Tech)



PLAN - 'A', 'B' & 'C' LINE
SCALE: 1"=20'





PROFILE - 'A' & 'B' LINE
SCALE: 1"=20' HORIZ, 1"=5' VERT

NOTES:

1. WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
2. CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
3. ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
4. CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.
5. REMOVE AND DISPOSE OF EXISTING 18" STEEL WATER MAIN AND REPLACE WITH NEW 24" DUCTILE IRON WATER MAIN IN THE SAME TRENCH FROM APPROXIMATELY STA A2+10 TO STA A5+76. SEE SPECIFICATIONS FOR ABANDONING REMAINING PIPE IN PLACE.
6. PROFILE SHOWN FOR ALIGNMENTS 'A' AND 'B' ONLY. ALIGNMENTS 'A' AND 'C' TO BE INSTALLED AT THE SAME INVERT ELEVATION STARTING AT STATION A6+60 UNLESS OTHERWISE SHOWN.
7. REPLACE EXISTING SANITARY SEWER WITH NEW DUCTILE IRON SANITARY SEWER MAIN FOR 10 FEET ON EITHER SIDE OF CROSSING WITH NEW WATER MAIN. SEE CITY STANDARD DETAIL WL-409.
8. EXISTING 18" STEEL WATER MAIN SHALL BE ABANDONED IN PLACE. FROM STATION A5+76, PIPE SHALL BE FILLED WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM), AND INSTALL A GROUT CAP FOR A MINIMUM OF 2 FEET ON EACH END. SEE SPECIFICATIONS, EXISTING PIPELINE ABANDONMENT.
9. EXISTING 2" PVC AND 4" CAST IRON WATERLINES SHALL BE ABANDONED IN PLACE TO LIMITS SHOWN. A GROUT CAP SHALL BE INSTALLED A MINIMUM OF 2 FEET ON EACH END OF THE PIPES BEING ABANDONED IN PLACE. SEE SPECIFICATIONS FOR MORE INFORMATION REGARDING ABANDONING EXISTING PIPELINES.


| | |
|----------|-----------|
| BY | |
| NO. | DATE |
| REVISION | |
| DESIGNED | BRF |
| DRAWN | HCW/BAW |
| CHECKED | LLA |
| APPROVED | TPB |
| SHEET | C-C3 |
| | 82 of 167 |




PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE: **WATER MAIN REPLACEMENT
ALIGNMENT 'A', 'B' & 'C' PLAN AND
PROFILE STA A4+60 TO STA A8+40**

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE 503-255-9010
FAX 503-255-9022
DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\14-1586-OR-SCH-C P--P.dwg C-C4 9/3/2015 3:33 PM DKT 20.0s (LMS Tech)



PLAN - 'A' & 'C' LINE
SCALE: 1"=20'



PROFILE - 'A' LINE
SCALE: 1"=20' HORIZ, 1"=5' VERT

NOTES:

1. WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
2. CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
3. ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
4. CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.
5. PROFILE SHOWN FOR ALIGNMENTS 'A' AND 'B' ONLY. ALIGNMENTS 'A' AND 'C' TO BE INSTALLED AT THE SAME INVERT ELEVATION STARTING AT STATION A6+60 UNLESS OTHERWISE SHOWN.
6. EXISTING 18" STEEL WATER MAIN SHALL BE ABANDONED IN PLACE. FROM STATION A5+76, PIPE SHALL BE FILLED WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM), AND INSTALL A GROUT CAP FOR A MINIMUM OF 2 FEET ON EACH END. SEE SPECIFICATIONS, EXISTING PIPELINE ABANDONMENT.
7. EXISTING 2" PVC WATERLINE SHALL BE ABANDONED IN PLACE TO LIMITS SHOWN. A GROUT CAP SHALL BE INSTALLED A MINIMUM OF 2 FEET ON EACH END OF THE PIPE BEING ABANDONED IN PLACE. SEE SPECIFICATIONS FOR MORE INFORMATION REGARDING ABANDONING EXISTING PIPELINES.

| | | | | | |
|----------|-----|----------|-----------|---------|------|
| BY | | REVISION | | NO. | DATE |
| DESIGNED | BRF | DRAWN | HCM/BAW | CHECKED | LLA |
| APPROVED | TPB | | | | |
| | | | SHEET | C-C4 | |
| | | | 83 of 167 | | |

SCALE: VERT: 1"=5' HORIZ: 1"=20'

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06


SHEET TITLE: **WATER MAIN REPLACEMENT
ALIGNMENT 'A' & 'C' PLAN AND PROFILE
STA A8+40 TO STA A12+40**

MSA Murray, Smith & Associates, Inc.
Engineers/Planners
21 S.W. Salmon, Suite 800
Portland, Oregon 97204
PHONE: 503-255-9010 FAX: 503-255-9022

DATE: SEPTEMBER 2015


MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\14-1586-OR-SCH-C P-P.dwg C-C5 9/3/2015 3:33 PM DKT 20.0s (LMS Tech)



PLAN - 'A' & 'C' LINE
SCALE: 1"=20'

- NOTES:**
- WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
 - CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
 - ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
 - CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.
 - PROFILE SHOWN FOR ALIGNMENTS 'A' AND 'B' ONLY. ALIGNMENTS 'A' AND 'C' TO BE INSTALLED AT THE SAME INVERT ELEVATION STARTING AT STATION A6+60 UNLESS OTHERWISE SHOWN.
 - EXISTING 18" STEEL WATER MAIN SHALL BE ABANDONED IN PLACE. FROM STATION A5+76, PIPE SHALL BE FILLED WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM), AND INSTALL A GROUT CAP FOR A MINIMUM OF 2 FEET ON EACH END. SEE SPECIFICATIONS, EXISTING PIPELINE ABANDONMENT.
 - EXISTING 2" PVC WATERLINE SHALL BE ABANDONED IN PLACE TO LIMITS SHOWN. A GROUT CAP SHALL BE INSTALLED A MINIMUM OF 2 FEET ON EACH END OF THE PIPE BEING ABANDONED IN PLACE. SEE SPECIFICATIONS FOR MORE INFORMATION REGARDING ABANDONING EXISTING PIPELINES.



PROFILE - 'A' LINE
SCALE: 1"=20' HORIZ, 1"=5' VERT

| | | | |
|----------|------|----------------|---------------|
| BY | | SHEET | C-5 |
| NO. | DATE | DESIGNED: BRF | CHECKED: LLA |
| REVISION | | DRAWN: HCM/BAW | APPROVED: TPB |
| | | | 84 of 167 |

VERT. 1"=5'
 HORIZ. 1"=20'
 SCALE


NOTICE
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06
 SHEET TITLE: WATER MAIN REPLACEMENT
 ALIGNMENT 'A' & 'C' PLAN AND PROFILE
 STA A12+40 TO STA A16+80


Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE 503-255-9010
 FAX 503-255-9022

DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\14-1586-OR-SCH-C P-P.dwg, C-06 9/3/2015 3:33 PM DKT 20.0s (LMS Tech)



- NOTES:
- WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
 - CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
 - ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.



| | | |
|----------------|--------------|---------------|
| BY | NO. DATE | REVISION |
| DESIGNED: BRF | CHECKED: LLA | APPROVED: TPB |
| DRAWN: HCM/BAW | | |
| SHEET C-06 | | 85 of 167 |

REGISTERED PROFESSIONAL ENGINEER
STATE OF OREGON
NO. 12345
DATE: 12/31/15
RENEW: 12-31-15

SCALE: VERT: 1"=5'
HORIZ: 1"=20'

NOTICE
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06


SHEET TITLE: WATER MAIN REPLACEMENT
ALIGNMENT 'A' PLAN AND PROFILE
STA A16+80 TO STA A21+80

Murray, Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022

DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586

C:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\14-1586-OR-SCH-C-P-P.dwg C-C7 9/3/2015 3:33 PM DKT 20.0s (LMS Tech)

SEE SHEET C-C6
MATCHLINE - STA A21+80




NOTES:

- WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
- CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
- ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
- CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.
- EXISTING 8" DUCTILE IRON WATERLINE SHALL BE ABANDONED IN PLACE TO LIMITS SHOWN. A GROUT CAP SHALL BE INSTALLED A MINIMUM OF 2 FEET ON EACH END OF THE PIPE BEING ABANDONED IN PLACE. SEE SPECIFICATIONS FOR MORE INFORMATION REGARDING ABANDONING EXISTING PIPELINES.

PLAN - 'A' LINE
SCALE: 1"=20'

MATCHLINE - STA A26+60
SEE SHEET C-C8





PROFILE - 'A' LINE
SCALE: 1"=20' HORIZ, 1"=5' VERT

| | | | |
|---|--|---|--|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | SHEET TITLE: WATER MAIN REPLACEMENT ALIGNMENT 'A' PLAN AND PROFILE STA A21+80 TO STA A26+60 | |
| Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9922 | | DATE: SEPTEMBER 2015 | |
| BY: _____ | | DESIGNED: BRP | |
| NO. DATE: _____ | | DRAWN: HCM/BAW | |
| REVISION: _____ | | CHECKED: LLA | |
| _____ | | APPROVED: TPB | |
| _____ | | SHEET C-C7 | |
| _____ | | 86 of 167 | |

SCALE: VERT: 1"=5'
HORIZ: 1"=20'
NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


REGISTERED PROFESSIONAL ENGINEER
N.W. 11111
1988
L.A.E.L. 12-31-15
RENEWS 12-31-15

G:\PDX_Proj\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\14-1586-OR-SCH-C-P-P.dwg C-C8 9/3/2015 3:33 PM DKT 20.0s (LMS Tech)




| | | | | | | | |
|--|-----------|------|-------|--|----------------|--------------|---------------|
| BY: | REVISION: | NO.: | DATE: | DESIGNED: BRF | DRAWN: HCM/JAW | CHECKED: LLA | APPROVED: TPB |
| | | | | | | | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' NOTICE: IF THIS BAR DOES NOT SHOW UP WHEN DRAWING IS NOT TO SCALE | | | | | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: WATER MAIN REPLACEMENT ALIGNMENT 'A' PLAN AND PROFILE STA A26+60 TO STA A30+60 | | | | | | | |
| | | | | DATE: SEPTEMBER 2015 MSA PROJECT: 14-1586 | | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED-C\14-1586-OR-SCH-C-P-P.dwg C-09 9/3/2015 2:42 PM DKT 20.0s (LMS_Tech)




PLAN - 'A' LINE
SCALE: 1"=20'

- NOTES:**
- WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
 - CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
 - ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
 - CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.
 - EXISTING 6" CAST IRON WATERLINE SHALL BE ABANDONED IN PLACE TO LIMITS SHOWN. A GROUT CAP SHALL BE INSTALLED A MINIMUM OF 2 FEET ON EACH END OF THE PIPE BEING ABANDONED IN PLACE. SEE SPECIFICATIONS FOR MORE INFORMATION REGARDING ABANDONING EXISTING PIPELINES.






PROFILE - 'A' LINE
SCALE: 1"=20' HORIZ, 1"=5' VERT



PROFILE - 'H' LINE
SCALE: 1"=20' HORIZ, 1"=5' VERT


| | | | | |
|---|----------------------|--|----------------|-------|
| | NO. | DATE | DESIGNED: BRF | SHEET |
| | REVISION | | DRAWN: HCM/BAW | C-09 |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | SHEET TITLE: WATER MAIN REPLACEMENT ALIGNMENT 'A' AND 'H' PLAN AND PROFILE STA A30+60 TO STA A33+26 AND STA H1+00 TO STA H2+31 | | |
| | DATE: SEPTEMBER 2015 | MSA PROJECT: 14-1586 | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED.C\4-1586-OR-SCH-C P-P.dwg C-C-10.9/3/2015 2:42 PM DKT 20.0s (LWS Tech)




| | | |
|---|--------------------|--|
| BY: | DESIGNED: BRF | SHEET: C-C10 |
| NO. DATE: | DRAWN: HCW/JAW/RLF | 89 of 167 |
| REVISION: | CHECKED: LLA | |
| | APPROVED: TPB | |
| | | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE. | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: WATER MAIN REPLACEMENT ALIGNMENT 'C' AND 'G' PLAN AND PROFILE STA C1+00 TO STA C4+40 AND STA G1+00 TO STA G2+40 | | |
| | | DATE: SEPTEMBER 2015 PHONE: 503-225-9010 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 FAX: 503-225-9022 |
| | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED C\14-1586-OR-SCH-C P-P.dwg, C-C11, 9/3/2015 2:42 PM, DKT 20.0s (LMS Tech)



NOTES:

- WHERE HORIZONTAL AND VERTICAL BENDS ARE NOT SPECIFIED, CONTRACTOR SHALL DEFLECT PIPE TO ACHIEVE HORIZONTAL AND VERTICAL CURVES AS SHOWN. THE MAXIMUM ALLOWABLE PIPE JOINT DEFLECTION SHALL NOT EXCEED 50% OF THE MAXIMUM INSTALLED DEFLECTION RECOMMENDED BY THE PIPE MANUFACTURER.
- CONTRACTOR SHALL POTHOLE AND VERIFY LOCATIONS, SIZES AND DEPTHS OF EXISTING UTILITIES. NOTIFY ENGINEER OF POTENTIAL CONFLICTS 72 HOURS IN ADVANCE OF WATER MAIN INSTALLATION TO ALLOW FOR CHANGES IN ALIGNMENT OR GRADE.
- ALL PIPE AND FITTINGS SHALL BE RESTRAINED JOINT UNLESS OTHERWISE NOTED.
- CONTRACTOR SHALL ADJUST EXISTING WATER SERVICE LATERALS IN CONFLICT WITH WATER MAIN ALIGNMENT TO MAINTAIN TEMPORARY SERVICE UNTIL NEW WATER MAIN AND SERVICE REPLACEMENTS ARE IN SERVICE. ADJUSTMENTS ARE CONSIDERED INCIDENTAL TO WATER MAIN INSTALLATION.



| | |
|-----------|-------------|
| BY | |
| NO. | DATE |
| REVISION | |
| DESIGNED: | BRF |
| DRAWN: | HCM/BAW/RLF |
| CHECKED: | LJA |
| APPROVED: | TPB |
| SHEET | C-C11 |
| | 90 of 167 |



SCALE: 1"=5' VERT, 1"=20' HORIZ

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: WATER MAIN REPLACEMENT
ALIGNMENT 'C' PLAN AND PROFILE
STA 4+40 TO STA C7+40

MSA Murray, Smith & Associates, Inc.
Engineers/Planners
21 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-0010
FAX: 503-225-0022


DATE: SEPTEMBER 2015

MSA PROJECT: 14-1586

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED_C\C-C12_9/3/2015 2:42 PM.DKT 20.0s (LMS Tech)

CONSTRUCTION SEQUENCING:

1. CONSTRUCT ALIGNMENT 'A' THROUGH TEE AT STA A6+73, INSTALLING TEMPORARY 24" PLUG ON EAST RUN OF TEE. PERFORM HYDROSTATIC TESTING, FLUSHING AND DISINFECTION FOR THIS SEGMENT. OBTAIN ACCEPTANCE OF SEGMENT FROM CITY, THEN PERFORM TIE-IN TO EXISTING SYSTEM.
2. CONSTRUCT TEMPORARY TIE-IN BETWEEN ALIGNMENT 'A' AND EXISTING 18" STEEL WATER MAIN AS SHOWN.
3. COMPLETE CONSTRUCTION OF ALIGNMENT 'A'. PERFORM HYDROSTATIC TESTING, FLUSHING AND DISINFECTION FOR THIS SEGMENT. OBTAIN ACCEPTANCE OF SEGMENT FROM CITY, THEN PERFORM TIE-IN TO EXISTING SYSTEM AS SHOWN ON DETAIL 2, THIS SHEET.
4. REMOVE TEMPORARY 24" PLUG IN TEE AT STA A6+73, AND CONNECT ALL 24" PIPING FOR ALIGNMENT 'A'.
5. INSTALL PERMANENT 18" PLUG IN THE BRANCH OF THE TEE AT STA A6+73, AND ABANDON ALL 18" WATER MAIN IN PLACE.




**PIPING CONNECTION DETAIL
INTERSECTION OF SKYLINE DR & SKYLINE DR**
SCALE: 1"=10' (C-C3)

STA A14+64, 21' LT
CONNECT TO EXIST 18" STL W
FURNISH & INSTALL:
1-18" 45° HORIZ BEND, MJ
1-TB, SEE CITY STD DET WL-406
1-18" DI/STL INSUL TRANS
CPLG, SEE DET 5, SHT DET-10
1-18" PLUG, MJ

STA A14+60, 14.3' LT
FURNISH & INSTALL:
1-18" 45° HORIZ BEND, MJ
1-TB, SEE CITY STD DET WL-406


STA A14+60
FURNISH & INSTALL:
1-24"x18" TEE, MJxMJxFLG
1-18" IJ, SEE DET 3, SHT DET-10
1-TS/IJ-1, SEE DET 1, SHT DET-11
1-18" BFV, FLGxMJ
1-TB, SEE CITY STD DET WL-406



**PIPING CONNECTION DETAIL
INTERSECTION OF SKYLINE DR & WEBB ST**
SCALE: 1"=10' (C-C5)

STA A28+16, 48' LT
CONNECT TO EXIST 8" DI W
FURNISH & INSTALL:
2-8" FLGxMJ ADAPTER
1-8" IJ, SEE DET 3, SHT DET-10
1-TS/IJ-1, SEE DET 1, SHT DET-11
1-8" LS, MJ

STA A28+14, 33' LT
FURNISH & INSTALL:
1-8" 45° HORIZ BEND, MJ
1-TB, SEE CITY STD DET WL-406
1-8" CAP, MJ




STA A28+06, 25.5' LT
FURNISH & INSTALL:
1-18"x8" RDCR, MJ
1-8" 45° HORIZ BEND, MJ
1-TB, SEE CITY STD DET WL-406

STA A28+06
FURNISH & INSTALL:
1-24" TEE, FLG
2-24" BFV, FLGxMJ
1-24"x18" RDCR, FLG
1-18" BFV, FLGxMJ

**PIPING CONNECTION DETAIL
INTERSECTION OF SKYLINE DR & A ST**
SCALE: 1"=10' (C-C8)

STA A32+88=STA H1+00
FURNISH & INSTALL:
1-24" TEE, FLG
1-24" BFV, FLGxMJ
1-24" FLGxMJ ADAPTER
1-24"x18" RDCR, FLG
1-18"x8" RDCR, FLG
1-8" GV, FLGxMJ


STA A33+08
FURNISH & INSTALL:
1-24"x18" TEE, MJ
1-24" PLUG, MJ
1-TB, SEE CITY STD DET WL-406



STA H1+24
FURNISH & INSTALL:
1-8" TEE, MJ
1-8" PLUG, MJ

STA A33+26
CONNECT TO EXIST 18" STL
FURNISH & INSTALL:
1-18" WET TAP W/ SADDLE ASSY
1-18" IJ, SEE DET 3, SHT DET-10
1-TS/IJ-1, SEE DET 1, SHT DET-11
1-18" GV, FLGxMJ



**PIPING CONNECTION DETAIL
INTERSECTION OF EASY ST
& BROADWAY ST**
SCALE: 1"=10' (C-C9)



BACKFLOW PREVENTION ASSEMBLY
SCALE: NTS (C-C10)

| | | | | |
|--|--|----------|----------------------|-----------|
| BY | NO. DATE | REVISION | DESIGNED: BRF | SHEET |
| | | | DRAWN: HCM/BAW/RLF | |
| | | | CHECKED: LLA | 91 of 167 |
| | | | APPROVED: TPB | |
| | | | REVISIONS 12-31-15 | |
| | | | | |
| SCALE: VERT. 1"=5' HORIZ. 1"=20' | NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | | |
| SHEET TITLE: PIPING CONNECTION DETAILS | | | | |
| Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9022 | | | DATE: SEPTEMBER 2015 | |
| MSA PROJECT: 14-1586 | | | | |

G:\PDX_Projects\14-1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED D\14-1586-OR-D-GRADING.dwg C-D1 9/24/2015 2:30 PM RER 20.0s (LMS Tech)




| LOCATION | APPROXIMATE DBH RANGE | APPROXIMATE QUANTITY (EA) |
|--|-----------------------|---------------------------|
| RIGHT SIDE OF SKYLINE DRIVE: FIRWOOD DR - CLARK ST | 6"-24" | 9 |
| LEFT SIDE OF SKYLINE DRIVE: FIRWOOD DR - CLARK ST | 8"-12" | 0 |
| RIGHT SIDE OF SKYLINE DRIVE: CLARK ST - A ST | 8"-54" | 53 |

| CURB | DESCRIPTION | CURB STATION | ELEV Δ | CURVE DATA |
|------|--------------------------------|--------------|---------------|--|
| C1 | BCR: N627570.41 E7655498.78 | LA1+29.8 | 461.87 | R = 15' $\Delta = 63^\circ 48' 52''$ L = 16.71' |
| | 1/4 Δ | LA1+33.9 | 461.96 | |
| | 3/4 Δ | LA1+42.3 | 461.79 | |
| C2 | ECR: N627561.65 E7655485.56 | LA1+46.4 | 461.76 | R = 15' $\Delta = 104^\circ 35' 22''$ L = 27.38' |
| | 1/4 Δ | LB1+36.9 | 460.95 | |
| | 3/4 Δ | LB1+50.6 | 461.18 | |
| | BCR: N627549.12 E7655549.86 | LB1+30.0 | 460.74 | R = 15' $\Delta = 104^\circ 35' 22''$ L = 27.38' |
| | 1/4 Δ | LB1+36.9 | 460.95 | |
| | 3/4 Δ | LB1+50.6 | 461.18 | |
| | ECR: N627570.14 E7655538.82 | LB1+57.4 | 461.04 | R = 15' $\Delta = 104^\circ 35' 22''$ L = 27.38' |
| | 1/4 Δ | LB1+36.9 | 460.95 | |
| | 3/4 Δ | LB1+50.6 | 461.18 | |

NOTE: ELEVATIONS FOR CURB RETURNS ARE FOR THE GUTTER LINE.




| | | | | |
|--|--|-----------|---------------|-----------|
| NO. DATE 9/24 ADD 2: REVD CURB RETURN DATA ELEV'S | REVISION 9/24 ADD 2: REVD CURB RETURN DATA ELEV'S | BY AHG | SHEET C-D1 | 92 of 167 |
| | | | | |
| DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TFB | | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | | |
| ALIGNMENT AND GRADING PLAN - 1 | | | | |
| SHEET TITLE: | | | | |
| DATE: SEPTEMBER 2015 | | | | |
| | | | | |
| 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022 | | | | |



PLAN
SCALE: 1" = 20'

| | | | | | |
|---|--|---|---|--|-------------------------------------|
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 21 S.W. Salama, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-0822</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>NO. DATE REVISION</p> | <p>DESIGNED: AHC/ RER DRAWN: HCM CHECKED: GFC APPROVED: TPB</p> | <p>BY: _____ DATE: _____ REVISION: _____</p> | <p>SHEET C-D2 93 of 167</p> |
| <p>ALIGNMENT AND GRADING PLAN - 2</p> | | <p>REGISTERED PROFESSIONAL ENGINEER OREGON ANTHONY HENRY RENEWS 6-30-17</p> | | <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED D\14-1586-OR-D-GRADING.dwg C-D3 9/24/2015 2:30 PM RER 20.0s (LMS Tech)



| CURB RETURN DATA | | | | |
|------------------|--------------------------------|--------------|--------|--|
| CURB | DESCRIPTION | CURB STATION | ELEV Δ | CURVE DATA |
| C3 | BCR: N627133.37 E7656345.60 | RA9+77.3 | 447.10 | R = 15' Δ = 61°34'57" L = 16.12' |
| | 1/4 Δ | RA9+81.3 | 446.94 | |
| | RAMP @ 1/2 Δ | RA9+85.4 | 446.79 | |
| | 3/4 Δ | RA9+89.5 | 446.70 | |
| C4 | ECR: N627122.43 E7656356.38 | RA9+93.4 | 446.64 | R = 15' Δ = 95°59'15" L = 30.16' |
| | BCR: N627133.80 E7656407.00 | RB0+12.2 | 445.54 | |
| | 1/4 Δ | RB0+19.7 | 445.43 | |
| | RAMP @ 1/2 Δ | RB0+27.2 | 445.31 | |
| | 3/4 Δ | RB0+34.8 | 445.16 | |
| | ECR: N627111.68 E7656391.96 | RB0+42.3 | 444.98 | |

NOTE: ELEVATIONS FOR CURB RETURNS ARE FOR THE GUTTER LINE.

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
ALIGNMENT AND GRADING PLAN - 3

NO. DATE REVISION

1 9/24 ADD 2: REV'D CURB RETURN DATA ELEV'S

BY: AHG

DESIGNED: AHG/RER

DRAWN: HCM

CHECKED: GEC

APPROVED: TPB

SCALE: VERT: 1"=5'
HORIZ: 1"=20'

NOTICE
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

REGISTERED PROFESSIONAL ENGINEER
STATE OF OREGON
NO. 2107
ANDREW NEVILL

RENEWS 6-30-17


MSA PROJECT: 14-1586

DATE: SEPTEMBER 2015


Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE 503-225-4010
FAX 503-225-4022

SHEET C-D3
94 of 167

c:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-CRADING.dwg C-D4 9/3/2015 4:43 PM PER 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'




PLAN
SCALE: 1" = 20'

| 'S' STATION | 1/4 PTS | ℄ ELEV | LT EOP ELEV | RT GUT ELEV |
|-------------|---------|--------|-------------|-------------|
| 'S'22+84.18 | PC | 429.36 | 429.91 | 428.74 |
| 'S'23+09.71 | 1/4 | 426.76 | 427.25 | 426.34 |
| 'S'23+35.25 | 1/2 | 424.08 | 424.56 | 423.76 |
| 'S'23+60.78 | 3/4 | 421.43 | 421.62 | 421.13 |
| 'S'23+86.31 | PT | 418.80 | 418.44 | 418.70 |

| | | | | |
|---|---|---|------------------------------|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: ALIGNMENT AND GRADING PLAN - 4</p> | <p>DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>NO. DATE REVISION</p> | <p>BY: _____ SHEET: C-D4 95 of 167</p> |
| | | <p>SCALE: VERT: 1" = 5' HORIZ: 1" = 20'</p> <p>NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | |
| <p>MURRAY SMITH & ASSOCIATES, INC. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022</p> | | <p>DATE: SEPTEMBER 2015</p> | | |


g:\pdx_projects\4\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-GRADING.dwg C-D5 9/3/2015 4:43 PM RER 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

| | | | |
|--|---|----------------------------------|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: ALIGNMENT AND GRADING PLAN - 5</p> | <p>NO. DATE</p> <p>REVISION</p> | <p>DESIGNED: AHC/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> |
| <p>SCALE: VERT: 1" = 5' HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | |
| | | <p>DATE: SEPTEMBER 2015</p> | |
| <p>MSA PROJECT: 14-1586</p> | | <p>SHEET: C-D5 96 of 167</p> | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\replacement\CAD\Sheets\SCHEM.D\14-1586-OR-D-CRADING.dwg C-D6 9/3/2015 4:43 PM RER 20.0s (LMS Tech)



| | | |
|-----------|---------|-----------|
| NO. | DATE | REVISION |
| | | |
| | | |
| | | |
| DESIGNED: | AHG/RER | SHEET |
| DRAWN: | FCM | C-D6 |
| CHECKED: | GEC | 97 of 167 |
| APPROVED: | TPB | |



SCALE: VERT: 1"=5'
HORIZ: 1"=20'

NOTICE
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE.


PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
ALIGNMENT AND GRADING PLAN - 6


MSA
Murray, Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 800
Portland, Oregon 97204
PHONE: 503-225-4010
FAX: 503-225-4022

DATE: SEPTEMBER 2015

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-GRAD.ING.dwg C-D7 9/3/2015 4:43 PM RER 20.0s (LMS Tech)



| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |
| | | |



SCALE: VERT: 1"=5'
HORIZ: 1"=20'

NOTICE
IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06


SHEET TITLE:
ALIGNMENT AND GRADING PLAN - 7

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9000
FAX: 503-225-9022

DATE: SEPTEMBER 2015


MSA PROJECT: 14-1586

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-CRADING.dwg C-D8 9/3/2015 4:43 PM RER 20.0s (LMS Tech)




| | | | | | |
|---|--|--|--|-----------------|-----------------------|
| <p>MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>NO. DATE</p> | <p>REVISION</p> | <p>BY</p> | <p>SHEET C-D8</p> |
| | <p>SHEET TITLE: ALIGNMENT AND GRADING PLAN - 8</p> | <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | <p>DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>REVISION</p> | <p>BY</p> |
| <p>DATE: SEPTEMBER 2015</p> | | <p>MSA PROJECT: 14-1586</p> | | | |

g:\pdx_projects\4\1586 -- bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-CRADING.dwg C-D9 9/3/2015 4:43 PM RER 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'



A ST DETAIL
SCALE: 1" = 10'

| | | | | | | | | | | |
|--|---|-----------------------------|-------------------------|--|------------------|-----------------|--|--------------------------------------|--|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: ALIGNMENT AND GRADING PLAN - 9</p> | <p>DATE: SEPTEMBER 2015</p> | <p>PROJECT: 14-1586</p> | <p>BY: _____</p> | <p>REVISION:</p> | <p>NO. DATE</p> | <p>DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>SHEET C-D9 100 of 167</p> | | |
| | | | | <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | | |
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-8000 FAX: 503-225-8022</p> | | | | | | | | | | |

g:\pdx_projects\4\1586 - bolton_reservoir_replacement\CAD\Sheets\replacement\CAD\14-1586-OR-D-IMP-PLAN.dwg C-D10 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'

KEY NOTES:

- 1 MATCH EXIST S/W AND STD CURB AT EXIST JT
- 2 CONST CONC STD CURB, SEE NOTE 1 (SEE ODOT DWG RD700)
- 3 CONST CONC S/W (SEE ODOT DWG RD720)
- 4 CONST PERPENDICULAR S/W CURB RAMP - OPTION D (SEE ODOT DWG RD756)
- 5 MAINTAIN AND PROTECT EXIST STD CURB, TYP
- 6 MAINTAIN AND PROTECT EXIST S/W, TYP
- 8 MAINTAIN AND PROTECT EXIST MAILBOX
- 9 AC PAVING LIMIT (SEE DETS 4 & 5, SHT C-D40)
- 11 REMOVE EXIST S/W
- 12 REMOVE EXIST STD CURB
- 13 INSTALL BARK MULCH - 3" THK BTWN EXIST S/W AND BACK OF PROPOSED CURB (SEE LANDSCAPE PLANS)
- 14 CONST NEW AC DWY APPROACH W/ LEVEL 2, 3/8" ACP MIX (PG 64-22) - 4" THK AGGREGATE BASE - 6" THK (SEE ODOT DWG NO RD715)
- 15 REMOVE DWY APPROACH
- 19 CURB FRAME & DOOR (SEE STORMWATER & UTILITIES SHEETS)
- 25 CONST PARALLEL S/W CURB RAMP - OPTION K (SEE ODOT DWG RD757)
- 30 REMOVE EXIST AC SURFACING
- 31 REMOVE EXIST MB (BY COWL)
- 33 CONST 7.1' WIDE S/W, MAINTAIN MIN 4.0' CLEAR WIDTH AROUND EXIST POLE
- 34 CONST 7.3' WIDE S/W, MAINTAIN MIN 4.0' CLEAR WIDTH AROUND EXIST POLE


SHEET NOTES:

1. CURBS: SEE ODOT STANDARD DRAWING RD700, E=6".
2. REMOVE ALL EXISTING SIGNS AND SIGN POSTS FROM PROJECT IN CONFLICT WITH PROPOSED CONSTRUCTION AND INSTALL EXISTING SIGNS ON TEMPORARY SIGN SUPPORTS AS NECESSARY DURING CONSTRUCTION. MAINTAIN AND PROTECT ALL OTHER SIGNS AS REQUIRED PER SIGNING AND STRIPING PLAN. CITY OF WEST LINN WILL INSTALL ALL GROUND MOUNTED SIGNS. RETURN EXISTING SIGNS TO CITY OF WEST LINN (JEFF RANDAL, 503-880-9194).
3. PAVING LIMITS TO MATCH EXISTING EDGE OF PAVEMENT UNLESS OTHERWISE SHOWN OR DIRECTED.

- 0"-2" TAPER GRIND SHOWN THUS:
- 2" GRIND SHOWN THUS:
- 6" GRIND SHOWN THUS:
- REMOVE EXIST SURFACING SHOWN THUS:
- TO BE ACCOMPANIED BY ODOT STD DWGS:
RD100, RD101, RD140, RD150, RD160,
RD610, RD700, RD715, RD720, RD755,
RD756, RD757, RD759, RD815

| | | | |
|--|------------------------------|--|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: STREET IMPROVEMENTS PLAN - 1</p> | <p>NO. DATE REVISION</p> | <p>DESIGNED: AHG/REB DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>BY: SHEET: C-D10 101 of 167</p> |
| <p>SCALE: VERT: AS SHOWN HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | |
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-0822</p> | | | |
| <p>DATE: SEPTEMBER 2015</p> | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PLAN.dwg C-D11 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ② CONST CONC STD CURB
- ③ CONST CONC S/W
- ⑦ CONST AC DWY APPROACH
(SEE DET 3, SHT C-D39)
- ⑧ MAINTAIN AND PROTECT EXIST MAILBOX
- ②③ REMOVE EXIST MB
PROVIDE TEMP MB DURING CONST
INSTALL NEW SINGLE MB SUPPORT
(SEE ODOT DWG RD100 & RD101)

| <p>MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9110 FAX: 503-225-9022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: STREET IMPROVEMENTS PLAN - 2</p> | <p>SCALE: VERT: AS SHOWN HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | <p>PROFESSIONAL SEAL ANDREW HENRY REGISTERED PROFESSIONAL ENGINEER NO. 22517 RENEW'S 6-30-17</p> | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NO.</th> <th>DATE</th> <th>REVISION</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table> <p>DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | NO. | DATE | REVISION | | | | | | | | | | <p>BY: _____</p> <p>SHEET: C-D11</p> <p>102 of 167</p> |
|---|--|---|--|--|-----|------|----------|--|--|--|--|--|--|--|--|--|--|
| NO. | DATE | REVISION | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |

g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED D\14-1586-OR-D-IMP-PLAN.dwg C-D12 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:


- ② CONST CONC STD CURB
- ③ CONST CONC S/W
- ⑨ AC PAVING LIMIT, (SEE DETS 4 & 5, SHT C-D40)
- ⑭ CONST NEW AC DWY APPROACH, W/ LEVEL 2, 3/8" ACP MIX (PG 64-22) - 4" THK AGGREGATE BASE - 6" THK (SEE ODOT DWG NO RD715)
- ⑮ REMOVE DWY APPROACH
- ⑯ CONST 4' WIDE MAINTENANCE PAD (FILL STATION) (SEE DET 2, SHT C-D39)
- ⑰ CONST LOW PROFILE MOUNTABLE CURB (SEE ODOT DWG RD700)
- ⑳ CONST PARALLEL S/W CURB RAMP - OPTION K
- ㉓ CONST ACP S/W RAMP - OPTION F AT S/W END (SEE ODOT DWG RD756)

| | | | | |
|--|--|---|--|--|
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-0010 FAX: 503-225-0022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: STREET IMPROVEMENTS PLAN - 3</p> | <p>NO. DATE REVISION</p> | <p>DESIGNED: AHC/REB DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>BY: _____ SHEET: C-D12 103 of 167</p> |
| <p>VERT: AS SHOWN HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | <p>REGISTERED PROFESSIONAL ENGINEER STATE OF OREGON NO. 112,323 AMERICAN INSTITUTE OF PROFESSIONAL ENGINEERS RENEWALS 8-30-17</p> | | |
| <p>DATE: SEPTEMBER 2015</p> | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-IMP-PLAN.dwg C-D13 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'




PLAN
SCALE: 1" = 20'

- KEY NOTES:**
- ② CONST CONC STD CURB
 - ③ CONST CONC S/W
 - ⑤ MAINTAIN AND PROTECT EXIST STD CURB, TYP
 - ⑦ CONST AC DWY APPROACH (SEE DET 3, SHT C-D39)
 - ⑧ MAINTAIN AND PROTECT EXIST MAILBOX
 - ⑨ AC PAVING LIMIT (SEE DETS 4 & 5, SHT C-D40)
 - ⑩ MAINTAIN AND PROTECT EXIST GUARDRAIL
 - ⑱ RECONSTRUCT ROADWAY HORIZONTAL CURVE. REGRADE ROADWAY CROSS SLOPE TO NEW SUPERELEVATION. (SEE TYPICAL SECTIONS AND CROSS SECTIONS)
 - ⑲ CURB FRAME & DOOR (SEE STORMWATER & UTILITIES SHEETS)
 - ⑳ CONST S/W LANDING (SEE DET 1, SHT C-D39)
 - ㉑ CONST AC BERM (SEE DET 4, SHT C-D39)

| | | | | | | | |
|--|---|---|------------------|--|-----------------|--|---------------------------------------|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: STREET IMPROVEMENTS PLAN - 4</p> | <p>DATE: SEPTEMBER 2015</p> | <p>BY: _____</p> | <p>NO. DATE</p> | <p>REVISION</p> | <p>DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>SHEET C-D13 104 of 167</p> |
| | | <p>VERT: AS SHOWN HORIZ: 1" = 20'</p> | | <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | |
| | | | | | | | |

g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PLAN.dwg C-D14 9/3/2015 1:04 PM DKT. 20.0s (LWS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ② CONST CONC STD CURB
- ③ CONST CONC S/W
- ⑦ CONST AC DWY APPROACH
(SEE DET 3, SHT C-D39)
- ⑩ MAINTAIN AND PROTECT EXIST GUARDRAIL
- ⑳ INSTALL PREFABRICATED MODULAR GRAVITY RETAINING WALL
W/ QUARRIED STONE FACE
(SEE SHT C-D38)
- ⑳ CONST S/W LANDING
(SEE DET 1, SHT C-D39)
- ㉑ CONST CL-4 CHAINLINK FENCE W/ BLACK VINYL CLAD FABRIC,
CAST FENCE POST FOOTINGS INTO WALL PER MANUFACTURER'S
RECOMMENDATIONS
- ㉒ CONST AC BERM
(SEE DET 4, SHT C-D39)

| | | | | | | |
|--|--|---|--|--|--|-----------------------------------|
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: STREET IMPROVEMENTS PLAN - 5</p> | <p>NO. DATE REVISION</p> <p>DESIGNED: AHC/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>BY: _____</p> <p>DATE: _____</p> <p>REVISION: _____</p> <p>DATE: _____</p> <p>REVISION: _____</p> | <p>VERT: AS SHOWN HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | <p>REGISTERED PROFESSIONAL ENGINEER STATE OF OREGON NO. 76447 AS 10/16/11 AMERICAN INSTITUTE OF PROFESSIONAL ENGINEERS RENEWED 8-30-17</p> | <p>SHEET C-D14 105 of 167</p> |
| <p>DATE: SEPTEMBER 2015</p> | | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PLAN.dwg C-D15 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ② CONST CONC STD CURB
- ③ CONST CONC S/W
- ⑦ CONST AC DWY APPROACH
(SEE DET 3, SHT C-D39)
- ⑧ MAINTAIN AND PROTECT EXIST MAILBOX
- ⑨ CURB FRAME & DOOR
(SEE STORMWATER & UTILITIES SHEETS)
- ⑩ INSTALL PREFABRICATED MODULAR GRAVITY RETAINING WALL W/
QUARRIED STONE FACE
(SEE SHT C-D38)
- ⑬ REMOVE EXIST MB
PROVIDE TEMP MB DURING CONST
INSTALL NEW SINGLE MB SUPPORT
- ⑮ CONST S/W LANDING
(SEE DET 1, SHT C-D39)
- ⑰ CONST CL-4 CHAINLINK FENCE WITH BLACK VINYL CLAD FABRIC,
CAST FENCE POST FOOTINGS INTO WALL PER MANUFACTURER'S
RECOMMENDATIONS
- ⑱ CONST AC BERM
(SEE DET 4, SHT C-D39)

| | <p>REGISTERED PROFESSIONAL ENGINEER ANDREW HENRY NO. 7644 EXPIRES 12/31/17</p> | <p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NO.</th> <th>DATE</th> <th>REVISION</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table> | NO. | DATE | REVISION | | | | <p>DESIGNED: AHG/REB DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>BY: _____ DATE: _____</p> |
|--|--|--|-----|--|----------|--|--|--|--|----------------------------------|
| NO. | DATE | REVISION | | | | | | | | |
| | | | | | | | | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | | <p>SHEET TITLE: STREET IMPROVEMENTS PLAN - 6</p> | | <p>SHEET C-D15 106 of 167</p> | | | | | | |
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022</p> | | <p>DATE: SEPTEMBER 2015</p> | | <p>MSA PROJECT: 14-1586</p> | | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-IMP-PLAN.dwg C-D16 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

- KEY NOTES:**
- ① MATCH EXIST S/W AND STD CURB AT EXIST JT
 - ② CONST CONC STD CURB
 - ③ CONST CONC S/W
 - ⑤ MAINTAIN AND PROTECT EXIST STD CURB, TYP
 - ⑥ MAINTAIN AND PROTECT EXIST S/W, TYP
 - ⑦ CONST AC DWY APPROACH (SEE DET 3, SHT C-D39)
 - ⑧ MAINTAIN AND PROTECT EXIST MAILBOX
 - ⑳ CONST AC BERM (SEE DET 4, SHT C-D39)

| | | | | | |
|---|-----|----------------------|--|----------------------|-------|
| | NO. | DATE | REVISION | BY | SHEET |
| | | | | | C-D16 |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | | | |
| SHEET TITLE: STREET IMPROVEMENTS PLAN - 7 | | | | | |
| SCALE: VERT. AS SHOWN HORIZ. 1" = 20' NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | | DESIGNED: AHG/REB DRAWN: HCM CHECKED: GEC APPROVED: TPB | | |
| | | DATE: SEPTEMBER 2015 | | MSA PROJECT: 14-1586 | |

g:\pdx_projects\4\586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-IMP-PLAN.dwg C-D17 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ② CONST CONC STD CURB
- ⑤ MAINTAIN AND PROTECT EXIST STD CURB, TYP
- ⑥ MAINTAIN AND PROTECT EXIST S/W, TYP
- ⑨ AC PAVING LIMIT
(SEE DETS 4 & 5, SHT C-D40)
- ⑳ REMOVE EXIST CURB AND GUTTER
- ㉑ MATCH EXIST CURB AND GUTTER
- ㉒ CONST AC BERM
(SEE DET 4, SHT C-D39)

| | | | | |
|--|--|--|-----------------|-----------|
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9000 FAX 503-225-0022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>NO. DATE</p> <p>DESIGNED: AHG/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>REVISION</p> | <p>BY</p> |
| <p>VERT: AS SHOWN HORIZ: 1" = 20'</p> | | <p>NOTICE IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE</p> | | |
| <p>STREET IMPROVEMENTS PLAN - 8</p> | | <p>DATE: SEPTEMBER 2015</p> | | |
| <p>SHEET TITLE:</p> | | <p>MSA PROJECT: 14-1586</p> | | |
| <p>PROJECT NO. PW 14-06</p> | | <p>SHEET C-D17</p> | | |
| <p>CITY OF WEST LINN, OREGON</p> | | <p>108 of 167</p> | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PLAN.dwg C-D18 9/3/2015 1:04 PM DKT 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ① MATCH EXIST S/W AND STD CURB AT EXIST JT
- ② CONST CONC STD CURB
- ③ CONST CONC S/W
- ⑤ MAINTAIN AND PROTECT EXIST STD CURB, TYP
- ⑥ MAINTAIN AND PROTECT EXIST S/W, TYP
- ⑪ REMOVE EXIST CURB AND GUTTER
- ⑫ MATCH EXIST CURB AND GUTTER
- ⑮ CONST PARALLEL S/W CURB RAMP - OPTION K
- ⑲ CONST CONC CURB & GUTTER (SEE ODOT DWG RD700)

| | | | | | |
|--|--|-----------------------------|--|--------------------------|--|
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>DATE: SEPTEMBER 2015</p> | <p>VERT: AS SHOWN SCALE: HORIZ: 1" = 20'</p> | <p>NO. DATE REVISION</p> | <p>BY: _____ DESIGNED: AIG/RER DRAWN: HCM CHECKED: GEC APPROVED: TTB</p> |
| <p>STREET IMPROVEMENTS PLAN - 9</p> | | | <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | |
| <p>REGISTERED PROFESSIONAL ENGINEER STATE OF OREGON ANDREW HEWITT RENEWED 8-30-17</p> | | | <p>SHEET C-D18 108 of 167</p> | | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PROFILE.dwg C-D19 9/3/2015 1:13 PM HCM 20.0s (LMS Tech)



NOTES:
EXISTING CROSS SLOPE OF THE ROADWAY TO BE EXTENDED FROM THE PROPOSED SAWCUT LINE TO THE PROPOSED GUTTER OR EDGE OF PAVEMENT PROFILE GRADE.


'LA' GUTTER LINE PROFILE
LEFT SIDE OF SKYLINE DRIVE, WEST OF FIRWOOD DR

SCALE: 1"=20' HORIZ; 1"=5' VERT



'LB' GUTTER LINE PROFILE
LEFT SIDE OF SKYLINE DRIVE, EAST OF FIRWOOD DR

SCALE: 1"=20' HORIZ; 1"=5' VERT








'LC' EOP LINE PROFILE
LEFT SIDE OF SKYLINE DRIVE, WEST OF CLARK STREET

SCALE: 1"=20' HORIZ; 1"=5' VERT

| | | | |
|---|-----|--|-------------------------------------|
| NO. DATE REVISION | BY: | DESIGNED: AHG/REB DRAWN: HCM CHECKED: GEC APPROVED: TPB | SHEET C-D19 110 of 167 |
| | | | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: STREET IMPROVEMENTS PROFILES - 1 | | | |
| | | DATE: SEPTEMBER 2015 | |
| Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-0010 FAX: 503-225-0022 | | MSA PROJECT: 14-1586 | |

g:\pdx_projects\4\1586 - bolton reservoir replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PROF\ILE.dwg C-D20 9/3/2015 1:13 PM HCM 20.0s (LMS Tech)




NOTES:
EXISTING CROSS SLOPE OF THE ROADWAY TO BE EXTENDED FROM THE PROPOSED SAWCUT LINE TO THE PROPOSED GUTTER OR EDGE OF PAVEMENT PROFILE GRADE.


'LC' EOP LINE PROFILE
LEFT SIDE OF SKYLINE DRIVE, EAST OF CLARK STREET
SCALE: 1"=20' HORIZ; 1"=5' VERT

| | | |
|--|--|-------------------------------------|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: STREET IMPROVEMENTS PROFILES - 2 | DESIGNED: AHC/RER DRAWN: HCM CHECKED: GEC APPROVED: TPB | SHEET C-D20 111 of 167 |
| | | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | |
| | | |
| MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022 | | |
| DATE: SEPTEMBER 2015 PROJECT: 14-1586 | | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-IMP-PROF\ILE.dwg C-D21 9/3/2015 1:13 PM HCM 20.0s (LMS Tech)



'RA' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, WEST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT



'RA' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, WEST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT




'RA' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, WEST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT


NOTES:
 EXISTING CROSS SLOPE OF THE ROADWAY TO BE EXTENDED FROM THE PROPOSED SAWCUT LINE TO THE PROPOSED GUTTER OR EDGE OF PAVEMENT PROFILE GRADE.

| | | | | | |
|--|---|----------------------------|----------------------------|-------------------------|------------------|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: STREET IMPROVEMENTS PROFILES - 3 | SHEET NO.: C-D21 | SHEET TOTAL: 112 of 167 | DATE: SEPTEMBER 2015 | PROJECT: 14-1586 |
| | | | | | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | | | | |
| REVISIONS: NO. DATE BY | | | | | |
| DESIGNED: AHG/PER DRAWN: BAW CHECKED: GEC APPROVED: TPB | | | | | |

g:\pdx_projects\4\1586 - bolton reservoir replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-IMP-PROF\LE.dwg C-D22 9/3/2015 1:13 PM HCM 20.0s (LMS Tech)



'RB' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, EAST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT



'RB' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, EAST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT


NOTES:
 EXISTING CROSS SLOPE OF THE ROADWAY TO BE
 EXTENDED FROM THE PROPOSED SAWCUT LINE TO THE
 PROPOSED GUTTER OR EDGE OF PAVEMENT PROFILE GRADE.

| | | | |
|---------------|---|--|--|
| PROJECT NAME: | CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | |
| SHEET TITLE: | STREET IMPROVEMENTS PROFILES - 4 | | |
| DATE: | SEPTEMBER 2015 | | |
| PROJECT: | 14-1586 | | |
| DESIGNED: | AHC/RER | | |
| DRAWN: | BAW | | |
| CHECKED: | GEC | | |
| APPROVED: | TPB | | |
| NO. DATE | | | |
| REVISION | | | |
| BY | | | |
| SHEET | C-D22 | | |
| 11.3 of 167 | | | |


SCALE: 1"=5' VERT; 1"=20' HORIZ

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14--1586-OR-D--IMP-PROF\LE.dwg C-D23 9/3/2015 1:13 PM HCM 20.0s (LMS Tech)



'RB' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, EAST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT




'RB' GUTTER LINE PROFILE
RIGHT SIDE OF SKYLINE DRIVE, EAST OF CLARK STREET
 SCALE: 1"=20' HORIZ; 1"=5' VERT

NOTES:
 EXISTING CROSS SLOPE OF THE ROADWAY TO BE
 EXTENDED FROM THE PROPOSED SAWCUT LINE TO THE
 PROPOSED GUTTER OR EDGE OF PAVEMENT PROFILE GRADE.

| | | | | | |
|--|---|---|----------------------|----------------------|---|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: STREET IMPROVEMENTS PROFILES - 5 | MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9022 | DATE: SEPTEMBER 2015 | MSA PROJECT: 14-1586 | NO. DATE REVISION DESIGNED: AHG/RER DRAWN: BAW CHECKED: GEC APPROVED: TPB |
| REVISIONS: 12-31-16 | | | | | |
| SHEET: C-D23 114 of 167 | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-UT\LS.dwg C-D24 9/3/2015 3:49 PM ZIS 20.0s (LMS Tech)




MATCHLINE - STA S15+20
SEE SHEET C-D25

KEY NOTES:

- ① REMOVE EXIST INLET
- ② ADD OR REPLACE MANHOLE ADJUSTMENT RING (SEE ODOT DWG RD356)
- ③ ADJUST EXIST W VALVE BOX
- ⑤ MAINTAIN & PROTECT EXIST UTILITY POLE, COORD W/ PGE AS REQ'D PROVIDE MIN 4' S/W WIDTH BETW POLE & BW
- ⑥ RELOCATE W FIRE HYDRANT (SEE SCHEDULE A FOR DETS)
- ⑦ RELOCATE EXIST T PEDESTAL (BY OTHERS), COORD W/ CTL AS REQ'D
- ⑧ ADJUST EXIST T MH (BY OTHERS), COORD W/ CTL AS REQ'D FURNISH CURB FRAME DOOR (BY OTHERS) INSTALL CURB FRAME & DOOR (SEE DET 1, SHT C-41)
- ⑨ RELOCATE EXIST UTILITY POLE (BY OTHERS), COORD W/ PGE AS REQ'D
- ⑩ RELOCATE OR ABAN EXIST W SVC (BY COWL PW)
- ⑪ STA 'S'9+74.9, 3.6' LT
INSTALL 1-48" SDMH (SDMH-1) OVER EXIST SD
INSTALL 12" SD PIPE - 106'
RIM=463.83
IE(IN)12"(E)=455.05
IE(IN)24"(S)=454.95 (EXIST)
IE(OUT)24"(N)=454.95 (EXIST)
(SEE PROFILE SHEET CD-21)
(SEE ODOT DWG RD335, RD336, RD344, RD345, RD356)
- ⑫ STA 'S'10+21.6, 24.6' LT = STA 'LA'1+20.5
INSTALL 1-G-2 INLET, (SDCB-1) W/ 12" SUMP
EXTEND EXIST 18" CMP SD PIPE W/ LIKE SIZE AND MATL
CONNECT TO EXIST 18" CMP SD PIPE
(SEE PROFILE SHEET CD-D21)
(SEE ODOT DWG RD325, RD326, RD364, RD365, RD339)
- ⑬ STA 'S'10+80.98, 16.9' RT = STA 'RA' 0+77.8
INSTALL 1-G-2 INLET, (SDCB-2) W/ 12" SUMP
INSTALL 12" SD PIPE - 10'
(SEE PROFILE SHEET CD-D21)
- ⑭ STA 'S'10+91.58, 16.7' RT = STA 'RA' 0+87.8
INSTALL 1-G-2 INLET, (SDCB-3)
INSTALL 10" SD PIPE - 116'
(SEE PROFILE SHEET CD-D21)
- ⑮ STA 'S'12+09.97, 15' LT = STA 'LB'2+80.2
INSTALL 1-G-2 INLET, CAST-IN-PLACE (SDCB-4) W/ 12" SUMP
(SEE PROFILE SHEET CD-D21)

| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: STORMWATER AND UTILITIES PLAN - 1</p> | <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | <p>REVISION:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table> | NO. | DATE | BY | | | | <p>DESIGNED: ATC/RE/R DRAWN: BAW CHECKED: GEC APPROVED: TPB</p> <p>SHEET: C-D24 115 of 167</p> |
|--|---|---|-----|------|----|--|--|--|--|
| NO. | DATE | BY | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204</p> <p>PHONE: 503-225-9010 FAX: 503-225-9022</p> | | | | | | | | | |
| <p>MSA</p> | | | | | | | | | |
| <p>TO BE ACCOMPANIED BY ODOT STD DWGS: RD300, RD302, RD306, RD312, RD317, RD318, RD325, RD326, RD335, RD336, RD380, RD339, RD344, RD345, RD356, RD364, RD365, RD370, RD371, RD373, RD386</p> | | | | | | | | | |
| <p>DATE: SEPTEMBER 2015</p> | | | | | | | | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\replacement\CAD\14-1586-OR-D-UT-ILS.dwg C-D25 9/3/2015 3:49 PM Z.I.S 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ③ ADJUST EXIST W VALVE BOX
- ② ADD OR REPLACE MANHOLE ADJUSTMENT RING
- ⑦ RELOCATE EXIST T PEDESTAL (BY OTHERS), COORD W/ CTL AS REQ'D
- ⑧ ADJUST EXIST T MH (BY OTHERS), COORD W/ CTL AS REQ'D
FURNISH CURB FRAME DOOR (BY OTHERS)
INSTALL CURB FRAME & DOOR
(SEE DET 1, SHT C-41)
- ⑨ RELOCATE EXIST UTILITY POLE (BY OTHERS), COORD W/ CTL AS REQ'D
- ⑪ NEW 8" W
ABAN EXIST 6" W
(SEE SCHEDULE C FOR DETS)
- ⑫ STA 'S'16+28.65, 15' RT = STA 'RA'6+20.3
INSTALL 1-G-2 INLET CAST-IN-PLACE (SDCB-5) W/ 12" SUMP
INSTALL 10" SD PIPE - 24'
CONST SLOPED END
CONST CULVERT EMBANKMENT PROTECTION
CONST RIPRAP BASIN
(SEE DET 6, SHT C-D40)
(SEE PROFILE SHEET C-D21)
(SEE ODOT DWG RD317 & RD318)

| | | | |
|---|--|----------------------|----------------------|
| MSA | Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-0010 FAX: 503-225-0022 | DATE: SEPTEMBER 2015 | MSA PROJECT: 14-1586 |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | |
| STORMWATER AND UTILITIES PLAN - 2 | | | |
| SHEET TITLE: | | | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | | |
| | | | |
| NO. | DATE | REVISION | BY |
| | | | |
| DESIGNED: | ATG/RER | SHEET | C-D25 |
| DRAWN: | BAW | CHECKED: | GEC |
| | | APPROVED: | TPB |
| | | | 116 of 167 |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-UT ILLS.dwg C-D26 9/3/2015 3:49 PM ZIS 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ① REMOVE EXIST INLET
- ② ADD OR REPLACE MANHOLE ADJUSTMENT RING (SEE ODOT DWG RD356)
- ③ ADJUST EXIST W VALVE BOX
- ⑥ RELOCATE W FIRE HYDRANT, (SEE SCHEDULE C FOR DETS)
- ⑪ NEW 8" W ABAN EXIST 6" W (SEE SCHEDULE C FOR DETS)
- ⑫ STA 'C'10+32.5, 5' RT = STA 'RA'10+03.7, 7.4' LT
INSTALL 1-48" SDMH (SDMH-2) OVER EXIST SD
INSTALL 12" SD PIPE - 24'
INSTALL 12" SD PIPE - 25'
(SEE PROFILE SHEET CD-21)
- ⑬ STA 'C'10+22.85, 27' RT = STA 'RA'9+98.6, 10.1' RT
INSTALL 1-TYPE D DITCH INLET, CAST-IN-PLACE (SDCB-7) W/ 12" SUMP
INSTALL 12" SD PIPE - 28'
GRADE AREA AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET CD-21)
(SEE ODOT DWG RD370)
- ⑭ STA 'S'19+70.8, 12.8' RT = STA 'RA'9+69
INSTALL 1-G-2 INLET, CAST-IN-PLACE (SDCB-6)
(SEE PROFILE SHEET CD-21)
- ⑮ STA 'C'10+40.67, 19' LT = STA 'RB'0+10.6, 1.1' RT
INSTALL 1-TYPE D DITCH INLET (SDCB-8) W/ 12" SUMP
GRADE AREA AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET CD-21)
- ⑯ STA 'C'10+52.20, 17.5' RT = STA 'RA'10+26.2
INSTALL 1-G-2 INLET, CAST-IN-PLACE (SDCB-9) W/ 12" SUMP
INSTALL 12" SD PIPE - 22'
(SEE PROFILE SHEET CD-21)
- ⑰ STA 'C'10+73.12, 18.5' RT = STA 'RA'10+48.4, 1.1' RT
INSTALL 1-TYPE D DITCH INLET, CAST-IN-PLACE (SDCB-10) W/ 12" SUMP
GRADE AREA AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET CD-21)

| | | | | | |
|---|--|--|--|--|---|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: STORMWATER AND UTILITIES PLAN - 3</p> | <p>SCALE: VERT: 1" = 5' HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | <p>NO. DATE</p> <p>DESIGNED: AHG/RER DRAWN: BAW CHECKED: GEC APPROVED: TPB</p> | <p>BY</p> <p>REVISION</p> <p>SHEET C-D26 117 of 167</p> |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-8010 FAX 503-225-9022</p> | | <p>DATE: SEPTEMBER 2015</p> | | <p>MSA PROJECT: 14-1586</p> | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-UT\ILS.dwg C-D27 9/3/2015 3:49 PM ZIS 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'

KEY NOTES:


- ③ ADJUST EXIST W VALVE BOX
- ④ ADJUST EXIST WM BOX
- ⑥ RELOCATE W FIRE HYDRANT, (SEE SCHEDULE C FOR DETS)
- ⑦ RELOCATE EXIST T PEDESTAL (BY OTHERS), COORD W/ CTL AS REQ'D
- ⑧ ADJUST EXIST T MH (BY OTHERS), COORD W/ CTL AS REQ'D
FURNISH CURB FRAME DOOR (BY OTHERS)
INSTALL CURB FRAME & DOOR (SEE DET 1, SHT C-41)
- ⑪ NEW 8" W
ABAN EXIST 6" W
(SEE SCHEDULE C FOR DETS)
- ⑫ NEW 24" W
ABAN EXIST 18" W
(SEE SCHEDULE C FOR DETS)



PLAN
SCALE: 1" = 20'

| | | |
|---|--|--|
| | NO. DATE REVISION | BY SHEET C-D27 118 of 167 |
| | DESIGNED: AIG/RER DRAWN: BAW CHECKED: GFC APPROVED: TPB | PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: STORMWATER AND UTILITIES PLAN - 4 |
| SCALE VERT: 1" = 5' HORIZ: 1" = 20' NOTICE IF THIS BAR DOES NOT MEASURE, THEN DRAWING IS NOT TO SCALE | MSA PROJECT: 14-1586 DATE: SEPTEMBER 2015 MSA PROJECT: 14-1586 DATE: SEPTEMBER 2015 | |
| | | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-UT\LS.dwg C-D28 9/3/2015 3:49 PM ZLS 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'


KEY NOTES:

- ③ ADJUST EXIST W VALVE BOX
- ④ ADJUST EXIST WM BOX
- ⑨ RELOCATE EXIST UTILITY POLE (BY OTHERS), COORD W/ PGE AS REQ'D
- ⑪ NEW 8' W
ABAN EXIST 6' W
(SEE SCHEDULE C FOR DETS)
- ⑫ NEW 24' W
ABAN EXIST 18' W
(SEE SCHEDULE C FOR DETS)
- ⑬ STA 'S28+02.75, 13.5' RT = STA 'RB'7+92.5
INSTALL 1-CG-3 INLET (SDCB-11) W/ OPTION 2 INLET TOP & 12" SUMP
(SEE PROFILE SHEET C-D22)
(SEE ODOT DWG RD371 & RD372)
- ⑭ STA 'S'28+04.12, 6' RT = STA 'RB'7+92, 6' LT
INSTALL 1-48" SDMH (SDMH-2)
INSTALL 12" SD PIPE - 16'
(SEE PROFILE SHEET C-D22)
- ⑮ STA 'S'28+84.82, 6.2' RT = STA 'RB'9+75.9, 6.5' LT
INSTALL 1-48" SDMH (SDMH-3)
INSTALL 12" SD PIPE - 82'
(SEE PROFILE SHEET C-D22)

| | | | | | |
|--|--|-----------------------------|-------------------------|--|---------------------------------------|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: STORMWATER AND UTILITIES PLAN - 5</p> | <p>DATE: SEPTEMBER 2015</p> | <p>PROJECT: 14-1586</p> | <p>DESIGNED: AHC/RER DRAWN: BAW CHECKED: GEC APPROVED: TPB</p> | <p>SHEET C-D28 119 of 167</p> |
|  | | | | | |
| <p>SCALE: VERT: 1" = 5' HORIZ: 1" = 20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | |
| <p>REVISION</p> | | | | | |

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 800
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-UT\ILS.dwg C-D29 9/3/2015 3:49 PM ZIS 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ① REMOVE EXIST INLET
- ③ ADJUST EXIST W VALVE BOX
- ④ ADJUST EXIST WM BOX
- ⑥ RELOCATE W FIRE HYDRANT (SEE SCHEDULE C FOR DETS)
- ⑦ RELOCATE EXIST T PEDESTAL (BY OTHERS), COORD W/ CTL AS REQ'D
- ⑧ ADJUST EXIST T MH (BY OTHERS), COORD W/ CTL AS REQ'D
FURNISH CURB FRAME DOOR (BY OTHERS)
INSTALL CURB FRAME & DOOR (SEE DET, SHT C-41)
- ⑨ RELOCATE EXIST UTILITY POLE (BY OTHERS), COORD W/ PGE AS REQ'D
- ⑪ NEW 8" W
ABAN EXIST W
(SEE SCHEDULE C FOR DETS)
- ⑫ NEW 24" W
ABAN EXIST 18" W
(SEE SCHEDULE C FOR DETS)
- ⑬ STA 'S'31+32.88, 6' RT = STA 'RA'11+23.9, 6.1' LT
INSTALL 1-48" SDMH (SDMH-4)
INSTALL 12" SD PIPE - 248'
INSTALL 12" SD PIPE - 8'
INSTALL 12" SD PIPE - 25'
(SEE PROFILE SHEET C-D23)
- ⑭ STA 'S'31+32.88, 13.5' RT = STA 'RA'11+23.9
INSTALL 1-CG-3 INLET (SDCB-12) W/ OPTION 2 INLET TOP & 12" SUMP
6" SUBSURFACE PERF DR PIPE - LENGTH AS REQ'D
(SEE RETAINING WALL DET, SHT C-D38)
(SEE PROFILE SHEET C-D23)
- ⑮ STA 'S'31+32.88, 19' LT
INSTALL 1-G-2 INLET (SDCB-11) W/ 12" SUMP
GRADE ACP AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET C-D23)
- ⑯ STA 'S'34+17.45, 6' RT = STA 'RA'14+08.8, 6.1' LT
INSTALL 1-48" SDMH (SDMH-5)
INSTALL 12" SD PIPE - 285'
INSTALL 12" SD PIPE - 22'
(SEE PROFILE SHEET C-D23)
- ⑰ STA 'S'34+17.45, 16' LT
INSTALL 1-G-2 INLET (SDCB-14) W/ 12" SUMP
GRADE ACP AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET C-D23)

| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Johnson, Suite 800 Portland, Oregon 97204 PHONE: 503-225-8000 FAX: 503-225-8022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: STORMWATER AND UTILITIES PLAN - 6</p> | <p>DATE: SEPTEMBER 2015</p> | <p>MSA PROJECT: 14-1586</p> | <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | <p>PROFESSIONAL SEAL REGISTERED PROFESSIONAL ENGINEER STATE OF OREGON NO. 7768 EDWARD J. EDWARDS RENEWED 12-31-16</p> | <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>NO.</th> <th>DATE</th> <th>REVISION</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table> <p>DESIGNED: AHG/RER DRAWN: BAW CHECKED: GEC APPROVED: TPB</p> <p>SHEET: C-D29 120 of 167</p> | NO. | DATE | REVISION | | | |
|---|--|--|-----------------------------|-----------------------------|--|---|---|-----|------|----------|--|--|--|
| NO. | DATE | REVISION | | | | | | | | | | | |
| | | | | | | | | | | | | | |

g:\pdx_projects\14\1586 -- bolton_reservoir_replacement\CAD\Sheets\SCHED_D\14-1586-0R-D-UT-ILS.dwg C-D30 9/3/2015 3:49 PM ZLS 20.0s (LMS Tech)




PLAN
SCALE: 1" = 20'

KEY NOTES:

- ① REMOVE EXIST INLET
- ③ ADJUST EXIST W VALVE BOX
- ⑫ NEW 24" W
ABAN EXIST 18" W
(SEE SCHEDULE C FOR DETS)
- ⑬ STA 'S'36+85.53, 15.5' RT = STA 'RB'16+77.7, 2.3' LT
INSTALL 1-48" SDMH (SDMH-6)
INSTALL 12" SD PIPE - 271'
INSTALL 12" SD PIPE - 9'
INSTALL 12" SD PIPE - 8'
INSTALL 12" SD PIPE - 40'
EXTEND EXIST 12" RCP SD PIPE W/ LIKE SIZE & MTL
CONST CONC CLOSURE COLLAR
(SEE PROFILE SHEET C-D23)
(SEE ODOT DWG RD306)
- ⑭ STA 'S'36+85.53, 23.6' RT
INSTALL 1-TYPE D DITCH INLET, CAST-IN-PLACE (SDCB-15) W/ 12" SUMP
GRADE AREA AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET C-D23)
- ⑮ STA 'S'36+61.39, 15.5' LT = STA 'LC'22+58.3
INSTALL 1-G-2 INLET, CAST-IN-PLACE (SDCB-16) W/ 12" SUMP
GRADE ACP AROUND INLET AS NEEDED TO DRAIN
(SEE PROFILE SHEET C-D23)

| | | | |
|---|--|---|--|
| MSA | Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-8010 FAX: 503-225-8022 | DATE: SEPTEMBER 2015 | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | SHEET TITLE: STORMWATER AND UTILITIES PLAN - 7 | |
| SCALE: VERT: 1"=5' HORIZ: 1"=20' | | NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | |
| | | REVISION: _____ NO. DATE _____ DESIGNED: AHC/RER DRAWN: BAW CHECKED: GEC APPROVED: TFB SHEET: C-D30 121 of 167 | |

SEE SHEET C-D30
MATCHLINE - STA S38+60




PLAN
SCALE: 1" = 20'

- KEY NOTES:**
- (18) MAINTAIN AND PROTECT EXIST INLET

MATCHLINE - STA S43+40
SEE SHEET C-D32

| | | | | | | |
|---|---|---|--------------------------|------------|--|-----------------------------------|
| <p>MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-255-9000 FAX 503-255-9022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: STORMWATER AND UTILITIES PLAN - 8</p> | <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE</p> | <p>NO. DATE REVISION</p> | <p>BY:</p> | <p>DESIGNED: AHG/RER DRAWN: BAW CHECKED: GEC APPROVED: TPB</p> | <p>SHEET C-D31 122 of 167</p> |
| | | | | | | |
| <p>DATE: SEPTEMBER 2015</p> | | | | | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED D\14-1586-OR-D-UTILS.dwg C-D32 9/3/2015 4:02 PM ZJS 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'

KEY NOTES:

- (18) MAINTAIN AND PROTECT EXIST INLET


| | | | |
|--|--|------------------------------------|---|
| <p>MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Johnson, Suite 400 Portland, Oregon 97204 PHONE: 503-225-4010 FAX: 503-225-4022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | | <p>NO. DATE REVISION</p> |
| | <p>SHEET TITLE: STORMWATER AND UTILITIES PLAN - 9</p> | | <p>DESIGNED: AHG/FRER DRAWN: BAW CHECKED: GEC APPROVED: TPB</p> |
| <p>DATE: SEPTEMBER 2015</p> | | <p>SHEET: C-D32 123 of 167</p> | |







VERT: 1" = 5'
HORIZ: 1" = 20'
SCALE

NOTICE
IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE

g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED D\14-1586-OR-D-TYPS.dwg C-D33 9/3/2015 9:38 AM RLF 20.0s (LMS Tech)



SKYLINE DRIVE
STA S10+00 TO STA S10+37
STA S10+37 TO STA S10+67 (TRANSITION SECTION)
 SCALE: NTS






SKYLINE DRIVE
STA S10+67 TO STA S10+90 (TRANSITION SECTION)
STA S10+90 TO STA S17+47
STA S17+47 TO STA S19+30 (TRANSITION SECTION)
 SCALE: NTS

- SHEET NOTES:**
- STANDARD CURB: SEE ODOT STANDARD DRAWING RD700, E=6".
 - SIDEWALKS: SEE ODOT STANDARD DRAWING RD720.
 - SIDEWALK CURB RAMPS: SEE ODOT STANDARD DRAWING RD755, RD756, RD757 AND RD759.
 - SIDE-SLOPES ARE SHOWN AS VERTICAL TO HORIZONTAL.
 - FOR SUPERELEVATED SECTIONS, SEE ODOT STANDARD DRAWING RD140.
 - EXISTING CROSS SLOPE OF THE ROADWAY TO BE EXTENDED FROM THE PROPOSED SAW CUT LINE TO THE PROPOSED GUTTER OR EDGE OF PAVEMENT PROFILE GRADE.


| | | | | | | | | | | | | |
|--|--|----------|--|-----|------|---------------|----------------|--------------|---------------|----------------------|-------|------------|
| BY | | REVISION | | NO. | DATE | DESIGNED: AHG | DRAWN: HCM/RLF | CHECKED: GEC | APPROVED: TPB | SHEET | C-D33 | 124 of 167 |
| | | | | | | | | | | | | |
| <p>VERT: AS SHOWN HORIZ: AS SHOWN</p> <p>NOTICE</p> <p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | | | | | | | | | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: TYPICAL ROAD SECTIONS - 1</p> | | | | | | | | | | | | |
| | | | | | | | | | | DATE: SEPTEMBER 2015 | | |

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\OR-D-TYPS.dwg C-D34 9/3/2015 9:38 AM RLF 20.0s (LMS Tech)




| | | | |
|---|----------|--|----------|
| BY | NO. | DATE | REVISION |
| DESIGNED: AHG | REVISION | | |
| DRAWN: HCM/RLF | NO. | | |
| CHECKED: GEC | DATE | | |
| APPROVED: TPB | REVISION | | |
| | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: TYPICAL ROAD SECTIONS - 2 | | | |
| Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Johnson, Suite 900 Portland, Oregon 97204 | | DATE: SEPTEMBER 2015 PHONE: 503-225-9010 FAX: 503-225-9022 | |
| MSA PROJECT: 14-1586 | | | |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\replacement\CAD\14-1586-OR-D-TYPES.dwg C-D35 9/3/2015 9:38 AM RLF 20.0s (LMS Tech)




SKYLINE DRIVE
STA S22+83 TO STA S23+86 (1)
 SCALE: NTS



STA S40+30 TO STA S40+70




STA S37+76 TO STA S40+30



SKYLINE DRIVE
STA S37+05 TO STA S40+70 (2)
 SCALE: NTS


| | |
|--|--|
| | |
| DESIGNED: AHG | CHECKED: GEC |
| DRAWN: HCM/RLF | APPROVED: TPB |
| SHEET: C-D35 126 of 167 | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: TYPICAL ROAD SECTIONS - 3 |
| MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9000 FAX 503-225-9022 | DATE: SEPTEMBER 2015 |

g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED D\14-1586-OR-D-TYPS.dwg C-D36 9/3/2015 9:38 AM RLF 20.0s (LMS Tech)




SKYLINE DRIVE
 STA S40+70 TO STA S42+05
 STA S42+05 TO STA S42+38 (TRANSITION SECTION)
 STA S42+38 TO STA S43+04 (TRANSITION SECTION)

SCALE: NTS



SKYLINE DRIVE
 STA S43+04 TO STA S44+40

SCALE: NTS




SKYLINE CIRCLE
 STA S0+28 TO STA S2+77

SCALE: NTS




| | | | | | |
|---|--|--|----------------------|-----------------------------|--|
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | SHEET TITLE: TYPICAL ROAD SECTIONS - 4 | MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmons, Suite 800 Portland, Oregon 97204 PHONE: 503-225-0010 FAX: 503-225-0022 | DATE: SEPTEMBER 2015 | REVISION NO. DATE BY | DESIGNED: ATG DRAWN: HCM/RLF CHECKED: GEC APPROVED: TPB |
| VERT: AS SHOWN HORIZ: AS SHOWN NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | REGISTERED PROFESSIONAL ENGINEER OREGON ANDREW HENRY JULY 23, 1998 LICENSE NO. 76447 RENEWS 8-30-17 | | | |
| SHEET C-D36 127 of 167 | | | | | |

g:\pdx_projects\4\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-TYPS.dwg C-D37 9/3/2015 9:38 AM RLF 20.0s (LMS Tech)





CLARK STREET
STA C10+00 TO STA C12+03 (1)
 SCALE: NTS



A STREET
STA A34+30 TO STA A37+84 (2)
 SCALE: NTS

| | | | | | |
|---|---|---|------------------------------|-----------------------------|--|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: TYPICAL ROAD SECTIONS - 5</p> | <p>DESIGNED: AHC DRAWN: HCM/RLF CHECKED: GEC APPROVED: TPB</p> | <p>NO. DATE REVISION</p> | <p>BY</p> | <p>SHEET C-D37 128 of 167</p> |
| <p>SCALE: VERT: AS SHOWN HORIZ: AS SHOWN</p> | | <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | | |
| <p>MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Phone: 503-225-8010 Fax: 503-225-8022 Portland, Oregon 97204</p> | | | | | |
| <p>MSA PROJECT: 14-1586</p> | | | | <p>DATE: SEPTEMBER 2015</p> | |



MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-0110
FAX: 503-225-0122

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
**CIVIL DETAILS - 1
RETAINING WALL**

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |

DESIGNED: AHG/RER
DRAWN: HCM
CHECKED: GFC
APPROVED: TFB


SHEET
C-D38
129 of 167

REGISTERED PROFESSIONAL
ROBERT EDWARD RYAN
REGISTERED PROFESSIONAL ENGINEER
NO. 71798
RENEWALS 12-31-16

SCALE: VERT: AS SHOWN
HORIZ: AS SHOWN


NOTICE
IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE

G:\PDX_Projects\14-1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED D\14-1586-OR-D-DETS.dwg C-D39 9/3/2015 10:02 AM DKT 20.0s (LMS Tech)




TYPICAL SIDEWALK LANDING PROFILE
SCALE: NTS


NOTE:
SIDEWALK LANDING LOCATED AT:
STA S 22+63, 12.5' RT = RB 2+73
STA S 27+02, 12.5' RT = RB 6+92
STA S 31+06, 12.5' RT = RB 10+97




TYPICAL SIDEWALK SECTION
SCALE: NTS



SIDEWALK TYPICAL LANDING SECTION
SCALE: NTS




MAINTENANCE PAD (FILL STATION)
SCALE: NTS



NOTE:
1. MATCH EXISTING CONCRETE DRIVEWAY OR EXTEND LIMITS 1-FOOT BEYOND RIGHT OF WAY.
2. ACP SHALL BE A LEVEL 2, 3/8" ACP MIXTURE (PG 64-22).

ASPHALT DRIVEWAY APPROACH
SCALE: NTS




NOTE:
1. ACP SHALL BE A LEVEL 2, 3/8" DENSE ACP MIXTURE (PG 64-22).

TYPICAL ASPHALT BERM
SCALE: NTS


| | | | |
|---|------|----------|-------------------------------------|
| NO. | DATE | REVISION | BY |
| DESIGNED: | AHG | HCM | |
| DRAWN: | HCM | GFC | |
| CHECKED: | GFC | TFB | |
| APPROVED: | TFB | | |
| | | | SHEET C-D39 130 of 167 |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | |
| SHEET TITLE: CIVIL DETAILS - 2 MISCELLANEOUS DETAILS | | | |
| MSA Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-9010 FAX 503-225-9622 | | | DATE: SEPTEMBER 2015 |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED D\14-1586-OR-D-DETS.dwg C-D40 9/3/2015 10:02 AM DKT 20.0s (LMS Tech)




- NOTES:**
1. SUBGRADE STABILIZATION AREAS TO BE COMPLETED AS DIRECTED BY THE ENGINEER.
 2. FOR PAVEMENT SECTION DEPTHS, SEE TYPICAL SECTIONS.

12" SUBGRADE STABILIZATION (1)
SCALE: NTS




- NOTES:**
1. CONSTRUCT BENCHES ON SLOPES STEEPER THAN 1V:5H TO PROVIDE POSITIVE BOND WITH EXISTING GROUND.
 2. BENCHING WORK IS INCIDENTAL TO EMBANKMENT CONSTRUCTION.
 3. FOR EMBANKMENTS WHICH TOE OUT GREATER THAN 5' ABOVE THE EXISTING TOE OF SLOPE, SEE SLIVER FILL DETAIL.

STANDARD EMBANKMENT CONSTRUCTION (2)
SCALE: NTS




- NOTES:**
1. CONSTRUCT BENCHES ON SLOPES STEEPER THAN 1V:5H TO PROVIDE POSITIVE BOND WITH EXISTING GROUND.
 2. BENCHING WORK IS INCIDENTAL TO EMBANKMENT CONSTRUCTION.
 3. FOR EMBANKMENTS WHICH TOE OUT AT A HEIGHT OF 5' OR LESS ABOVE THE EXISTING TOE OF SLOPE, SEE STANDARD EMBANKMENT DETAIL.

SLIVER FILL BENCHING (3)
SCALE: NTS





AC OVERLAY TRANSITION DETAIL (4)
SCALE: NTS



- NOTE:**
1. WHEN COLD PLANE REMOVAL PRODUCES A ROUNDED EDGE, A SAW CUT SHALL BE USED TO MANUFACTURE A PERPENDICULAR EDGE AS SHOWN. THE ENGINEER SHALL BE SOLE JUDGE CONCERNING THE USE OF THIS DETAIL.

ACP DETAIL AT BUTT JOINT (5)
SCALE: NTS




- NOTES:**
1. DO NOT EXCAVATE NON-ERODIBLE ROCK IN ORDER TO PLACE RIPRAP.

RIPRAP BASIN (6)
SCALE: NTS

| | | | | | | | |
|---|----------|-----|------|--|------------|--------------|---------------|
| BY | REVISION | NO. | DATE | DESIGNED: AHG | DRAWN: HCM | CHECKED: GEC | APPROVED: TPB |
| | | | | | | | |
| | | | | SHEET C-D40 131 of 167 | | | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | | | | | | |
| SHEET TITLE: CIVIL DETAILS - 3 MISCELLANEOUS DETAILS | | | | | | | |
| MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S.E. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-255-9100 FAX: 503-255-9022 | | | | DATE: SEPTEMBER 2015 MSA PROJECT: 14-1586 | | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\SCHED D\14-1586-OR-D-DETS.dwg C-D41 9/3/2015 10:02 AM DKT 20.0s (LMS Tech)




TYPICAL INSTALLATION
DOOR SHOWN 90° OPEN

TYPICAL INSTALLATION
DOOR SHOWN CLOSED

NOTES:

1. FRAME DESIGNED TO BE CAST IN CONCRETE.
2. DESIGNED FOR 300PSF, PEDESTRIAN RATED TRAFFIC ONLY.
3. FRAME AND COVER TO BE INSTALLED AS ONE UNIT (DO NOT DISASSEMBLE).
4. HOT-DIPPED GALVANIZED NON-SLIP FINISH.
5. CURB FRAME AND DOORS WILL BE FURNISHED BY UTILITY FACILITY OWNER. APPROVED CURB FRAME AND DOOR IS MODEL 4042, AS MANUFACTURED BY UTILITY VAULT.

CURB FRAME AND DOOR
SCALE: NTS



NOTES:









1. PERFORM PAVEMENT REPAIRS PRIOR TO ACP OVERLAY.
2. LOCATION OF AC PAVEMENT REPAIR ARE AS DIRECTED BY ENGINEER.
3. PERFORM AC PAVEMENT REPAIRS AT EXIST AC COLD PATCH LOCATIONS.
4. AREA OF AC PAVEMENT REPAIR ASSUMES A 7-FOOT GRINDER WIDTH. LENGTH SHALL BE AS DIRECTED BY ENGINEER.

AC PAVEMENT REPAIR DETAIL
SCALE: NTS



| | | | | | |
|---|--|---|-----------|--|---------------------------------------|
| <p>MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-225-0910 FAX 503-225-0922</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>NO. DATE REVISION</p> | <p>BY</p> | <p>DESIGNED: AHG DRAWN: HCM CHECKED: GEC APPROVED: TPB</p> | <p>SHEET C-D41 132 of 167</p> |
| <p>CIVIL DETAILS - 4 MISCELLANEOUS DETAILS</p> | | <p>VERT. AS SHOWN SCALE: AS SHOWN HORIZ. AS SHOWN</p> | | <p>NOTICE IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | |
| <p>DATE: SEPTEMBER 2015</p> | | | | | |

c:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-XSEC.dwg C-D42 9/3/2015 9:41 AM HCM 20.0s (LMS Tech)



| | | | |
|-----|------|----------|----|
| NO. | DATE | REVISION | BY |
| | | | |
| | | | |
| | | | |

DESIGNED: AHG/RER
 DRAWN: HCM
 CHECKED: GEC
 APPROVED: TFB

SHEET
C-D42
 133 of 167

SCALE: VERT: 1"=2'
 HORIZ: 1"=10'

NOTICE
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE







REVISIONS 12-31-16

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE:
**CIVIL DETAILS - 5
 CROSS SECTIONS**

121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE: 503-225-4010
 FAX: 503-225-4022

DATE: SEPTEMBER, 2015
 MSA PROJECT: 14-1586



| | | | |
|-----|------|----------|----|
| NO. | DATE | REVISION | BY |
| | | | |

DESIGNED: AHG/RER
 DRAWN: HCM
 CHECKED: GEC
 APPROVED: TPB

SHEET: C-D43
 134 of 167



SCALE: VERT: 1"=2'
 HORIZ: 1"=10'

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE






PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE: CIVIL DETAILS - 6
 CROSS SECTIONS

MSA Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE: 503-225-4010
 FAX: 503-225-4022

DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586

g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED_D\14-1586-OR-D-XSEC.dwg C-D44 9/3/2015 9:41 AM HCM 20.0s (LMS Tech)



| NO. | DATE | REVISION |
|-----|------|----------|
| | | |

DESIGNED: AHG/RER
 DRAWN: HCM
 CHECKED: GEC
 APPROVED: TPB



SCALE: VERT: 1"=2'
 HORIZ: 1"=10'





NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE: CIVIL DETAILS - 7
 CROSS SECTIONS

MSA Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE: 503-225-9010
 FAX: 503-225-9022


DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586



| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |

DESIGNED: AHG/RER
 DRAWN: HCM
 CHECKED: DECC
 APPROVED: TPB

BY: SHEET C-D45
 136 of 167



SCALE: VERT: 1"=2'
 HORIZ: 1"=10'







NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE: CIVIL DETAILS - 8
 CROSS SECTIONS

MSA Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE: 503-225-9010
 FAX: 503-225-9022

DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586



SCALE: VERT. 1"=2'
HORIZ. 1"=10'

NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE: CIVIL DETAILS - 9
CROSS SECTIONS







MSA Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022

DATE: SEPTEMBER 2015

| NO. | DATE | REVISION | BY |
|-----|------|----------|----|
| | | | |
| | | | |
| | | | |

DESIGNED: AHC/RER
DRAWN: HCM
CHECKED: GEC
APPROVED: TPB

SHEET: C-D46
137 of 167



SCALE: VERT: 1"=2'
HORIZ: 1"=10'

NOTICE
IF THIS BAR DOES NOT MEASURE THEN DRAWING IS NOT TO SCALE

| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |
| | | |

DESIGNED: AHG/RER
DRAWN: HCM
CHECKED: GEC
APPROVED: TPB





BY: _____
SHEET: C-D47
138 of 167

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
**CIVIL DETAILS - 10
CROSS SECTIONS**

MSA
Murray Smith & Associates, Inc.
Engineers/Planners
121 S.W. Salmon, Suite 900
Portland, Oregon 97204
PHONE: 503-225-9010
FAX: 503-225-9022


DATE: SEPTEMBER 2015
MSA PROJECT: 14-1586



| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |

DESIGNED: AHG/RER
 DRAWN: HCM
 CHECKED: GEC
 APPROVED: TPB

BY: _____
 SHEET: C-D48
 139 of 167



SCALE: VERT: 1"=2'
 HORIZ: 1"=10'

NOTICE
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE:
**CIVIL DETAILS - 11
 CROSS SECTIONS**

MSA Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE: 503-225-4010
 FAX: 503-225-4022


DATE: SEPTEMBER 2015

c:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED_D\14-1586-OR-D-TRAFFIC.dwg TC-DI 9/3/2015 9:42 AM RLF 20.0s (LMS Tech)




- NOTES:**
1. TO BE ACCOMPANIED BY OREGON DEPARTMENT OF TRANSPORTATION (ODOT)/AMERICAN PUBLIC WORKS ASSOCIATION (APWA) STANDARD DRAWINGS TM800, TM810, TM820, TM821, TM840, TM841, TM850.
 2. SUBMIT TRAFFIC CONTROL PLAN FOR APPROVAL PRIOR TO CONSTRUCTION.
 3. FOR STAGE 1 - WATER MAIN REPLACEMENT, SEE ODOT/APWA STANDARD DRAWINGS AND SCHEDULE C SHEETS. MAINTAIN A MINIMUM OF ONE-WAY FLAGGED TRAFFIC UNLESS OTHERWISE APPROVED BY THE CITY.
 4. FOR WORK AREAS OUTSIDE OF THE ROADWAY WIDENING AREA, USE ODOT AND APWA STANDARD DRAWINGS TO COMPLETE THE WORK.
 5. WEEKS OF FULL ROADWAY CLOSURE BETWEEN CLARK ST TO A ST WILL BE PERMITTED IF REQUESTED FROM JUNE 13, 2016 TO AUGUST 12, 2016.
 6. REMOVE EXISTING STRIPING AS NECESSARY AND INSTALL TEMPORARY STRIPING FOR STAGED CONSTRUCTION.
 7. FINAL ACP WEARING COURSE LIFT SHALL BE PAVED AFTER ALL WATER MAIN AND ROAD WIDENING IMPROVEMENTS HAVE BEEN MADE. USE ODOT/APWA STANDARD DRAWINGS TO COMPLETE FINAL LIFT PAVING WORK.


PLAN
SCALE: 1"=150'




STAGE 2 - WIDENING RIGHT:
FIRWOOD DR - CLARK ST
SCALE: NTS



STAGE 3 - WIDENING LEFT:
FIRWOOD DR - CLARK ST
SCALE: NTS



STAGE 4 - WIDENING LEFT:
CLARK ST - A ST
SCALE: NTS








STAGE 5 - WIDENING RIGHT:
CLARK ST - A ST
SCALE: NTS











| | | | | |
|--|---------------|---|----------|-------------------------------------|
| | DESIGNED: AHG | PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 SHEET TITLE: TRAFFIC CONTROL - STAGING PLAN | BY | SHEET TC-DI 140 of 167 |
| | DRAWN: HCM | | NO. DATE | |
| | CHECKED: GEC | | REVISION | |
| SCALE: VERT: AS SHOWN HORIZ: AS SHOWN | | NOTICE: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE | | |
| | | DATE: SEPTEMBER 2015 MSA PROJECT: 14-1586 | | |

G:\PDX_Projects\14\1586 - Bolton Reservoir Replacement\CAD\Sheets\14-1586-OR-D-TC.dwg TC-D2 9/3/2015 9:42 AM RLF 20.0s (LMS Tech)

LEGEND


-  STREET WIDENING & REHABILITATION
-  DETOUR ROUTE: EASTBOUND SKYLINE DRIVE
-  DETOUR ROUTE: WESTBOUND SKYLINE DRIVE
-  TEMPORARY TRAFFIC CONTROL SIGN
-  TEMPORARY TYPE 3 BARRICADE

SIGN LEGEND

- 1  **SKYLINE DR CLOSED
CLARK ST TO WEST A ST
XXX TO XXX**
- 2  **DETOUR**
M4-9L
30"x24"
- 3  **DETOUR**
M4-9R
30"x24"
- 4  **DETOUR**
M3
30"x36"
- 5  **ROAD
CLOSED
AHEAD**
W20-3
36"x36"
- 6  **ROAD CLOSED
TO
THRU TRAFFIC**
R11-4
60"x30"
- 7  **ROAD
CLOSED**
R11-2
60"x30"
- 8  **SKYLINE DRIVE**
- 9  **DETOUR
AHEAD**
W20-2
36"x36"
- 10  **R3-1**
24"x24"

NOTES:


1. LOCAL ACCESS SHALL BE PROVIDED TO RESIDENTS AT ALL TIMES.
2. DETOUR REQUIRED FOR ALL THROUGH TRAFFIC.
3. SEE SPECIFICATIONS FOR TRAFFIC CONTROL AND WORK HOUR REQUIREMENTS.




PLAN
SCALE: 1"=400'

| | | | | |
|---|--|---|---|---|
| <p>MSA Murray, Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-255-9010 FAX: 503-255-9022</p> | <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>DATE: SEPTEMBER 2015</p> | <p>SHEET TITLE: TRAFFIC CONTROL - DETOUR & ROAD CLOSURE PLAN</p> | <p>BY: _____ NO. _____ DATE _____ DESIGNED: JHF/AHG DRAWN: DAK CHECKED: GEC APPROVED: TPB</p> |
| <p>SCALE: VERT: AS SHOWN HORIZ: AS SHOWN</p> <p>NOTICE IF THIS BAR DOES NOT MEASURE, THE DRAWING IS NOT TO SCALE</p> | | <p>REGISTERED PROFESSIONAL ENGINEER OR OREGON NO. 12345 JUNE 2, 2010 AND NEW HENRY RENEWS 6-30-17</p> | | |
| <p>SHEET TC-D2 141 of 167</p> | | | | |

g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED.D\14-1586-0R-D-STR\IP_INC.dwg S-D1 9/3/2015 9:53 AM RLF 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'



PLAN
SCALE: 1" = 20'

SHEET NOTES:

1. ALL LONGITUDINAL CENTERLINE PERMANENT PAVEMENT MARKINGS SHALL BE METHOD "A" THERMOPLASTIC, EXTRUDED, SURFACE, PROFILED.
2. ALL LONGITUDINAL FOG LINE AND BIKE LANE LINE PERMANENT PAVEMENT MARKINGS SHALL BE METHOD "A" SURFACE, THERMOPLASTIC, NON-PROFILED.
3. ALL TRANSVERSE PAVEMENT MARKINGS AND LEGENDS SHALL BE METHOD "B-HS", PREFORMED, FUSED THERMOPLASTIC HIGH SKID FILM.
4. MATCH POINTS TO EXISTING STRIPING CALLOUTS ARE APPROXIMATE AND SHALL BE FIELD VERIFIED.
5. REMOVE ALL SIGNS SHOWN. CITY OF WEST LINN PUBLIC WORKS (COWL) WILL INSTALL ALL GROUND MOUNTED SIGNS. RETURN SIGNS TO CITY OF WEST LINN (JEFF RANDAL, 503-880-9194).
6. SIGN LOCATIONS ARE APPROXIMATE. CITY OF WEST LINN TO FIELD VERIFY LOCATIONS PRIOR TO INSTALLATION.

STRIPING KEY NOTES:

- (W) INSTALL 4" WHITE LINE
- (W-2) INSTALL 8" WHITE LINE
- (ND) INSTALL NARROW DOUBLE NO-PASS 4" YELLOW LINES
- (BS) INSTALL BIKE LANE STENCIL
- (S) INSTALL STOP BAR
- (CW-SC) INSTALL STAGGERED CONTINENTAL CROSSWALK
- (D) DOUBLE NO-PASS WITH TWO 4" YELLOW LINES
- (WD) INSTALL 4" WHITE DOTTED LINE
- (WD-2) INSTALL 8" WHITE DOTTED LINE
- (TS) INSTALL TRANSVERSE SHOULDER BARS (MODIFIED - 2' SPACING)
- (LSA) INSTALL LEFT TURN STRAIGHT ARROW
- (SLM) INSTALL SHARED LANE MARKING (SEE DET, SHT S-D6)
- (RA) INSTALL RIGHT TURN ARROW
- (EX/N) MAINTAIN AND PROTECT EXIST 'N' PAVEMENT MARKING
- (RX/N) REMOVE EXIST 'N' PAVEMENT MARKING

TO BE ACCOMPANIED BY ODOT STD DWGS: TM500, TM501, TM503, TM520, TM521, TM530, TM560, TM561

| | |
|-----------|-------------|
| BY | |
| REVISION | |
| NO. | DATE |
| DESIGNED: | AHG/RRR/ANB |
| DRAWN: | HCM/RLF |
| CHECKED: | GEC |
| APPROVED: | TPB |
| SHEET | S-D1 |
| | 142 of 167 |

REGISTERED PROFESSIONAL ENGINEER
 OREGON
 ANDREW HENRY
 LICENSE NO. 1100
 RENEWS 8-30-17

SCALE: VERT: 1"=5'
 HORIZ: 1"=20'

NOTICE
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE


PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE:
SIGNING AND STRIPING PLAN - 1

MSA
 Murray Smith & Associates, Inc.
 Engineers/Planners
 121 S.W. Salmon, Suite 900
 Portland, Oregon 97204
 PHONE 503-225-9010
 FAX 503-225-9022

DATE: SEPTEMBER 2015
 MSA PROJECT: 14-1586


g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED.D\14-1586-OR-D-STRIP.LNG.dwg S-D2 9/3/2015 9:53 AM RLF 20.0s (LMS Tech)



- STRIPING KEY NOTES:**
- (W) INSTALL 4" WHITE LINE
 - (W-2) INSTALL 8" WHITE LINE
 - (ND) INSTALL NARROW DOUBLE NO-PASS 4" YELLOW LINES
 - (BS) INSTALL BIKE LANE STENCIL
 - (S) INSTALL STOP BAR
 - (CW-SC) INSTALL STAGGERED CONTINENTAL CROSSWALK
 - (D) DOUBLE NO-PASS WITH TWO 4" YELLOW LINES
- EX MAINTAIN AND PROTECT EXIST 'N' PAVEMENT MARKING
 RX REMOVE EXIST 'N' PAVEMENT MARKING

| | | |
|--|-----------|--|
| <p>NO. DATE</p> <p>REVISION</p> | <p>BY</p> | <p>SHEET</p> <p>S-D2</p> <p>143 of 167</p> |
| | | |
| <p>DESIGNED: AHG/RER/ANB DRAWN: FCM/RLF CHECKED: GEC APPROVED: TPB</p> | | |
| <p>REVISIONS 6-30-17</p> | | |
| <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE</p> <p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | |
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> <p>SHEET TITLE: SIGNING AND STRIPING PLAN - 2</p> | | |
| | | <p>DATE: SEPTEMBER 2015</p> |
| | | <p>MSA PROJECT: 14-1586</p> |


g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED\14-1586-OR-D-STRIP\INC.dwg S-D3 9/3/2015 9:53 AM RLF 20.0s (LMS Tech)




- STRIPING KEY NOTES:**
- (W) INSTALL 4" WHITE LINE
 - (W-2) INSTALL 8" WHITE LINE
 - (ND) INSTALL NARROW DOUBLE NO-PASS 4" YELLOW LINES
 - (BS) INSTALL BIKE LANE STENCIL
 - (S) INSTALL STOP BAR
 - (CW-SC) INSTALL STAGGERED CONTINENTAL CROSSWALK
 - (D) DOUBLE NO-PASS WITH TWO 4" YELLOW LINES
 - EX/N MAINTAIN AND PROTECT EXIST 'N' PAVEMENT MARKING
 - RX/N REMOVE EXIST 'N' PAVEMENT MARKING

| | | | | | |
|--|--|-----------------------------|--|--|-----------------------------------|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: SIGNING AND STRIPING PLAN - 3</p> | <p>DATE: SEPTEMBER 2015</p> | <p>DESIGNED: AHG/RER/ANB DRAWN: HCM/RLF CHECKED: GEC APPROVED: TPB</p> | <p>BY: _____ NO. DATE: _____ REVISION: _____</p> | <p>SHEET: S-D3 144 of 167</p> |
| <p>SCALE: VERT: 1"=5' HORIZ: 1"=20'</p> <p>NOTICE: IF THIS BAR DOES NOT MEASURE, THEN DRAWING IS NOT TO SCALE.</p> | | | | | |
| <p>Murray Smith & Associates, Inc. Engineers/Planners 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE 503-255-9010 FAX 503-255-9022</p> | | | | | |
| <p>MSA</p> | | | | | |

q:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED D\14-1586-OR-D-STRIP.ING.dwg S-D4 9/3/2015 9:53 AM RLF 20.0s (LMS Tech)



PLAN
SCALE: 1" = 20'




PLAN
SCALE: 1" = 20'

STRIPING KEY NOTES:

- (W) INSTALL 4" WHITE LINE
- (ND) INSTALL DOUBLE NO-PASS 4" YELLOW LINES


| | | | | | |
|--|--|--|------------------|-----------------------------|-------------------|
| <p>PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06</p> | <p>SHEET TITLE: SIGNING AND STRIPING PLAN - 4</p> | <p>DATE: SEPTEMBER 2015</p> | <p>BY: _____</p> | <p>REVISION</p> | <p>NO. DATE</p> |
| | | <p>DESIGNED: AHG/RER/ANB DRAWN: HCM/RLF CHECKED: GEC APPROVED: TPB</p> | | <p>SHEET S-D4</p> | <p>145 of 167</p> |
| | | <p>121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022</p> | | <p>MSA PROJECT: 14-1586</p> | |

g:\pdx_projects\14\1586 - bolton_reservoir_replacement\CAD\Sheets\SCHED D\14-1586-OR-D-STRIPING.dwg S-D5 9/3/2015 9:53 AM RLF 20.0s (LWS Tech)



PLAN
SCALE: 1" = 20'


- STRIPING KEY NOTES:
- (W) INSTALL 4" WHITE LINE
 - (ND) INSTALL NARROW DOUBLE NO-PASS 4" YELLOW LINES
 - (D) INSTALL DOUBLE NO-PASS 4" YELLOW LINES
 - (CW-SC) INSTALL STANDARD CROSSWALK
 - (SCH) INSTALL 'SCHOOL' LEGEND
 - (XING) INSTALL 'XING' LEGEND



PLAN
SCALE: 1" = 20'

| | | |
|--|-----------------------|----------------------|
| | DESIGNED: AHG/RER/ANB | SHEET |
| | DRAWN: HCM/RLF | S-D5 |
| | CHECKED: GEC | 146 of 167 |
| | APPROVED: TPB | |
| NO. DATE | REVISION | |
| PROJECT NAME: CITY OF WEST LINN, OREGON BOLTON RESERVOIR REPLACEMENT PROJECT NO. PW 14-06 | | |
| SHEET TITLE: SIGNING AND STRIPING PLAN - 5 | | |
| | | DATE: SEPTEMBER 2015 |
| 121 S.W. Salmon, Suite 900 Portland, Oregon 97204 PHONE: 503-225-9010 FAX: 503-225-9022 | | MSA PROJECT: 14-1586 |


g:\pdx_projects\14\1586 - bolton reservoir replacement\CAD\Sheets\SCHED D\14-1586-OR-D-STRIPING.dwg S-D6 9/3/2015 9:53 AM RLF 20.0s (LMS Tech)





PLAN
SCALE: 1" = 20'

STRIPING KEY NOTES:

- (W) INSTALL 4" WHITE LINE
- (W-2) INSTALL 8" WHITE LINE
- (D) INSTALL DOUBLE NO-PASS 4" YELLOW LINE
- (BS) INSTALL BIKE LANE STENCIL
- (SB) INSTALL STOP BAR
- (CW) INSTALL STANDARD CROSSWALK
- (ST) INSTALL 'STOP' MARKING PER MUTCD
- (AH) INSTALL 'AHEAD' MARKING PER MUTCD
- (TS) INSTALL TRANSVERSE SHOULDER BARS (MODIFIED 2' SPACING)
- (EX N) MAINTAIN AND PROTECT EXIST 'N' PAVEMENT MARKING
- (RX N) REMOVE EXIST 'N' PAVEMENT MARKING



| | | | |
|--|-----------|---|--|
| <p>NO. DATE</p> <p>REVISION</p> | <p>BY</p> | <p>DESIGNED: AHG/RER/ANB</p> <p>DRAWN: HCM/RLF</p> <p>CHECKED: GEC</p> <p>APPROVED: TPB</p> | <p>SHEET</p> <p>S-D6</p> <p>147 of 167</p> |
| | | | |
| <p>SCALE: VERT: 1"=5'</p> <p>HORIZ: 1"=20'</p> <p>NOTICE</p> <p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE</p> | | <p>PROJECT NAME: CITY OF WEST LINN, OREGON</p> <p>BOLTON RESERVOIR REPLACEMENT</p> <p>PROJECT NO. PW 14-06</p> <p>SHEET TITLE: SIGNING AND STRIPING PLAN - 6</p> | |
| <p>Murray Smith & Associates, Inc.</p> <p>Engineers/Planners</p> <p>121 S.W. Salmon, Suite 900</p> <p>Portland, Oregon 97204</p> <p>PHONE 503-225-9010</p> <p>FAX 503-225-9022</p> | | <p>DATE: SEPTEMBER 2015</p> <p>MSA PROJECT: 14-1586</p> | |



WALKER
111 SW OAK, SUITE 2
PORTLAND, OR 97204
503-228-3122



Murray, Smith & Associates, Inc.
Engineers/Planners
121 S.E. Adams, Suite 400
Portland, Oregon 97204
PHONE 503-225-4610
FAX 503-225-4622

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-1

| | | | |
|--|----------|----------|------------|
| REGISTERED 588 <i>Chelsea M. McCann</i> LANDSCAPE ARCHITECT OREGON | NO. DATE | REVISION | BY |
| DESIGNED: JP/KD DRAWN: KD CHECKED: JP/KD APPROVED: CM | | | |
| | | | SHEET L-D1 |
| | | | 148 of 167 |

MSA PROJECT: 14-158A.060L DATE: SEPTEMBER 2015



WALKER MACY
111 SW OAK, SUITE 200
PORTLAND, OR 97204
503-228-3122

MSA
Murray, Smith & Associates, Inc.
Engineers/Planners
10 E. Adams, Suite 400 PHONE 503-225-9110
Portland, Oregon 97204 FAX 503-225-9922


MSA PROJECT: 14-15568.0501 DATE: SEPTEMBER 2015

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06
SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-2


SCALE VERT: AS SHOWN
HORIZ: AS SHOWN
NOTICE
IF THIS BAR DOES NOT APPEAR THEN DRAWING IS NOT TO SCALE



| NO. | DATE | REVISION | BY |
|-----------|---------|----------|------------|
| DESIGNED: | JP / KD | | |
| DRAWN: | KD | | |
| CHECKED: | JP / KD | | |
| APPROVED: | CM | | |
| SHEET | | | L-D2 |
| | | | 149 of 167 |



ROUGH SEED AREA, TYP.
SEE SHEET L-A1 FOR
ADDITIONAL INFORMATION



SCALE: 1" = 20'-0"



| NO. | DATE | REVISION | BY |
|-----------|-------|----------|----|
| | | | |
| DESIGNED: | JP/KD | | |
| DRAWN: | KD | | |
| CHECKED: | JP/KD | | |
| APPROVED: | CM | | |



VERT: AS SHOWN
HORIZ: AS SHOWN


NOTICE
IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-3




111 SW OAK SUITE 2
PORTLAND, OR 97204
503-228-3122



121 S.E. Madison, Suite 400
Portland, Oregon 97204
PHONE 503-225-4610
FAX 503-225-4622

MSA PROJECT: 14-158A.060L DATE: SEPTEMBER 2015

SHEET L-D3
150 of 167



SCALE: VERT: AS SHOWN
HORIZ: AS SHOWN

NOTICE
IF THIS BAG DOES
NOT OPEN,
THEN DRAWING IS
NOT TO SCALE

PROJECT NAME: CITY OF WEST LINN, OREGON
BOLTON RESERVOIR REPLACEMENT
PROJECT NO. PW 14-06

SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-4



MSA
Murray, Smith & Associates, Inc.
Engineers/Planners
10 E. Main, Suite 400 PHONE 503-225-8110
Portland, Oregon 97204 FAX 503-225-8922

WALKER | MACY
111 SW OAK, SUITE 204
PORTLAND, OR 97204
503-228-3122

MSA PROJECT: 14-1566.0601

DATE: SEPTEMBER 2015

| NO. | DATE | REVISION | BY |
|-----------|--------|----------|------------|
| DESIGNED: | JP /KD | | |
| DRAWN: | KD | | |
| CHECKED: | JP /KD | | |
| APPROVED: | CM | | |
| | | | SHEET |
| | | | L-D4 |
| | | | 151 of 167 |



WALKER
 111 SW OAK SUITE 2
 PORTLAND, OR 97204
 503-228-3122

Murray, Smith & Associates, Inc.
Engineers/Planners
 111 S.E. Adams, Suite 400
 Portland, Oregon 97204
 PHONE 503-225-4610 FAX 503-225-4622

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE:
 SKYLINE DRIVE, LANDSCAPE PLAN-5



SCALE: VERT: AS SHOWN
 HORIZ: AS SHOWN

NOTICE:
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE

REGISTERED
 588
Chelsea M. McCann
 Chelsea M. McCann
 OREGON
 LANDSCAPE ARCHITECT

| NO. | DATE | REVISION | BY |
|-----------|-------|----------|--------------|
| DESIGNED: | JP/KD | | |
| DRAWN: | KD | | |
| CHECKED: | JP/KD | | |
| APPROVED: | CM | | |
| | | | SHEET |
| | | | L-D5 |
| | | | 152 of 167 |

MSA PROJECT: 14-158A.060L **DATE:** SEPTEMBER 2015



WALKER | MACV
 111 SW OAK, SUITE 204
 PORTLAND, OR 97204
 503-228-3122


MSA
Murray, Smith & Associates, Inc.
Engineers/Planners
 10 E. Adams, Suite 400 PHONE 503-225-9110
 Portland, Oregon 97204 FAX 503-225-9822

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06
 SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-6


SCALE: VERT: AS SHOWN
 HORIZ: AS SHOWN
 NOTICE
 IF THIS BAG DOES
 NOT OPEN,
 THEN DRAWING IS
 NOT TO SCALE

REGISTERED
 588
Chelsea M. McCann
 Chelsea M. McCann
 OREGON
 LANDSCAPE ARCHITECT

| NO. | DATE | REVISION | BY |
|-----------|---------|----------|------------|
| | | | |
| DESIGNED: | JP / KD | | |
| DRAWN: | KD | | |
| CHECKED: | JP / KD | | |
| APPROVED: | CM | | |
| | | | SHEET |
| | | | L-D6 |
| | | | 153 of 167 |



PLANT 200 LILIUM COLUMBIANUM (TIGER LILY) IN CLUSTERS ALONG BACK SIDE (AWAY FROM ROAD) OF DITCH LINE.



WALKER | MACV
 111 SW OAK, SUITE 204
 PORTLAND, OR 97204
 503-228-3122

MSA
Murray, Smith & Associates, Inc.
Engineers/Planners
 10 E. Adams, Suite 400 PHONE 503-225-9110
 Portland, Oregon 97204 FAX 503-225-9922

MSA PROJECT: 14-1566.0601 DATE: SEPTEMBER 2015

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-7



SCALE VERT: AS SHOWN
 HORIZ: AS SHOWN

NOTICE

IF THIS BAR DOES NOT PRINT, THEN DRAWING IS NOT TO SCALE.



| NO. | DATE | REVISION | BY |
|------------------|------|----------|------------|
| DESIGNED: JP /KD | | | |
| DRAWN: KD | | | |
| CHECKED: JP /KD | | | |
| APPROVED: CM | | | |
| | | | SHEET |
| | | | L-D7 |
| | | | 154 of 167 |



WALKER MACY
 111 SW OAK, SUITE 204
 PORTLAND, OR 97204
 503-228-3122



Murray, Smith & Associates, Inc.
Engineers/Planners
 10 E. Main, Ste. 400 PHONE 503-225-8110
 Portland, Oregon 97204 FAX 503-225-8922

MSA PROJECT: 14-15568.0601 DATE: SEPTEMBER 2015

PROJECT NAME: CITY OF WEST LINN, OREGON
 BOLTON RESERVOIR REPLACEMENT
 PROJECT NO. PW 14-06

SHEET TITLE:
SKYLINE DRIVE, LANDSCAPE PLAN-8

SCALE

VERT: AS SHOWN

HORIZ: AS SHOWN

NOTICE

IF THIS BAR DOES NOT EQUAL 1" THEN DRAWING IS NOT TO SCALE



NO. DATE REVISION

| NO. | DATE | REVISION |
|-----|------|----------|
| | | |
| | | |

DESIGNED: JP /KD
 DRAWN: KD
 CHECKED: JP /KD
 APPROVED: CM

BY

SHEET
 -D8
 1115 of 167